

PREFACE.

The Gazetteer of Ajmer-Merwara compiled by Mr. J. D. (now Sir James Digges) LaTouche in 1875, is the basis of the present work. The arrangement has been altered in accordance with Government's general scheme for the new District Gazetteers, and it has been brought up to date, but except where recent investigations have thrown new light on any subject, the matter, and in many cases even the wording of the original have been retained. I am indebted to Mr. R. C. Bramley for the use of material collected for his article on Ajmer-Merwara in the Imperial Gazetteer at present under issue, to Colonel Melvill for helful criticism and advice, and to many members of the District Staff for useful notes on various subjects. My clerk Munshi Kanahaya Lal has given much assistance throughout.

C. C. W.

Abu, 21st August 1904.

Chapter III.—Population.						D
						PAGE
Density	200	***	***	1-4		21
Towns and villages	***	•••	***	***	•••	79
Movements of population	•••	•••	***	•••	•••	22
Migration	•••	101	P1	•••	•••	77
Vital statistics	***	000	100	***	•••	"
Diseases	444	•••	•••	***	•••	23
Sex and civil condition	•••	•••	•••	***	***	**
Inheritance	***	•••		114	•••	25
Education	***	•••	•••	•••	•••	"
Language	•••	•••	•• '	***	•••	26
Castes, tribes and races :-	-					
(a) Brāhmans	4**	1 144	***	9.AL	14.0	26
(b) Vaishyās	***	,=4	•••	104		33
(c) Kāyasthās	104	•••	•••	•••		22
(d) Rājputs			•••		•••	"
(') Jāts			•••	•••		29
(f) Güjars	•••	***	•••	***		21
(h) Merwāra clans		***	•••		•••	
(i) Other tribes		••			•••	" 33
Religions	••	***	***		•••	34
Christian Missions	•••	•••		•••	•••	36
Occupation	100	***	•••	***		37
Food	***	411	***		•••	-•
Dress		•••	•••		•••	", 38
Dwellings	•••		•••		•••	39
Disposal of the dead		•••	•••	•••	***	
Games and Amusements	400		•••	800	•••	,,
Festivals	•••	•••	462		•••	" 40
Names and titles	•••			•••	•••	
2100000 0000	•••	111	•••	***	•••	41
	-					
I	PART II.	ECONOMI	C.			
	_					
CE	TAPTER IV	.—Agricult	ure.			
General conditions	***					40
Halaana		••	•••	•••	•••	43
Agricultural implements	•••	•••	•••	•••	•••	44
Agricultural population		***	***	***	•••	45
Sowing	B-84	•••	***	•••	•••	11
Manama	•••	•••	••	•••	•••	23
Principal crops		•••	•••	•••	•••	33
Rotation of crops	***	•••	•••	***	•••	46
Extension and decrease of	on Himskin	···	•••	***	•••	**
			4 4	***	094	47
Land Improvement and A	griouiturali	ists' Loans	Acts	•••	***	"

CHAPTER X.—Famines.						
	· · · · · ·					PAGE.
Earlier famines	•••	•••	•••	100	100	71
Famine of 1868-69	•••	•••	•••	•••	•••	"
Famine of 1890-92	•••	•••	•••	104	•••	72
Famine of 1898-1900	•••	•••	•••	•••	••	73
Famine of 1901-02	•••	•••	•••	•••	•••	75
Protective measures	•••	•••	•••	•••	•••	76
Langar-khāna of Dargāl	ı Khwāj	a Sāhib	•••	•••	•••	"
•.	***	-ADMINIST	ים איז זיים מיי			
1'AR	т 111.—	-WIMIN 191	.KAII V L.			
	Chaptei	XI.—Gore	rnment.			
General Administration	•••		•••	••		78
Sub Divisions			•••	***	•••	,,
Revenue Officers		•••	•••	•••	•••	79
	ik XII.	—Legirlation	n and Justi	ce.		
Legislation	•••	••	•••	•••	•••	81
Civil and Criminal Justi	ice	***	•••	•••	•••	99
Civil Justice	***	••	•••	•••	•	82
Criminal Justice	••	•••	•••	•••	•••	,, 83
Registration	•••	•••	•••	100		00
			_			
		n XIII.—F	inance.			
Financo in former times	•••	•••	•••	•••	•••	84
Currency	•••	-	•••	••	•••	85
Early Taxation	•••	•••	•••	•••	••	"
Спарти	: XIV	-Land Rerei	nve and Te	nurcs.		
Tenures	•••		•••	•••	••	88
Khālsa		••	•••	***	•••	"
Istimiār	•••	•••	•••	•••	••	90
Jāgir	• •	•••	•••	•••	•••	92
Bhūm	•••	•••	•••	•••	••	"
Tenures in Morwara	•••	••	•••	•••	•••	94
Non-proprietary cultiva		•••	••	•••		>5
Revenue in former times		••	•••	••	•••	,,,
Mr. Wilder's administra			***	••	•••	95
Re-adjustments between		nd 1841	••	••	•••	"
Colonel Dixon's Settlem		••	•••			09
Mr. LaTouche's Settlem			••	••	•••	102
Mr. Whiteway's Settler		••	••	•••	•••	104
Susponsions and Remiss	ions of	Kevenuc	••		***	106

CONTENTS.


Part L-DESCRIPTIVE.

			CHAPTER I	.—Physica	deputs.			
	Boundaries on	A At	. 7		•			Page
			1911119	***	4.2	**	***	1
	Origin of nam	U	***	***	***	••	***	33
	Divisions	***	***	*#*	***	***	***	53
	Hill system	***	***	***	***	. ***	•••	.55
	Configuration	ami wa	tersited	•••	***	***	•••	2
	Panisus	***	***	**	***	***		73
	River system	***	***	***	***	***	***	33
	Scenery	•••	* 4 4	***	***	***	***	3
	Geology	***	***	***	***	***	***	4
	Botany	***	275	23		***	4.0	5
	Wild animals	***	***	*1	•••	***		G
	Climate and se	asons	***	***	***	***		39
	Temperaturo	•••	***	***	***	***		33
	Rainfall		***	•••	***	***		33
	Storms, cyclon	es and e	an thquakes			*:*		8
			Q					•
٠.			CHAPTE	n II.—Hi	torg.			
(a)	Ajmer.—							
	Hindu period		***	915	224	4	***	9
	Delhi Sultāns		***	***	***	***	222	10
	Mughal Emper		423	223	223	***		11"
	Rahtors of Ma	ewar	***	113	242	*10	***	22
	Marātkās	220	***	***	412	***		12
	Cession to the	British	Governmen	t	***	460		23
	Mutiny of 185	7	400	***	242	444	***	£3
(6)	Mermira							
	Early History		***	***	***	***	***	13
	Treaties with U	Maipur	and Jodhyr	n	***	87 4		14
	Administration	s of Co	k. Hall and	Dixon	***	***	***	15
e)	Archaelegy							10
	Arrhai-din-ka J	Jhener		411		***		17
	Baradaris	~					•••	
	Dargāh		***	***		***	***	31
	Magazine Fort		t11 t11			205	***	37
	Tätägarh Fort		***	***	E 28.4	254	***	18
	Pushkar	***		W 8 2	***	274		53
	Other places	===	***	***	545		413	29

CHAPTER XXI. - Medical.

--

							PAGE.
Hospitals and	dispen	saries	***	•••	•••		133
Medical statis	ties	***	•••	•••	•••		,,
Finances	•••	•••	•••	•••	•••		"
D'seases	•••	•••	•••	•••	•••	•••	134
Lunatic Asylu	m	•••			•••		
Vaccination	•••	•••	•••	•••		• •	"
Sanitation	•••	***	:	•••	••		135
		-					
		CHAPTER X	XIIS	urveys.			
Trigonometric	ıl Surve	ey of 1847-48	***	•••	***		136
Topographical	Survey	of 1868-75	•••		•••		,,
Survey of 188:	1-85	•••	•••	***	•••	••	,,
Survey training	g of Pa	twāris	••	***			137
Forest Survey	•••	••	•••	•••			,,
Bibliography	•••	•••	•••	•••			138
Index	• •	••	•••	•••			i – vi



CHAPTER I.

PHYSICAL ASPECTS.

Ajmer-Merwāra is an isolated Province of British India in Rāj-putāna, lying between 25° 24′ and 26° 42′ North Latitude and 73° 45′ * East Longitude. The Province is composed of two districts (1) Ajmer and (2) Merwāra, and is entirely surrounded by Native States.

The Ajmer district is bounded on the north and west by Mārwār, on the south by Mewār, on the south-west by Merwāra and on the east by Jaipur and Kishangarh. Merwāra is bounded on the north and west by Mārwār and Ajmer, on the south and east by Mewār and on the north-east and to some extent on the

north by Ajmer.

The length of the Ajmer district is some 80 miles from north to south, while it is 50 miles in breadth. Merwara is a narrow strip about 70 miles long, and with a varying breadth of from 15 miles to 1 mile. They have a total area of 2,711 square miles, of which Ajmer has 2,070 and Merwara 641. The population according to the census of 1901 is 4,76,912 or 175.93 persons to the square mile.

The Sanskrit word Mern, a hill is a component part of the names of both districts. In Ajmer it is combined with the name of Rājā Aja, the traditional founder of the fort and city: in Merwāra it

expresses the physical features of the country only.

The boundaries are territorial: there are no natural divisions. The two tracts originally formed distinct districts, and each possesses a history of its own. The number of villages on the Government rent roll according to the last census is 740, of which 425 are in Ajmer, and 315 in Merwära. The Land Revenue in 1902-03 amounted to Rs. 2,63,845, Ajmer contributing Rs. 2,09,111 and Merwära Rs. 54,734. The gross revenue for the Division, including the District Funds, was Rs. 14,49,200.

Of the 2,711 square miles of area $kh\bar{a}lsa$ and $j\bar{a}g\bar{i}r$ villages occupy 1,399 square miles, the $istimr\bar{a}ri$ estates in Ajmer 1,272 square miles,

and towns 40 square miles.

The distinguishing feature of the country is the Aravalli range, the strong barrier which divides the plains of Mārwār from the high tableland of Mewār. The range, which commences at the "Ridge" at Delbi, comes into promitence near the town of Ajmer, where it appears in a parallel succession of hills. The highest point, on which is perched the fort of Tāragarh, rises immediately above the city of Ajmer to a height of 2,855 feet above the level of the sea,

Boundaries.

Dimensions.

Origin of name.

Divisions.

Hill system.

and between 1,300 and 1,400 feet above the valley at its base. The "Nāgpahār," or Serpent hill, 3 miles west of Ajmer city, attains a scarcely inferior elevation. About 10 miles from Ajmer the hills disappear for a short distance, but in the neighbourhood of Beāwar form a compact double range which approach each other at Jawāja, 14 miles further south, and finally meet at Kukra in the north of the Todgarh tahsīl, from which village a succession of hills and valleys extends to the furthest extremity of the Merwāra district. Thence the range gradually becomes bolder and more precipitous, till it finally terminates in the south-east corner of the Sirohi State, near Mount Abu.

Configuration and Watershed. The plateau on which the town of Ajmer stands marks the highest point in the plains of Hindustan; and from the hills, which hem it in, the country slopes away on every side. The range of hills between Ajmer and Nasīrābād marks the dividing watershed of the continent of India. The rain which falls on the southern or Nasīrābād side, finds its way by the Chambal into the Bay of Bengal; that which falls on the other side is discharged by the Luni into the gulf of Cutch. Further south the watershed is still more clearly marked, and is the high wall of rock which separates Mārwār from Merwāra. The portion of Ajmer east of the range, which connects Srinagar with Rājgarh, including the pargana of Rāmsar and the estates of the istimrārīdurs generally, is an open country with a slope to the east and broken only by gentle undulations. West of the Nāgpahār the pargana of Pushkar stands quite apart from the rest of the district, and is a sea of sand.

Passes.

In Merwāra there are no important mountains; the highest hills occur near Todgarh, where the peak of Goramji attains an elevation of 3,075 feet above the level of the sea. The average level of the valleys is about 1,800 fect. In the talist of Beāwar there are four well-known passes. The Barr Pass on the west is a portion of the Imperial road from Agra to Ahmadabād and is metalled throughout. On the eastern side are the Pakheria and Sheopura Ghāts, the first leading to Masuda and the second to Mewār. There is also the Sura Ghāta pass which leads to Mewār. In the Todgarh talist there are the Kachbali, Pipli Undabāri, Sarupa Ghāta and Dewair passes leading from Merwāra into Mārwār. There are no passes deserving of the name in Ajmer except where the road to Pushkar, six miles west of Ajmer city, traverses a dip in the Nāgpahār range.

River system.

Owing to their position on the watershed of the continent, the districts do not possess rivers of any importance. The principal stream is the Banās, which takes its rise in the Aravalli range, about 40 miles north-west of Udaipur, and enters the Ajmer District at the extreme south-east corner, not far from the cantonment of Deoli. During the rains this river is frequently in flood, and travellers from Kōtah and Deoli are ferried across at the village of Negria, in Jaipur territory, 5 miles from Deoli. Besides the Banās there are four streams, the Khāri Nadi, the Dai Nadi, the Sagarmati and the Sāraswati. All are mere rivulets in the hot weather, but become torrents in the rains: neither they nor the Banās are used for the transport of produce. The Khāri Nadi rises in the hills near the village of Birjāl in the Merwāra dis-

trict, and after forming the boundary between Mewar and Ajmer for a short distance, falls into the Banas at the northern extremity of the Sāwar pargana. The Dai Nadi, flowing from west to east across the Ajmer district, is arrested in the early part of its course by the Neārān embankment. Thence it flows by Sarwar, belonging to Kishangarh, and, leaving the district close to Baghera, eventually also empties itself into the Banās. The Sagarmati rises near the Bisla tank in Ajmer, and after flowing through and fertilizing the Ajmer valley, takes a sweep northwards by Bhaonta and Pisangan to Govindgarh. Here it meets with the Saraswati, which carries the drainage of the Pushkar valley, and the united stream from this point until it falls into the Rann of Cutch is designated the Luni, or salty river, and it is on this stream that Mārwār chiefly depends for what fertility it has. The affluents of these streams are many, and there are some independent rivulets running northwards into the Sambhar lake. None of them have obtained a name, as they are mere drainage channels running only in the rainy season.

In striking scenery Ajmer district is deficient, although Ajmer itself is an exception. The ancient city, with the frowning heights of Tāragarh as a background, makes an effective picture, even when the hot weather has stripped the hills of all their covering. But the general aspect of the country at that season is desolate and forbidding. A change comes with the burst of the monsoon, when the arid plain and rocky hills are transformed by a covering of verdure, which contrasts pleasantly with the blue of the sky. The sunset effects are at times very striking. The most beautiful scene of all is the Anasāgar embankment and lake on a night when the moon is at its full and the marble chatris of Shāh Jahān are mirrored in the waters.

Merwāra scenery with its hills has a certain rugged grandeur at all times. But when the autumn and spring harvests are standing in the valleys, some parts are remarkably pretty, and the effect is heightened by the glimpses of water in the numerous tanks and the fresh foliage on the hill side trees. The view from the top of the Dewair pass looking down is singularly beautiful, and also the view from the top of the pass which separates Barākhan from Todgarh. Comparing small things with great, an enthusiast has called the Todgarh district the "Alps of Rājputāna."

It is regrettable that there are few topes of trees to be met with either in Ajmer or Merwāra. Except on the embankment of Jawāja tank it is difficult to get shade for tents and animals. Even in the forests the trees are generally mean and scrubby in appearance, and round Ajmer the humble euphorbia supplies their place on the hill-sides. Only near wells or in the watered gardens of the towns do they attain any height or luxuriance of foliage.

Low cover is scanty, both on the slopes of the hills and in the valleys. After good rains the grass grows to a height of two or three feet, but it is soon cut and utilized as fodder.

In ordinary years during the cold weather any traveller through Ajmer-Merwāra will find the districts covered with lakes of all sizes.

Scenery.

With four exceptions all the water reservoirs are artificial, and most of them have been constructed since the establishment of British rule. Of these last the great majority owe their existence to the unaided and untiring energy of one man, who ruled Merwara from 1836 to 1842, and the united districts from 1842 to 1857, when he died at The name of Colonel Dixon will be remembered in Ajmer and Merwara for many generations. For years he worked steadily at this single object without help or sympathy, and without much encouragement; for until the works were completed they attracted but little attention, and the district was too remote to allow of the Government of the North-Western Provinces taking at first an intelligent interest in the work. With such help as his tahsildars and a few trained chaprasis could give, Colonel Dixon constructed these works, and it was only in 1853, when his tanks had been completed, that the appointment of an uncovenanted European Assistant was sanctioned. Nothing worthy of note was done after Colonel Dixon's death till the establishment of the Ajmer Irrigation Division of Public Works in the beginning of 1869. Most of the tanks thereafter constructed are the products of famine labour during the calamities which have since come upon the country.

Besides the artificial reservoirs there are four natural lakes which, in less dry countries, would hardly deserve mention. Of these are the sacred lake of Pushkar and the lake known as Old Pushkar, near the former. Both are depressions among sand-hills without any outlet, but exercise a considerable influence by percolation through the sand-hills on the low sandy bottoms in their vicinity. In Merwara there are two natural basins, that of Sargaon and that of Karantia, both near Beawar. A passage for the escape of the water of the former has been cut through the encircling sand-hills, and the bed is now regularly cultivated for the spring crop. That of Karantia lies among hills, and is of no use for irrigation. There are no jhils in the districts i.e., extensive swamps such as are met with in the United Provinces of Agra and Oudh, which in the cold weather teem with duck and snipe.

The geology of the province is that of the Aravalli range, which extends throughout it. The rocks consist of gneiss, biotite, horn blendic schists and limestone, mostly in the form of marble and quartzite, which is probably the Alwar quartzite. The whole are much disturbed, most frequently nearly vertical, and repeated several times in the section. It is the Alwar quartzite, the rock highest in the section within the range, broken, repeated and placed upon end that forms all the long narrow ridges, which rise to a considerable height above the general level of the range, and of which an example is the Tāragarh hill near Ajmer. The best sections of the range in the province are exposed in the Dewair and Pipli passes in Merwāra, ascending from the western plains. The rocks of the former consist of schists and bands of white marble, the actinolite schists occurring at the top. There is also a section of mica schists frequently felspathic and often including bands of limestone. The Pipli pass is similar but contains more frequent quartzite ridges. Granitic intrusions are common and

Geology.

increase in the direction of Todgarh. Towards Beāwar gneiss and granite predominate, hardly any other rocks being exposed. Quartzite in contact with a large pile of gneiss is the characteristic formation of the Chang and Sendra hills. Towards Ajmer granite alternates with limestone, dark mica schists, and gneiss being not much more than a quartzite containing some felspar. At Ajmer the section across the range differs from the others in the number and size of the ridges of quartzite which cross it. Tāragarh hill, formed of Alwar quartzite rises to a height of upwards of 1,300 feet above the level of the surrounding country, and the same quartzite is repeated in the ridge east of the Anasagar. East of Ajmer the Alwar quartzites are repeated five times in the section, the intervening low grounds being occupied by schists and limestone, in which intrusive granite is of frequent occurrence. North of Ajmer, the range becomes very broken, and near the Sambhar lake it consists almost entirely of the Alwar quartzites, repeated five or six times, forming high narrow parallel nearly vertical ridges a mile or so apart, the intervening ground being covered with blown sand. Under some of the ridges a small thickness of the schists is exposed, and at Makrāna on the western side of the range, the famous white marble quarries are situated. The hills are schistose for the most part, and in appearance often serrate, and are probably volcanic. The cultivated soil is a natural mixture of one-third stiff yellow loam and two-thirds sand, consisting of disintegrated mica schist and felspar. Pure silicious sand is rare.

Owing to its geographical position and limited rainfall the flora of Ajmer-Merwāra is not a rich one. Indigenous species are limited, and few of them are attractive in appearance. Several centuries of civilization have practically denuded the Ajmer hillsides of all timber. Even in Merwāra—" the impenetiable jungle" of 1819—only within the reserved areas are trees still found in any quantity. The district has no species peculiar to itself, every plant in it being found also either in the adjacent provinces, or in the dry regions of the Deccan and southern India.

As in other parts of India with a similar vegetation, the majority of the trees and shrubs flower during the hot season, while the herbaceous plants blossom chiefly in the rains. Many of the latter are annuals which wither and die at the approach of the cold weather. Among the larger trees which yield both fuel and building timber are the semul (bombax malabaricum), the khejra (prosopis spicifera), the kurr (sterculia urens), the two acacias (leucoplhwa and catechu), anogiesus latifolia and pendula, dichrostachys cinerca, lordia rothisi and the aonla (phyllanthus emblica). On the roadsides the babul (acacia arabica) nīm (melia indica) kurrus (pangamia glabra) and jal (salvadora persica) are commonly planted, as they thrive well and give good shade. The pīpal (ficus religiosa), the banyan (ficus bengalensis), the gular (ficus glomerata), the tamarind (tamarindus indica), and the mango (mangifera indica), are found usually in gardens or near villages throughout the district. The shrubby vegetation, which is everywhere more prominent than the arboreal, consists

largely of capers, jujubes, tamarisks and grewias. Of the capparideae, the gynandropsis pentaphylla is common in waste lands, as is also the small jujube (zizyphus nummularia). Tamarisks of several species abound in the watercourses, while the grewias pilosa and populifolia are found everywhere. The euphorbia nivalia occurs near Ajmer and in the Merwāra hills.

The herbaceous vegetation consists of leguminosae of the genera alysicarpus, desmodium, crotalaria, cassia, etc., of various widely distributed species of compositue and rubiaceae. During the rains a few convolvulaceae appear, and grasses and sedges are abundant. The only ferns ever seen are adiantum lunulatum and candatrum, nephrodium molle and actiniopterus rudiata. The latter is found only on walls, where it is associated with funaria hygrometrica, the only moss at all common in the region. In wells the maidenhair (adiantum capillus reneris) is occasionally met with.

Wild Ani-

There is little cover for large game. An occasional tiger is to be met with in the Merwara forests, while leopards and hyænas are found in the hills from Nagpahar to Dewair. Wolves are rare. are found in most of the istimrari estates. They are preserved by the Thakurs, as pig-shooting is a favourite amusement of Rajputs. A Tent Club has recently been revived at Nasirabad, but the pig love the shelter of the hills, and the country is broken and hard to ride. Black buck (untelope bezoartica), ravine deer (gazella bennettii) and nīlgāi (portus pietus) are met with in Ajmer. A few sāmbhar (rusa aristotelis) are to be found in the hills of both districts. Rewards are given for the destruction of wild animals—Rs. 7 for a tiger, Rs. 5 for a leopard, Rs. 3 for bears, hyanas or wolves; and 2 annas for snakes. The reward for snakes is increased to 6 annas during the two months immediately preceding the breeding season, i. e., May and June. Of small game the great Indian bustard is occasionally found in Ajmer, and florican is a visitor during the rains. Geese duck and snipe are found about the tanks in the cold weather, but good snipe ground is very limited. The small sand grouse is found in abundance; the large sand grouse is rare. Quail are moderately plentiful in the cold weather, and hares and grey partridge are common at all seasons.

Climate and Seasons. The climate is healthy. In summer it is dry and hot, in the winter cold and bracing, especially in December, January and February, when hoar frost not infrequently covers the ground.

Temperature.

During the 20 years ending in 1900, the maximum temperature recorded in the shade was 116.9° F. in June 1897, the minimum being 35° F. in December 1892. In 1902 the maximum recorded was 108° 5′ F. in May, and the minimum 36° 8′ F. in December.

Rainfall.

The rainfall is precarious and partial. The province is on the border of what may fairly be called the arid zone, and is the debateable land between the north-eastern and south-western monsoons, and beyond the full influence of either. The south-west monsoon sweeps up the Narbada valley from Bombay, and, crossing the table-land at Nimach, gives copious supplies to Mālwa, Jhālawār and Kōtah, and

the countries which lie in the course of the Chambal river. The clouds which strike Kathiawar and Cutch are deprived of a great deal of their moisture by the influence of the hills in those countries, and the greater part of the remainder is deposited on Abu and the higher slopes of the Aravalli range, leaving but little for Merwāra, where the hills are lower, and still less for Ajmer. It is only when this monsoon is in considerable force that Merwāra gets a plentiful supply from it, and only the heaviest storms get as far as Jodhpur, where the average rainfall does not exceed 13 or 14 inches, while beyond lie the Jaisalmer State, with an average fall of 6.7 inches, and the rainless land of Sind. The north-eastern monsoon sweeps up the valley of the Ganges from the Bay of Bengal and waters the northern part of Rājputāna, but hardly penetrates further west than the longitude of Ajmer. On the conflicting strength of these two

monsoons the rainfall of the province depends.

The prevailing wind during the rainy season is a south-westerly one, but there is little rain from this direction. The south-west monsoon is exhausted before it reaches even Merwara, and if this monsoon is in the ascendant, the weather may be cloudy and there may be little and partial showers, but no heavy rain. It is from the north-east that Ajmer, Beāwar and Todgarh obtain their heaviest rainfalls, though the south-western monsoon has naturally more effect at Todgarh than at Ajmer. The central portions of the province often receive heavy falls from the north-west, the north-east monsoon being apparently diverted from its course by the winds from the desert. Not only, however, is the rainfall most precarious and partial, varying much in total amount from year to year and from place to place, and falling with fury on one side of a hill, while the other side is perfectly dry, but it is most irregularly distributed over the rainy season, and most uncertain in the intensity of the tail. The last is a most important question with reference to the filling of the reservoirs. If the rain comes in light showers, even though it be on the whole an average fall, the soil will absorb it, the nallas will not run and the tanks will remain empty. If the fall is sudden and heavy, and at the same time general within the catchment area of a tank, the chances are that the embankment will be damaged. The best rainy season is one which includes a fall of 3 or 4 inches in the 24 hours in June, and a similar fall in September, with intermediate showers. Then the tanks fill and are replenished for the rabi harvest, and the kharif crop is not drowned with excess of moisture. These peculiarities may be illustrated from the history of the twenty years before 1899-1900. In 1881-82 the rainfall in Ajmer was 17.9 inches. The early rainfall was deficient and the kharif crops failed, but heavy showers in September filled the tanks and the irrigated rabi crops were good. In 1882-83 the monsoon began well, but the kharif crops were injured by excessive rainfall in September. This filled the tanks and gave a good irrigated rabi crop, but the burani or dry crop failed through want of light showers after September. The rainfall was 24 inches: much the same happened in 1884-85, when the rainfall was 23.9 inches in Ajmer and 28.5 in

Merwara. The heavy September rains filled the tanks but rained the maize and cotton crops sown as *kharif.* In 1835-86 the rains recorded were 193 inches. There was a good fall in July and August but hardly a drop in September. The tanks did not fill nor did the early crops ripen properly, so both klearly and rubi were comparative failures. In 1887-38, 22 inches fell in Ajmer and 208 in Merwara, but it came principally in June and July and in the form of constant drizzle, with a result to the crops similar to that in 1885-30. In 1889-59 only 187 inches were recorded in Ajmer and 209 in Merwam, but though slightly deficient in quantity is was well distributed. Heavy rain fell in July and September, with intermediate light showers : the

tanks filled and the crops were good.

In 1889-90 there was promise of excellent harvests, but although there was a total rainfall of 21-4 inches in Ajmer and 16% in Merwara, it ceased early in September and the out-turn was below the average in both crops. In 1890-91 the rain was very deficient, 1205 inches in Ajmer and 1950 in Merwara. It set in early but soon ceased The following year was one of famine. The rainfall was \$50 inches in Ajmer and 10·24 in Merwära. These two successive years of shortage produced a water as well as a crop famine. In 1892-93 the total rainfall was large, averaging 37% inches in both districts, but owing to its late commencement the kharif out-turn was only fair. In 1890-94 the rains were timely and well distributed and crops were good. In 1894-95 the rains, 25:33 inches in Ajmer and 28:51 in Merwara, were above the normal but were badly distributed. Want of heavy showers in September left the tanks half empty, and the consequent irrigation suffered. In 1896-97 heavy showers fell in September and filled the tanks, but there was no rain later, and the dry crops were a failure. In 1897-98 the rain was over the average and well distributed. In 1898-99 only 1405 inches fell in Ajmer and 1006 in Merwara. The rain began early but stopped entirely by the end of July. The kharif suffered severely and, as the tanks did not fill, the rubi cultivated area was insignificant. It was followed by the famine year of 1899-00, when 836 inches fell in Ajmer and 492 in Merwara. The greater part came in June; the kharif crops failed to reach maturity and, as the rains ceased entirely after a few showers in September, the rubi crops were lost also.

The average annual fall during the 20 years was 19 inches in the Ajmer district and 20 inches in Merwara. The maximum raintall during this period was 37 inches in each district in 1892-93 and the minimum 8 inches in Ajmer and 5 inches in Merwara in 1899-1900, as already stated. The rainfall in 1900-01 was 28 inches in the Ajmer

district and 30 in Merwara.

There have been no cyclones or floods within Ajmer-Merwära Storms, Cy-clones, Earthduring the last three decades. On the 12th June 1897 slight quakes.

shocks of earthquake were felt at 4-45 P.M. in Ajmer. They came from west to east, and were felt horizontally about 5 or 6 times within the duration of 15 minutes. But for the fact of their rarity they

would be hardly worth mentioning.

CHAPTER II.

HISTORY.

(a.) Ajmer.

The early history of Ajmer is, as might be expected, legendary in its character, and commences with the rule of the Chauhāns, the last born of the Agnikulas, and the most valiant of the Rajput races. According to tradition, the Fort and City of Ajmer were founded by Rāja Aja, a descendant of Anhal, the first Chauhān, in the year 145 A.D. Aja at first attempted to build a fort on the Nägpahär, or Serpent Hill, and the site chosen by him is still pointed out. His evil genius, however, destroyed in the night the walls erected in the day, and Aja determined to build on the hill now known as Taragarh. Here be constructed a fort, which he called "Garh Bitle," and in the valley known as Indrakot he built a town, which he called after himself, and which has become famous as Ajmer. This Prince is generally known by the name of Ajaipal, which, Colonel Tod explains, was derived from the fact that he was a goat-herd "whose piety in supplying one of the saints of Pushkar with goats' milk procured him a territory." The name probably suggested the myth, and it is more reasonable to suppose that the appellation was given to him when, at the close of his life, he became a hermit, and ended his days at the gorge in the hills about ten miles from Ajmer, which is still venerated as the temple of Ajaipal.

It has been shown, however, by more recent research that Aja or Ajāya flourished about 1000 A.D., and that the foundation of Ajmer must be ascribed to this period. The Chauhāns came to Rājputāna from Ahichhatrapur on the Ganges about 750 A.D., and their first capital was Sāmbhar. Their possessions included the tract now known as Ajmer, but there was at that time no known city there. Ajāya's son Anā (or Arno) constructed the fine Anāsāgar embankment, on which the Emperor Shah Jahan subsequently erected a magnificent range of marble pavilions. An inscription discovered at Chitor by Pandit Gauri Shankar of Udaipur shows that Ana was alive in 1150 A.D. Vigraharāja III, otherwise known as Visaldeo, a son of Anā, was the most famous of the Chauhān dynasty of Ajmer. He conquered Delhi from the Tuars, and constructed the Bisal-Sagar Tank in his ancestral territory. The latest inscription under his reign is dated 1163. Prithvi Rāj, nephew of Visaldeo, was king of Delhi and Ajmer at the time of the invasion of Shahāb-ud-dīn Muhammad Ghorī. In 1191 he defeated the latter in a great battle and forced him to fly. But in 1193 Muhammad Ghori returned with a fresh army recruited in Afghānistān and Central Asia. The Rājput chiefs were weakened by feuds, and Prithvi Raj was defeated, taken prisoner, and murdered in cold blood. Muhammad Ghori shortly afterwards took Ajmer, massacred all the inhabitants who opposed him, and reserved the rest for slavery. After this expedition he made over the country to a

Hindu Period.

relation of Prithvi Rāj under an engagement for a heavy tribute. In the following year Muhammad Ghorī prosecuted his conquests by the destruction of the Rāhtor kingdom of Kanauj, an event of considerable importance in the history of Ajmer, in that it led to the emigration of the greater part of the Rāhtor clan from Kanauj to Mārwār.

The Delhi Sultans. gration of the greater part of the Rahtor clan from Kanauj to Marwar. The new Raja of Ajmer was soon reduced to perplexities by a pretender, and Kutab-ud-din Eibak, then Viceroy and afterwards the first of the slave dynasty at Delhi, marched to his relief. Hari Rāj the pretender was defeated, and Kutab-ud-din, having appointed a governor of his own faith to control the Raja, proceeded with his expedition to Gujarat. A year or two afterwards, however, the Raja, uniting with the Rahtors and Mers, attempted independence. Kutab-ud-din, marched from Delhi in the height of the hot season and shut up the Rāja in the fort. Here finding no means of escape, he ascended the funeral pyre as is related in the Tajul Maasir. Kutab-ud-din then marched against the confederated Rahtors and Mers, but was defeated and wounded, and obliged to retreat to Ajmer, where he was besieged by the confederate army. A strong reinforcement from Ghazni, however, caused the enemy to raise the siege, and Kutab-ud-din annexed the country to the kingdom of Delhi, and made over the charge of the fort of Taragarh to an officer of his own, Sayyid Husain, whose subsequent tragic fate has caused him to be enrolled in the list of martyrs, and whose shrine is still the most conspicuous object on the hill he was unable to defend. On the death of Kutab-ud-dīn in A.D. 1210, the Rähtors joined the Chauhans and made a night attack upon the fort. The garrison was taken unprepared, and massacred to a man. Their tombs, as well as those of Sayyid Husain and his celebrated horse, may still be seen on Taragarh in the enclosure, which bears the name of Ganj Shahīdān or treasury of martyrs.

Shams-ud-dīn Altamsh, the successor of Kutab-ud-dīn, restored the authority of the Kings of Delhi, and it was maintained till the disastrous invasion of Taimur. Rāna Kumbho of Mewār profited by the relaxation of all authority, which ensued upon the sack of Delhi and the extinction of the house of Tughlak, to take possession of Ajmer, but on his assassination the territory fell into the hands of the Kings of Mālwā, with whom the Rāna had been perpetually at variance, and for 15 years had waged war.

The Kings of Mālwā obtained possession in A.D. 1469, and held Ajmer till the death of Mahmud II in A.D. 1531, when the kingdom

of Mālwā was annexed to that of Gujarāt.

On the death of Mahmud II, Mal Deo Rahtor, who had recently succeeded to the throne of Marwar, took possession of Ajmer among other conquests. He improved the fortress of Taragarh, and commenced the construction of a lift to raise water to the fort from the "Nur Chashma" spring at the foot of the hill. The work still stands, as solid as on the day it was built, but the scheme was never completed. The Rahtors held Ajmer for 24 years, but the country was one of the earlier acquisitions of Akbar, and from 1561 A.D. to 1730, a period of 170 years, Ajmer was an integral part of the Mughal Empire.

Akbar included Ajmer in a sūbah or province, which gave its name to the whole of Rājputāna. The great importance of the fort and district of Ajmer as a point d'appui in the midst of Rājputāna was early recognized by the Muhammadan rulers. It commanded the routes from northern India to Gujarāt on the one side, and to Mālwā on the other. Ajmer itself was a centre of trade, with a wellnigh impregnable fort to protect it. The situation was strong, central, and picturesque, and was well watered as compared with the arid tracts around. The Mughal sovereigns, like their predecessors, were not slow to grasp the advantages of the place, and Ajmer became an

appanage of the royal residence.

Akbar had made a vow that, if a son were born to him and lived, he would go on foot from Agra to Ajmer, and offer thanks at the tomb of the saint Muin-ud-dīn Chishti, a holy man who came from Gor to India in 1143 A.D., and whose tomb, known as the Dargah Khwaja Sāhih, has been a place of Muhammadan pilgrimage for several centuries. Salīm, afterwards Jahāngīr, was born in A.D. 1570. years later Akbar built a fortified palace, the Dar-ul-Khair, just outside the city. Jahangir and Shah Jahan both spent a considerable portion of their time at Ajmer, and it was here that the former received Sir Thomas Roe, the Ambassador from King James I, who reached Ajmer on the 23rd December 1615. He had his first audience with Jahāngīr on the 10th January 1616, and was received by the Mughal Emperor with "courtly condescension." Near Chitor, on his way to Ajmer from Surat, Roe met the eccentric Thomas Coryat, whose mania for travelling brought him on foot from Jerusalem to Ajmer. The "World's foot post," as he describes himself, wrote a pamphlet, "From the Court of the great Moghul, Resident at the Town of Asmere in Eastern India," which is a quaint and early specimen of travellers' tales. Roe himself remained at Ajmer until November 1616, and afterwards accompanied Jahangir in his March to Ujjain. Although it appears doubtful whether he managed to obtain any substantial advantage for the East India Company as a result of his mission, his Journal has left us a vivid picture of the life both in Ajmer and in camp. It was at Deora, near Ajmer, that in A.D. 1659 Aurangzeb crushed the army of the unfortunate Dara and forced his brother into the flight which was destined to terminate only by his imprisonment and death. The celebrated traveller Bernier met and accompanied Dārā for three days during the flight, and has given a graphic description of the miseries and privations of the march. During the war with Mewar and Marwar, which was brought about by the bigotry of Aurangzeb, Ajmer was the head-quarters of that Emperor, who nearly lost his throne here in 1679 by the combination of Prince Akbar with the enemy.

On the death of the Sayyids in 1720 A.D., Ajīt Singh, son of Jaswant Singh of Mārwār, found his opportunity in the weakness consequent on the decline of the Mughal Empire to seize on Ajmer, and kill the Imperial governor. He coined money in his own name and set up every emblem of sovereignty. Muhammad Shāh collected a large army and

Mughal Emperors.

Råhtors of Märwär.

invested Taragarh. The fort held out for four months, when Ajīt Singh agreed to surrender his conquest. Ten years later Abhay Singh, the accomplice in the assassination of his own father, Ajīt Singh, was appointed by Muhammad Shāh Viceroy of Ajmer and Ahmadābād, and Ajmer became practically a portion of Mārwār. The parricide Bakht Singh obtained Nagaur and Jalor from his brother, Abhay Singh. Abhay Singh was succeeded by Ram Singh, who attempted to wrest Jalor from his uncle. This led to the battle of Merta, where Ram Singh was defeated and forced to fly. He determined to call in the aid of the Marāthās, and at Ujjain found the camp of Jai Appa Sindhia, who readily took the opportunity of interference. Meanwhile Bakht Singh had been poisoned, and his son, Bijai Singh, opposed the Marathas. He was defeated and fled to Nagaur, which withstood a year's siege, though meanwhile all the country submitted to Ram Singh. At the end of a year Jai Appa was murdered by two soldiers of Bijai Singh, who sacrificed themselves in their master's interest. With Jai Appa removed, the siege languished, and eventually a compromise was agreed upon. Bijai Singh surrendered to the Marathas in full sovereignty the fort and district of Ajmer as mundkati or blood-money for the death of their leader. The Marathās on their side abandoned the cause of Ram Singh. A fixed triennial tribute was to be paid to the Marāthās by Bijai Singh. Ram Singh obtained the Mārwār and Jaipur share of the Sāmbhar Lake, and resided there until his death. These events occurred in A.D. 1756.

Marāthās.

For 31 years the Marāthās held undisturbed possession of Ajmer, till in 1787, on the invasion of Jaipur by Madhoji Sindhia, the Jaipur Rāja called in the Rāhtors for aid against the common foc. The call was promptly answered, and at the battle of Tonga the Marāthās suffered a signal defeat. The Rāhtors re-took Ajmer, drove out Mirza Beg, the Marāthā governor, and annulled their tributary engagements. The success was, however, transient, for in three years time the Marāthās, led by De Boigne, defeated the Rāhtors utterly at Patan. General De Boigne then marched on Ajmer. On the 21st August 1791, he arrived under the walls: the next day the town was taken and the fort invested. The citadel, however, had been provisioned for a year and was defended by a numerous garrison. After 17 days' operations De Boigne, converting the siege into a blockade, marched with the greater part of his troops against the Rājputs, who had assembled on the plains of Merta. On the 10th September the Rājput army was surprised before daybreak and nearly annihilated, and by three o'clock on the same day the town of Merta was taken by assault. The Rāhtors now submitted and agreed to pay tribute. Ajmer reverted to the Marāthās and was held by them till its cession to the British Government.

Cession to the British Government. Singhi Dhanraj was Governor of Ajmer during the three years it was held by the Rāhtors. The best known of the Marāthā sūbahdārs was Govind Rao, who appears to have been a strong and good governor. By the treaty of 25th June 1818, Daulat Rao Sindhia, after the Pindari war, ceded the district of Ajmer, valued in the

treaty at Rs. 505,484, to the British Government; and on the 28th July 1818, Mr. Wilder, the first Superintendent of Ajmer, received charge of the district from Bāpu Sindhia, the last Harāthā sūbahdār.

The history of Ajmer from 1818 is the history of its administration. The long roll of battles and sieges is closed. The district, worn out by the incessant warfare of half a century, at length enjoys rest, and the massive battlements of Taragarh begin to crumble in a secure peace. Mr. Wilder and his successors worked hard to improve the condition of the people, and the long incumbency of Colonel Dixon, who took charge of the district in 1842 in addition to Merwara, was productive of much good. Irrigation works were vigorously pushed forward. Commerce and agriculture were encouraged, and in 1851 the district came under a regular settlement. The measures taken to win the confidence of the people were successful, and the mutiny of 1857 passed over the province like a cloud. On the 28th May two regiments of Bengal Infantry and a battery of Bengal Artillery mulinied at Nasilābād. The European residents, however, were sufficiently protected by a regiment of Bombay Infantry, while a detachment of the Merwara Battalion made a forced march to Ajmer and protected the Treasury and Magazine There was no interruption The mutinous regiments marched direct to of civil government. Delhi, and the agricultural classes did not source in the revort.

Since then fammes alone have troubled the district. The more noteworthy are described in then proper place. The opening of the Rājputāna-Mālwā Railway in 1879 ushered in a period of material prosperity. The population of Ajmer city has nearly double, and the place will probably continue to grow in size and importance. The district, although severely affected by recent famines will, given a series of good years, quickly recuperate. These natural calamities

alone disturb its peaceful progress.

(b.) Merwara.

The history of Merwara before the occupation of Ajmer by the British authorities in 1818, is practically a blank. Hardly anything was known of the country, except that it was a difficult, hilly tract, inhabited by an independent and plundering race, who cared not for agriculture, and who supplied their wants at the expense of the surrounding territories. Sawai Jai Singh of Jaipur had penetrated no further than Jhak in an endeavour to subdue the country, and Amir Khan had failed in an attempt to chasise the plunderers of Jhāk and Chāng. Mr. Wilder, the first Superintendent of Ajmer, entered into agreements with the villages of Jhāk. Shāmgarh, Lūlwa, Kāna Khera and Kheta Khera, the nucleus of what is now Khālsā Merwara, binding them to abstain from plunder. The pledge, however, was little respected, or could not really be enforced by the headmen, and in March 1819, a force was detached from Nasīrābād for the attack of these places. No opposition was encountered, the villages were taken one after the other, and all levelled to the ground. The inhabitants escaped into the adjacent hills. Strong police posts were stationed at Jhak, Shamgarh, and Lulwa.

Mutiny of 1857

Early History. In November 1820 a general insurrection broke out. The police posts were cut off and the men composing them were killed. The thorough subjugation of the country was then determined on. A force stronger than the former retook Jhāk, Lūlwa, and Shāmgarh, and after some correspondence with the governments of Udaipur and Jodhpur, and after co-operation promised on their part, the force advanced into Mewār and Mārwār-Merwāra to punish the refugees of Jhāk Lūlwa and Shāmgarh, and the men who had given them an asylum.

Lülwa, and Shāmgarh, and the men who had given them an asylum. Bōrwa was the first village of which possession was taken, and the attack was then directed against Hathun, where a repulse was sustained with a loss of three killed and twenty-three wounded. In the night, however, the garrison evacuated the fort. The troops then marched on Barar and took it after slight resistance. The capture of Mandlan and Barsawara followed, and a strong detachment was then sent against Kot-Kirāna and Bagri in Mārwār-Merwāra. These were taken and made over to Jodhpur, and the reverses of the Mers reached their culminating point in the capture of Ramgarh, whither most of their chief men had retreated. These were nearly all killed or wounded or taken prisoners, and the remaining strongholds submitted in rapid succession. A detachment of cavalry and infantry was left at Jhūk, and the main body withdrew at the close of January 1821, the campaign having lasted three months. Captain Tod, in the name of the Rana, undertook the administration of the portion belonging to Mewar. He appointed a governor, built the fort of Todgarh in the centre of the tract, raised a corps of 600 matchlock men for this special service, and began to collect revenue. A different policy was pursued by the court of Jodhpur. The villages which had been decided to belong to Marwar were made over to the adjoining Thakurs: there was no controlling authority and no unity of administration. Ajmer brought all its share under direct management, but at first the Thakurs of Masada and Kharwa were held responsible for the establishment of order, under the superintendence of Mr. Wilder. It soon appeared that this triple government was no government; the criminals of one portion found security in another; the country became infested with murderous gangs, and the state of Merwara was even worse than before the conquest. In these circum-tances it was determined that the three portions should be brought under the management of one officer, vested with full authority in civil and criminal matters, and that a battalion of 8 companies of 70 men each should be enrolled from among the Mers.

Treaties with Udaipur and Jodhpur. The negotiations with Udaipur resulted in the treaty of May 1823, by which the management of Mewār-Merwāra, consisting of 76 villages, was made over to the British Government for a period of 10 years, the Rāna agreeing to pay Rs. 15,000 a year to cover civil and military expenses. In March, 1824, a similar engagement was, after some difficulty, concluded by Mr. Wilder with the Jodhpur Durbar. It was arranged that the sum of Rs. 15,000 should be paid annually on account of civil and military expenses, the Maharāna and Maharāja receiving in each case the revenue of their respective

portions. In March 1833, the arrangement with Mewar was continued for a further period of eight years, the Rana agreeing to pay Rs 20,000 Chitori or Rs. 16,000 Kaldar on account of expenses. On the 23rd October 1835, the arrangement with Mārwār was extended for a further period of nine years. The transfer of Jodhpur territory was only partial, and many villages were left in the hands of the border ing Thakurs, though nominally under the police superintendence of the British authorities. Twenty villages were made over by the first treaty, and by the second treaty some were added, but these latter were returned to Marwar in 1842. About this year the agreements of 1833 and 1835 expired, and it became necessary to make further arrangements for their continuance. The Udaipur Durbar expressed its willingness to allow its villages to remain under British management so long as it might suit the convenience of the British Government, and the Jodhpur Durbar expressed its readiness to do the same. But no agreements were executed, and although an effort was made to procure the perpetual cession of their shares from the respective Durbars, it was unsuccessful. On this unsatisfactory footing the British administration of Merwara remained for many With Udaipur the question was finally settled in 1883 by the following arrangement:-

The British Government was to accept the revenues of Mewār-Merwāra in full discharge of the Udaipur State's contributions towards the cost of administration of the tract, the expenses of the Mewār Bhil Corps and of the Merwāra Battalion, and no demand was to be made upon the Durbār for arrears of payment. The Mah rāna was specifically assured that his rights of sovereignty over Mewār-Merwāra would be in no wise prejudiced by this arrangement; and that, should the yearly receipts for the district at any time exceed Rs. 66,000, which sum represents the contribution payable by the Durbār for the administration of Mewār-Merwāra and the expenses of the two local corps, the surplus money should be paid in full to the Durbār. The Resident at Mewār was to annually report to the Durbār the aggregate revenue received from the district. This

arrangement is still in force.

In the case of Mārwār-Merwāra it was many years also before a satisfactory solution could be effected. Eventually in 1885 it was agreed that Jodhpur should retain its sovereign rights in its Mārwār-Merwāra villages and receive Rs. 3000 a year from them, and that in the event of a profit being derived from them by Government, the Durbār should receive 40 per cent. of it. On these conditions the Government of India have full and permanent administrative

control over the villages.

Colonel Hall was the first officer appointed to the charge of the newly acquired district, and he ruled Merwära from 1823 to 1836. He was fettered by no instructions, and was left to provide for the administration of the country. His system was simple and paternal, but well suited to the needs of the people. Civil and criminal justice were administered by panchāyat or arbitration of the assembled

Administration of Colonels Hall and Dixon.

elders of the village. If two-thirds of the panchayat agreed, the

question was settled.

The jail was made self-supporting; each prisoner was supplied with a seer of barley-meal daily and with nothing else, but if the prisoner wished he might furnish his own flour. On his release he was obliged to pay for his food and for his share of the jail establishment as well as for any clothing that might have been given him, and this system of recovering the jail expenses from the prisoners and their relations lasted till Colonel Dixon's death, when, on the representation of Captain Brooke it was abolished in 1858. The revenue was collected by an estimate of the crops, one-third of the produce being the Government's share, except in some special cases. The estimate was made by a writer on the part of Government, assisted by the patels, the patroaris, and the respectable landowners. In calculating the money payment to be made, the prices current in the country for 10 or 12 miles round were taken and an average struck. Cultivators who broke up new land or made wells received leases authorizing them to hold at th and th of the produce. The headmen of the villages paid 4th.

This system of administration possesses historical value as being that under which the country throve until 1851, the year of Colonel Dixon's regular settlement. According to competent observers it was consistently successful, and to it much of the rapid progress Another important factor in the made by the country was due. civilization of the people was the Merwara Battalion which was raised in 1822. By service in its ranks the wild mountaineers became brave and disciplined soldiers, and when they returned home

they carried the leaven of law-abiding order into the villages.

Colonel Hall was followed by Colonei Dixon, who ruled Merwara until 1842, and thereafter the combined districts of Ajmer and Merwara until his death in 1857 He is still, and deservedly, remembered by the Merwara people as their greatest benefactor. administration was remarkable for the large number of tanks which were built in Merwara for irrigation purposes, and they were all entirely due to his personal energy and enthusiasm. Their good effect can hardly be over-estimated. Agriculture became possible and profitable, and the area under cultivation increased rapidly. In order to make the people obtain the benefits of their industry and to attract traders to Merwara, Colonel Dixon founded the walled town of Nayanagar, or Beawar, in 1835. Mahajans flocked to it; the enterprise was at once successful; and the place is now the commercial and administrative capital of the district. The founder is probably the latest Englishman who has built a "fenced city." Before he died he had the satisfaction of seeing around him a people whose wants had been supplied, whose grievances had been redressed, and who were described as being "most prosperous and highly favoured."

Nothing can speak more plainly to the great social change which has been wrought in the inhabitants of Merwara than the deserted and ruined state of their ancient villages. These were formerly invariably perched upon hills in inaccessible places for the sake of safety from the attack of their fellow-men and of wild beasts. The adoption of habits of industry and agriculture has rendered the retention of such dwellings alike unnecessary and inconvenient. The old villages are nearly deserted and are fast falling into decay. New hamlets have sprung up everywhere in the villages, and the tendency to settle near the cultivated land is still on the increase.

(c) Archæology.

Ajmer is rich in objects of archæological interest. The most important is the mosque known as the $Arrh\bar{a}i$ -din- $k\bar{a}$ - $Jhonpr\bar{a}$ or "Two and a-half days' shed." This, originally a Brahmanical temple or college, was converted into a mosque by order of Muhammad Ghori, the legend being that as he passed the temple, he ordered that it should be ready for him to pray in on his return in two and a-half days. The pillars and the roof of the temple were permitted to remain, but the rest of the Hindu portion of the building was demolished and much of the carving on the remaining pillars A screen or facade of very remarkable beauty was erected, and forms the front of the present mosque, which was surrounded further by lofty cloisters with a tower at each corner of the The cloisters have largely fallen in, and the surviving portions of the towers are very imperfect. The facade of the mosque, however, and the mosque itself are in good preservation, having been extensively repaired in Lord Mayo's Viceroyalty, while considerable further restorations were carried out in 1900-1902. The mosque is a few years only later in date than the Kutab mosque, near Delhi, and is one of the best specimens of the mosques of its kind.

The embankment of the Anā Sāgar Lake supports the beautiful marble pavilions erected as garden or pleasure-houses by Shāh Jahān. Of the five original pavilions, four remain in good preservation: the remains of the fifth have been preserved but are very slender. The embankment, moreover, contains the site of the former hammām, the floor of which still remains. Of the five marble pavilions two were at one time built into residencies for British officials, while two others were converted into an office and a library. The houses and enclosures were finally swept away in 1900-1902, when the two south pavilions were re-erected, the marble parapet completely repaired, and the embankment restored as far as was practicable to its early conditions.

The shrine of the "Dargāh Khwāja Sāhib," where is the tomb of the Muhammadan saint Muīn-ud-dīn Chishti, is another remarkable building, and is an object of pilgrimage to Muhammadans from all parts of the world. The shrine contains a mosque of Akbar, another by Shāh Jahān, and numerous more modern sacred buildings. The gateway, though disfigured by modern colouring, is picturesque and old. The shrine contains the large drums and brass candlesticks taken by Akbar at the sack of Chitōr, and given by him to the shrine. The saint's tomb is richly adorned with gold and silver, but only

Arrhāi-dinkā-Jhonprā

Bārādaries.

Dargāh.

Muhammadans are permitted to enter its precincts. The Dargah was commenced in the reign of Shams-ud-din Altamash (circa 1211—1236 A.D.) and finished in that of Sultan Humāyūn shrine is venerated and visited by Hindus as well as Muhammadars.

Magazine Fort.

The Ajmer Fort was built by the Emperor Akbar. It is a massive square building, with lofty octagonal bastions at each corner. The Fort was used as the residence of the Mughal Emperors during their visits to Aimer, and was the head-quarters of the administration, both in their time and in that of the Marathas. The main entrance faces the city and is lofty and imposing. It was here that the Mughal Emperors appeared in state, and here that, as recorded by Sir Thomas Roe, state criminals were publicly executed. ground surrounding the Fort has been largely built over, and its striking appearance is thus considerably impaired. The interior was used as a magazine during British occupation until 1857, and the centre building, now used as tahsīl offices, has been so much altered that its original shape and proportions are difficult to trace With the Fort the outer city walls of the same and restore. period are connected. These surround the city, and are pierced by five gates named the Delhi, Madar, Usri, Agra and Tirpolia gates. These gates were at one time highly decorated, but the Delhi gate alone retains any traces of its earlier ornament.

Tāragarh Fort.

In the older city, lying in the valley beneath the Taragarh hill and now abandoned, the Nur-chashma, a garden-house used by the Mughals, still remains, as do the water lifts built by the Rahtors and previously mentioned. The Taragarh Fort or citadel

which defended the earlier city is in fair preservation.

Pushkar.

Pushkar, seven miles north of Ajmer, is a celebrated place of pilgrimage, and the great sanctity of its lake, equalled, according to Colonel Tod, only by that of Manusarowar in Tibet, is due to the belief that here Brahma performed the yajna, and that the Sarasvati here reappears in five streams. The legends connected with these two beliefs may be found in the "Pushkar Mahatma" of the Brahmā was perplexed as to where he should " Padma Purāna." perform the sacrifice according to the Vedas, as he held no temple on earth like other deities. As he reflected, the lotus fell from his hand, and he determined that where it fell, there would he perform his sacrifice. The lotus rebounding struck the earth in three places; water issued from all three, and Brahmā descending called the name of the place "Pushkar," after the lotus. Brahmā then collected all the gods, and on the 11th day of the bright half of Kārtik all was ready. Each god and rishi had his own special duty assigned to him, and Brahmā stood ready with a jar of *amrit* on his head. The sacrifice, however, could not begin until Sāvitri appeared, and she refused to come without Lakshmi, Pārvati, and Indrāni, whom Pavan had been sent to summon. On hearing of her refusal Pavan had been sent to summon. Brahmā became enraged and said to Indra, "Search me out a girl that I may marry her and commence the sacrifice, for the jar of amrit weighs heavy on my head." Indra accordingly went, but found none except a Gūjar's daughter, whom he purified by passing through the body of a cow, and then bringing her to Brahmā told what he had done. Vishnu observed: "Brāhmans and cows are in reality identical; you have taken her from the womb of a cow, and this may be considered a second birth." Shīva added that as she had passed through a cow she might be called Gāyatri. The Brāhmans agreed that the sacrifice might now proceed, and Brahmā having married Gāyatri and having enjoined silence upon her, placed on her

head the jar of amrit, and the yajna commenced.

The sacrifice, however, was soon interrupted by a naked man, who appeared crying, "Atmat, atmat," and who, at the instigation of Shīva, threw a skull into the sacrificial ground. When it was attempted to remove the skull, two appeared in its place, and the whole ground gradually became covered with skulls, till Shīva, at Brahmā's request, finally agreed to remove them on condition that he should have a temple at Pushkar, there to be worshipped under the name Atmateswar. Meanwhile a number of Brāhmans, all ugly men, arrived from the Dakhin. As they bathed in the lake they became handsome, and the ghāt at which they bathed, called Sarup ghāt, is the resort of pilgrims on the 11th day of Kārtik. On the morning of the 12th day the Brāhmans came to Brahmā and asked where they were to bathe. In reply he directed them to bathe in the Prechi Sarasvati, the stream which passes by the village of Hokran, and it is explained how the Sarasvati, after disappearing under ground to escape the heat of the fire which she is carrying to the sea, re-appears in five channels in the sacred soil of Pushkar; how two of these meet at Nand, 5 miles from Pushkar; and how from the junction the river, thereafter called the Luni, proceeds to the sea. The sacrifice was disturbed this day by Bhattu Brāhman, who let lose a snake among the Brāhmans. The reptile coiled itself round Bhrigu Rishi, whose son imprecated a curse against Bhattu that he might become a snake. Bhattu, going to his grandfather Brahmā, was consoled by the promise that he should be the founder of the 9th order of snakes, and was directed to go to the Nagpahar, where he should receive worship on the 5th day of the dark half of Sāwan, at the place called the Nagkund.

The sacrifice proceeded till the 15th, each day having its appointed duties; for this day the Brāhmans were directed to make a circuit of the lakes and to bathe in "Gayākup," the tank now known by the name of "Sudā Bāi." Shortly after their return Sāvitri appeared, greatly incensed at the disregard which had been shown to her. Brahmā sought to pacify her, but to no purpose, and she went away in a rage to the hill north of the lake, where is her temple.

After the yajna was performed by Brahmā, Pushkar became so holy that the greatest sinners by merely bathing in it went to heaven. Heaven became inconveniently crowded, and the gods complained that no man any longer regarded them or his duty, so easy was it to get to heaven. Brahmā agreed accordingly that the tirth should only be on earth from the 11th day of Kārtik to the full moon, and for

the remainder of the year he promised to remove the tirth to the

Such is the legend given in the Pushkar Mahatma.

The legends concerning Pushkar after the yajna of Brahmā are rather confusing. The virtue of the lake is said to have been forgotten till it was re-discovered by Raja Nahar Rao Parikar of Mandor, who followed a white boar to the margin of the lake, and then, dismounting to quench his thirst, found on touching the water that he was cured of a skin disease. He is accordingly said to have had the lake excavated and to have built ghāts. Pushkar after this appears to have come into the possession of Chechi Gujars, for there is a legend that some 700 years ago, a large body of Sanyāsīs came to bathe in Pushkar; they disapproved of the Gujars being in possession of the ghāts, killed them all on the night of the Dewali, and turning out the Kanphata Jogis, who had become priests of the temples, themselves left a representative at each temple.

There are five principal temples at Pushkar, those dedicated to Brahmā, Sāvitri, Badri Nārāyana, Varaha, and Shīva Atmateswara. They are all of comparatively modern construction, for the old temples suffered much at the hands of the Mughals, and Aurangzeb here, as elsewhere in India, enjoys the reputation of having destroyed many temples. A masjid which is still kept up was built by him on the site of a temple to Keshav Rai. The temple of Brahma was built by Gokul-Parak, an Oswāl Mahājan of Gwalior, and is said to be the only temple dedicated to Brahmā in India. The attendants at the temple are Puri Gosains. The temple of Savitri is built on the north of the lake, and was constructed by the "purchit" of Ajit Singh of Marwar. The temple to Badri Nārāyana was rebuilt by the Thākur of Kharwa some 100 years ago. That of Varāha, or the boar, was demolished by Jahangir, and the present temple was built by Bakht Singh of Jodhpur. Goma Rao, sūbahdār of the Marāthās rebuilt the temple of Shīva Atmateswara.

The town is picturesquely situated on the lake, with hills on three sides; on the fourth side the sands, drifted from the plains of Marwar, have formed a complete bar to the waters of the lake, which has no outlet, though filtration through the sand hills is considerable. Bathing ghats have been constructed nearly all round the lake, and most of the princely and wealthy families of Rajputana have houses round the margin.

A fair at Pushkar takes place in October or November, and like other religious fairs is used as an opportunity for trade. It is attended

by about 100,000 pilgrims, who bathe in the sacred lake.

Outside Ajmer and Pushkar there are few objects of archaeological interest. In the south-west of the Ajmer district there are several remains of Hindu temples, the age of which is not known. It is possible that they date from the time of the Hindu kings of Toda Raisen, the ruins of which lie some 30 miles across the border in Jaipur territory. Baghēra and Sakrāni contain the better known of these remains. The fort at Bhinai is a good specimen of the forts built by the smaller Rajput Chiefs.

Other places.

CHAPTER III.

POPULATION.

The census of 1901 was the sixth of a series, which began in 1865. It was practically speaking a famine census. Nothing can show more clearly the vicissitudes of season to which this tract of Rajputana is exposed, and their influence on the people, than the extraordinary fluctuations of the population during the last forty years, as noted in the margin. The year 1872 followed the severe famine of 1868-69, and the effects are seen in the reduction of population by over a lakh. The census of 1891 was taken after 20 years of unusual prosperity, in which the opening of the railway and establishment of Ajmer as a large railway centre took place. The reduction in the population of 1901 is the outcome of the natural calamities of the decade, which included two famines, that of 1891-92 and that of 1899-00.

1865—4,26,268. 1872—3,16,590. 1877—3,96,331. 1881—4,60,722. 1891—5,42,358.

1901-4,76,912.

Density.

The square mile density for the province, including urban areas, is 175.93, as compared with 200.08 in 1891 and 169.96 in 1881.

As regards density of the rural population, Ajmer and Merwara have now changed places; Merwara has the larger figure (1369 to the square mile); the Ajmer figure is 130. Both are considerably less than those of 1891 (154.9 Merwara, 159.8 Ajmer). The result is probably due to the better physique of the Mer population of Merwara, where a larger birth rate has consistently obtained since 1872. During the actual famines the Mers came and remained upon relief works more readily than the inhabitants of Ajmer, and the latter suffered more severely from the epidemics that followed.

> Towns and Villages.

The total population in the last census was 4,76,912-2,51,026 males and 2,25,886 females—distributed over four towns and 740 villages and living in 1,07,401 occupied houses. The number of persons per house was 4.44. Of the total population Ajmer claims 3,67,453, of whom the residents in urban areas number 1,03,386 and in rural areas 2,64,067. In Merwara the urban and rural populations are 21,928 and 87,531 respectively.

The villages of Ajmer are larger and more compact than those of Merwara, where 52.2 per cent of the population live in hamlets of less than 500 inhabitants. In Ajmer the average village population is 621, and 46.8 of the rural inhabitants live in villages containing from 500 to 2.000 persons. In Merwara the average village population is only 278. The difference in the physical features of the two districts is primarily responsible for this. The open plains of Ajmer encourage the growth of large central villages. In Merwara the small patches of culturable land are scattered among the valleys, and are separated from each other by rocky and difficult hill country. Each man likes to live where he can keep a watch upon his crops, so every valley has its

Movementa

of Population. little hamlet, while the fortified and inaccessible central village, the product of an age of war and plunder, is falling into ruins.

On the whole the population of Ajmer-Merwara has decreased by 65,446 since the census of 1891, but with the exception of Kekri, the

decrease has taken place entirely in rural areas.

Of the towns, Ajmer, with a population of 73,839, shows an increase of 4.996, which may be attributed to the rise in the number of workmen in the Railway carriage and locomotive shops and the influx of people from Native States during the famine. Beawar and Nasīrabad, with returns of 21,728 and 22,494 respectively, are almost stationary. Kekri alone with 7,053 shows a decrease of 47. There are no other places treated as towns within the division. It is doubtful whether the decrease in the rural population during the last decade. can be attributed to any general movement on the part of the inhabitants. The increase in Ajmer city may be due to some extent to an influx of muskilled labourers, who could no longer get employment upon the land. But such movement would only be temporary, and no general tendency to desert rural areas could be deduced from it. The decrease in the rural population is rather to be accounted for by positive causes affecting those who remained in their villages, viz., a low birth rate and a high death rate. Abnormally high prices ruled during the last half of the decade, during the last three years of which the whole or part of the district was affected by famine, and they checked the natural growth of the population; while the famines were followed by epidemic diseases, among which that of malarial fever at the close of 1900 was by far the most conspicuous. In that year the recorded fever deaths alone numbered 44,236, and the recorded death rate reached the unprecedented figure of 11997 per 1,000.

Migration.

Considerable immigration is believed to have taken place from Native States during the famines, but reliable statistics are not available. In Merwära the practice of emigration is common among the Mers, but the prompt provision made for them in recent famines has reduced the tendency. During the year 1899,7,938 persons left Merwära with 37,978 head of cattle. Most of the emigrants returned, but the number of cattle brought back was only 13,868. There is always a large stream of emigration through Merwära from the neighbouring Native States whenever there is a scarcity of grain or fodder in Mewär or Märwär; the stream always follows the same well-defined routes, and the local officials are well necustomed to dealing with it.

Vital Statistes, The record of the population by age periods exhibits clearly the effects of the recent severe famines. The infant population of less than a year in age in 1891 was 19,976. In 1901 it was 6,117. That between one and two years of age fell from 9,555 to 3,116. Children between the ages of 5 and 10 years numbered 52,549 in 1901, whereas in 1891 their number was 76,192. It was the infant population that the famine most heavily affected.

The mean age of males in 1901 was 25:53, and had risen since 1881. The mean age of females was 26:27, and had also risen. The figures again indicate the heavy mortality among children in the famine.

In the municipalities of Ajmer, Beāwar and Kekri the municipal authorities, and in Nasīrābād the cantonment authorities, make the necessary arrangements for collecting and reporting vital statistics, under rules sanctioned by the Local Government. In rural areas the police are the reporting agency. Village watchmen make reports of births and deaths to the police stations, while revenue officials (patwāris) and managers (kāmdārs) of istimrāri estates also submit weekly reports to the same quarter. These reports check each other. The weekly figures are sent to the Civil Surgeon, Ajmer, who submits the monthly statement, through the Commissioner, Ajmer-Merwāra, to the Chief Medical Officer for Rājputāna. No doubt the system by which vital statistics are obtained in rural areas is far from perfect, but an efficient reporting agency is very hard to find. It has, however, received much attention recently and is believed to be improved. The ratio of births per 1,000, which was 27 76 in 1881, fell in 1891 to 21:32, while in 1901 the effects of famine reduced it to 16:10 per 1,000. The death rate possesses the same features and stands at 33:13 per 1,000 in 1901, against 20:23 in 1891 and 23:33 in 1881. In 1902 the birth and death rates per 1,000 were 36.08 and 32.86 respectively.

The majority of deaths are due to fever and bowel complaints. The death rate from fever in 1901 was 27:45 per 1,000. The fever that supervened upon the famine was widespread and of a very fatal character, causing a mortality which exceeded that of the period when the famine prevailed. Small-pox is a not uncommon epidemic, but the continued decrease of blindness in recent census returns is satisfactory, and points to the steady progress made year by year in vaccination. Cholera often occurs at the commencement of the rainy The last serious outbreak was in 1900. Dysentery and diarrhoa are very prevalent during the rains, as also is rheumatism. Cases of ophthalmia are frequently met with. Diseases of the skin are very common; they assume various types and characters, from a common herpetic cruption to the most inveterate form of lepra. Pleurisy and pnemonia carry off many people in the cold weather. Boils and abscesses are very prevalent during the rains, and scurvy is common at this season. Guinea-worm is always more or less prevalent, and in some years hundreds of people are attacked by the malady. Unless the worm is extracted at an early stage, considerable irritation and inflammation supervene, and it may be weeks or months before the patient recovers. So far Ajmer-Merwara has been fortunate in continuing practically free from plague, in spite of the fact that it has been raging in the Punjab, in Bombay and in the Central Provinces. A few imported cases have been detected, but prompt isolation has prevented any spread of the disease. Measures have been decided upon and will be put in force in the event of any outbreak, whether in rural or urban areas. At present the inspection of all passengers arriving by train in Ajmer is the only prophylactic measure in operation.

There are 2,51,026 males and 2,25,886 females in the division according to the 1901 census. The proportion of females to males is condition.

Diseases.

higher among the Hindus than among Muhammadans, and taking all religions the proportion is higher in Ajmer than in Merwara. Among selected castes the proportion of females to males has been found to

be lowest in the castes of high social status.

The unmarried population is 1,76,338 and the married 2,32,920, while widowers and widows number 20,614 and 47,040 respectively. There has been a decline in the number of married persons and increase in the number of widowed since 1891, due to the calamities of the decade. The seasons of marriage among the Hindus are determined by astrological considerations. As a rule marriages are avoided during the rainy season, as it is believed that the gods are asleep in those months. But among Rajputs the festivals of Janum-Ashtami, Basant Panchmi, Rādha Ashtami and Akhey Tij are deemed propitions for marriage. Gujars and Jats also marry on certain specified festivals. Among the Jats marriage is not allowed within the same got, and generally takes place later in life than in Upper India. A cocoanut and a rupee, emblems of fertility and wealth, are sent to the house of the bride. There the brotherhood is collected, and the contract is concluded by throwing the cocoanut and the rupee into the lap of the bride. The day is then fixed by the bride's parents, and the barat which consists generally of 25 to 30 men, reaches the village in the evening. At the appointed time the bridegroom proceeds to the bride's house in red clothes and with a sword in his hand. A frame of wood called a toran is fixed over the door, and this the bridegroom strikes with his sword and enters the house. All castes put up torans, which is a cross-barred frame resembling a wicket, and the custom is probably a relic of the marriage by conquest. When the bridegroom has entered the house, the Brahman causes him and the bride to go round a fire lit in the centre of the courtyard. This is the ceremony called phera and is the only one used. On the second day there is a feast, and the bridal party then disperses. The bridegroom's father spends about Rs. 200, the bride's father nearly as much, and the subsequent goung, when the bride's father gives turbans to his son-m-law and relatives, costs him about Rs. 150 more.

Among the Jūts—as among the Gūjars, Mālis and all the tribes of Merwūra—widow marriage is the rule and is called nāta. A man cannot marry his younger brother's widow, but may marry the widow of his elder brother. The younger brother has the first claim on the widow's hand, but if he does not marry her, any one in the gōt may do so. It is probably a relie of the now obsolete custom of niyoga, which obtained in Vedic times. No disability of any kind attaches to the children of nāta marriage: young widows are married off by their husband's relations, who take money from the second husband. In the early accounts of the Mers the custom is stigmatized as revolting, under the name of sale of women. As a matter of fact, grown up widows choose for themselves, though when they do the panchāyat generally orders a certain sum to be paid to the deceased husband's relations. These orders are often contested and are not enforced in

the courts. It must, moreover, be noted that a wid w cannot contract a valid nāta marriage except with a man of her own caste. If a widow chooses to remain so, she is not forced to marry, and in all castes a widow who has no sons retains her deceased husband's property till her death or re-marriage. She cannot mortgage except to pay her husband's funeral expenses, his debts, or to marry her daughter. The condition of widows under this custom is infinitely preferable than if they were forced to remain unmarried all their lives. Colonel Hall has recorded that, while he was complaining that women were sold as sheep, the women themselves so far from considering it a grievance, were flattered by the payment of a high price as a testimony to their beauty and usefulness. The Muhammadan law permits re-marriage of widows, but curiously enough the Muhammadan Khādims (Sayyids) of the Dargāh Khwāja Sāhib at Ajmer follow the custom of the superior Hindu classes. Rājputs and Brāhmans do not practice nāta. With Rājputs the custom of sati used to be optional, but it is now obsolete. Infant marriage is very restricted and polygamy is rare. Among Rajputs the marriageable age of a bride, as fixed by the rules of their Subha, is 14 years, and that of the bridegroom 18 years. The rules are enforced by the Sabha, and any contravention of them is punished by fine. Divorce is only allowed among Muhammadans, according to their laws. The proportionate number of unmarried Muhammadans exceeds that of the Hindus.

Formerly large sums of money were wasted at marriages and similar festivals. But in 1891 rules were drawn up with a view to reducing such expenses among the Mer zamindārs in Merwāra. A reasonable scale of expenditure was laid down for all ceremonies, and it is believed that an improvement in the direction of economy is being effected.

Among the Mer clans inheritance through the mother prevails. In the event of there being sons from two or more wives, the property is divided per capita of the wives and not per capita of the sons. In Ajmer primogeniture is recognized among the Rājputs.

Education generally has receded since 1891, the number of literate males per 1,000 having fallen from 108'3 to 103'7. Female education is still insignificant, but a slight increase is recorded. According to the last census there are 30,166 literate males and 1,922 literate females. The numbers of males and females literate in English are 4,152 and 646 respectively. In English education only has a considerable extension taken place during the last decade, and it has been entirely among the native population. The decline in education other than English is due to the recent famine, in which many village schools were closed while the children were on relief works. The heavy mortality in 1900 among children of a school-going age has also affected the figures. The Jains, who include the extensive trading communities of Ajmer and Beāwar, predominate among the literates, and after them come the Brāhmans. In Ajmer education is considerably more extended than in Merwära.

Inhoritance.

Education.

Language.

Local dialects and Hindi form the language of the great bulk of the population. Whether the former are off-shoots of Hindi or whether they and Hindi are derived from a common parent may be ascertained from experts. The dialects are rough and difficult to understand, and are used by a largely illiterate and backward population.

Castes, Tribes, and Races.

Brāhmans.

Of the various castes, Brāhmans come first on the list of social precedence. They number 25,045, or 6.5 per cent. of the Hindu population of the province. The Panch Dravid Brāhmans have the highest rank socially but are few in number. Panch Gaudas come next. They number 11,583 persons and include, among others, the Gaudas, Kanaujias and Sāraswats. The Gaudas again include six castes, locally known as the Chhanayatis. These are Gaudas, Dāymās, Gūjar Gaudas, Pārikhs, Sikhwāls and Khandelwals. Dāymās do not follow the marriage rules of the shāstras but rather those of the Mahājans and other castes. Some Brāhmans of Merwara eat meat and have no dealings with other Brahmans. not generally cultivators, but hold revenue free land in nearly every village. As none of their caste sub-divisions are peculiar to Ajmer-Merwara, a full description of them is beyond the scope of this article, and belongs rather to the Imperial Gazetteer of India.

Vaishyās.

The Vaishyās, or Mahājans are the most numerous class of the community and number 37,027, or 7.8 per cent. of the total population of all religions. Their principal sub-divisions are the Oswāls, who trace their birth-place to Osa-nagri in Mārwār, and the Agarwals, who derive their name from Agarsen, who lived at Agroda in Hariāna. Other Vaishya castes are the Masheshwaris and Bijbargis. The Seths of Ajmer are the leading members of this portion of the community, whose occupation is trading. They are generally well off, but during the last famine Mahājans came on relief works in both Ajmer and Merwāra. This shows how severely they were affected, and gives some clue to the decrease in their numbers since the 1891 census.

Kāyasthās.

Kāyasthās have been classified as a caste allied to Kshatiyas, Rājputs and Khattris. Some of them wear the Brahmanical thread. They number 2,620, and their chief sub-divisions are Māthur, Bhatnāgar, Shrivāstava, and Saksena. They are much employed in offices and educational establishments. There are three distinct families in Ajmer, known by the names of their pargunās—Ajmer, Rāmsar and Kekri—and these acknowledge no relationship. They have been hereditary kānūngoes since the time of the Emperors, and hold about 1,000 acres of revenue free land, along with certain perquisites from jāgīr and istimrāri villages.

Rājputs.

Among the land-owning eastes, the highest socially are the Rājputs. But they hold hardly any land except on bhūm and istimrāri tenures. The great majority of proprietors belongs to other eastes. No Rājput will touch a plough unless forced by hard necessity to do so; and the crown tenants, as well as the tenants of the jāgīr estates, are mainly the descendants of the ancient cultivators of the soil who have

held their land in all the dynastic changes through which Ajmer has passed. Where every man who dug a well became owner of the land irrigated therefrom, and where a cultivator without a well is considered a waif, with no tie to bind him to the village where he may reside, the land-owning castes must be nearly co-extensive with the cultivating castes, and such is found to be the case. Of the 195 Ajmer khālsa villages, 52 are held by Jāts, 41 belong to Mers, 35 to Gūjars, 4 to Rājputs, 4 to Merāts, 6 to Chitās, 2 to Deswāli Musalmāns; 8 castes hold one village each—Māli, Sayyid, Pathān, Mughal, Bānjāras, Ahir, Fakir and Christian. In the remaining 43 villages there is no exclusive caste ownership; the principal castes in these villages are 14 in number—Mālis, Telis, Mers, Merāts, Deswālis, Gūjars, Brāhmans, Rājputs, Mahājans. Kāyasthas, Khārols, Ahirs, Rebāris and Regars. The remaining land-owning castes have few representatives, and are scattered over many villages.

The four villages belonging to Rājputs are Arjanpura Jāgīr, Arjanpura Khālsa, Göla and Khori. The two former belong to Gor Rājputs, the two latter to Rāhtors. This exception, however, only proves the conclusion of the foregoing paragraph. Arjanpura Jāgīr was given on condition of protecting the road, and assimilates to a bhām tenure. Arjanpura Khālsa stands quite alone as the only zamindāri tenure in the district, with the exception of Muhammadgarh, where the tenure has been created by ourselves. Gola was held on istimrāri tenure till shortly before the establishment of British rule. Khori was originally a Mer village, but the Rāhtors held a large amount of bhām in it, and gradually turned out the Mers. In short, where Rājputs hold jāgīr or khālsa land, it will generally be found that it is the relic of a tālukdār tenure, or of a jāgīr grant, or of an encroachment by bhāmiās. All the istimrārdārs of Ajmer are Rājputs, and

they constitute the native aristocracy of the district.

Rājputs are returned in the census papers at 15,430. It is a curious fact, illustrative of the great vicissitudes of early times, that though Ajmer was held for over four hundred years by the Chauhāns, there are now comparatively few in the province. They must be looked for in Hāraoti, in Alwar, and in the desert of Nagar Pārkar, whither they have been pushed by the Rāhtors, who have occupied their place as the ruling tribe, and who in numbers, wealth and power greatly preponderate over the other Rājput clans in the district. These are three in number—Gor, Sesodiā, and Kachhwāha, and it will be convenient to consider them in the order of their arrival in the province, for a definite date can be fixed for the arrival of each.

In the time of Prithvi Rāj Chauhān (circa 1190 A.D.) Rājā Bach Rāj, and Rājā Bāwan, Gor Rājputs from Bengal, came to Ajmer on the customary pilgrimage to Dwārka. Prithvi Rāj engaged the brothers in an expedition against Daya Singh of Nāgaur which was successful, and subsequently each of them married a daughter of Prithvi Rāj. Rājā Bāwan settled at Kuchāwan in Mārwār; Rājā Bach Rāj remained in Ajmer. In course of time Junia, Sarwār, Deolia and the adjacent country fell into the hands of the Gor Rājputs, and to the head of

the clan Humāyūn gave a mansab of Rs. 7,000. In the time of Akbar Rājā Bithal Dās founded the town of Rājgarh, and called it after the name of his grandson, Rāj Singh. The son of the latter took Srinagar from the Ponwar Rājputs, who have now disappeared from the district. This, however, was the climax of the prosperity of the Gor Rājputs, for soon afterwards they were ejected from Rājgarh and all their territory by Kishen Singh Rāhtor. After 25 years of dispossession Gopāl Singh recovered Rājgarh, and the Gors were in possession when the country fell into the hands of the Marāthās. The latter in 1817 resumed Rājgarh and the 12 villages attached to it, as the Rājā was unable to pay a contribution of Rs. 10,000 fauj kharch. On the establishment of British rule these villages were returned on the condition of payment of nazarāna; but as the nazarāna was not, or could not be paid the whole was resumed with the exception of one small village, Kothāj, and remained khālsa until 1874. In March of that year the town of Rājgarh was presented by Government in jāgīr to Rājā Davi Singh, the representative of this ancient but fallen house. The Gor Rājputs hold land in 14 villages. The descendants of Bithal Dās are jāgīrdārs of Rājgarh and Kothāj and bhāmiās of Dānta and Jātiā. Bithal. Dās had 5 brothers, whose descendants are the istimrārdārs of Manoharpur and the bhūmiās of Sanod, Nāndla, Neārān, Lavera, Dodiāna, and Jharwāsa. The descendants of Rājā Bāwan are jāgīrdārs of Arjunpura Jāgir, are owners and bhāmiās of Arjunpura Khālsa, and hold bhūm in Tabiji.

It is unnecessary in this place to give a detailed history of the Rāhtors, the great conquering race which, in the year 1194, abandoned the ruined capital of Kanauj and founded a kingdom in the desert of Mārwār Such an account belongs more properly to the Gazetteer of Jodhpur. There are 4,609 Rāhtors in Ajmer-Merwāra. All the tālukdārs of Ajmer, with the exception of the Thākur of Manoharpur, the Thākur of Sāwar and his relations, and the Chitās of Merwāra descent, who hold 4 villages on istimrār tenure, are Rāhtors, and have their descent from Sivaji, the founder of the monarchy. Of the 109 bhām holdings in the district, 83 are held by Rāhtors, nearly all the younger sons and brothers of the istimrārdārs. The Rāhtors of Ajmer have the same characteristics as their brethren in Mārwār. Their physique is not remarkable; they are still warlike and indolent, and great consumers of opium. Each man carries at least a dagger, and, except under extreme pressure, none will touch a plough.

Sesodiā Rājputs hold the pargana of Sāwar at the south-eastern extremity of the Ajmer district on istimrār tenure, and the estate is a portion of a grant made by Jahāngir to Gokal Dās, who is said to have received 84 wounds in the service of the Emperor. There is a family of Sesodias who are bhāmiās in Nepoli. These are the only Sesodiās in the district.

The Kachhwāha Rājputs, like the Sesodiās, are to be found in the villages adjoining their respective States of Jaipur and Udaipur, and hold $bh\bar{u}m$ in 5 villages. They are found principally in the villages

of Harmāra and Tilaurniā in the extreme north of the Ajmer district. Their number was returned as 666 at the last census.

Rājputs differ from other high-caste Hindus, in that they are exogamous so far as their different clans are concerned. A Rāhtor will not marry a Rāhtor, but will take his wife from the Sesodiās or Kachhwāhas.

The Jāts were numbered at the census at 27,952. They are first-rate agriculturists, and possess a fine physique. They, with the Gūjars, are the original cultivators of the soil. Nearly the whole of the Rāmsar pargana belongs to them. They are settled in Kekri and in the best villages of the Ajmer and Rājgarh parganas. Tabiji, Sarādhna, Makrera, Jethāna, Budhwāra and Pecholiān belong to Jāts. In the Beāwar tahsīl they hold 7 villages, chiefly in and about the old town of Beāwar, adjoining the Ajmer district, for they never penetrated far into Merwāra, and are not to be found in the Todgarh tahsīl. They are divided into three main families, Puniyo, Sishmo, and Harchitral, but their gōts are more than a hundred. They hold no revenue free land nor any bhūm; they have in Ajmer double as much land as the Gūjars and pay three times as much revenue, partly no doubt owing to their having monopolized the chief villages, but principally to their greater energy in making wells and improving the land.

The Gūjars hold 35 villages in all parts of Ajmer district and 4 in the Beāwar tahsīl, where they are settled in the outlying villages of Jetgarh, Bhairon Khera, Pillāni and Sheonāthpura. They are returned in the census at 36,278. They are careless cultivators and devote their energies to grazing cattle. Those who live in or near Ajmer sell milk and butter in the town. Their customs are identical with those of the Jāts, but the Gūjars of Merwāra follow the inheritance laws of the Mers. Gūjars and Jāts will eat together. Their chief men are called Mir.

The Merwara clans consisting, as classified at the last census, of Rawats 32,209, Mers 21,649 and Merats 8,554, are supposed to be descended from a common ancestor. Their sub-divisions present peculiar features and deserve special notice.

They do not claim to be, nor do they appear to have been the original inhabitants of Merwāra. Of these last, however, little is known. The country must have been an impenetrable jungle, and the majority of the sparse inhabitants were probably outlaws, or fugitives from neighbouring States. The caste of Chandela Gūjars is said to have dwelt on the hills about Chāng; the hills near Kālinjar, Sāroth and Bhāilān are assigned by tradition to the Brāhmans. On the east side, on the Bōrwa hills, the caste of Bhātti Rājputs is said to have been located, while the southern portion of the Todgarh tahsīl was occupied by Mīnas. There is a tradition that a Bhātti Rājput, Ajit Singh, bore the title of king of Merwāra.

Mer, which can be used promiscuously for all inhabitants of Merwāra, means a "hill man." It is not by origin a caste or tribe name, but signified the dweller on this portion of the Aravalli range. The

Jats.

Gūjars.

Merwāra Clans. two main tribes of Merwara are known by the appellation of Chita and Barar, each class traditionally divided into 24 gots, but new gots are constantly being formed which take the name of their

immediate ancestor, and there are now many more.

Colonel Tod ("Rajasthan," Volume I, page 680) asserts that the tribes of Chita and Barar are Minas, and the traditions of the people themselves point to a Mina ancestry. Both tribes claim a common descent from Prithvi Rāj, the last Chauhāu king of Ajmer, and the story is that Jodh Lakun, the son of Prithvi Raj, married a girl of the Mina caste, who had been seized in a marauding raid near Bundi, supposing her to be a Rajputni. When he discovered his mistake he turned her and her two sons, Anhul and Anup, away. The exiles wandered to Chang in Beawar, where they were hospitably entertained by the Güjars of that place. Annul and Anup rested one day under a bar or fig tree, and prayed that if it were destined that their race should continue, the trunk of the tree might be rent in twain. The instant occurrence of the miracle raised them from their despondency, and the splitting of the fig tree is a cardinal event in the history of the race, according to the following distich:

"Charar se chita bhayo, aur Barar bhayo Barghat,
Shākh ek se do bhayo, jagat bakhāni jāt."
From the sound "charar" (the noise which is supposed to have reached Anhal from the splitting tree) the Chitas are called, and the clan Barar from the splitting of the fig tree. Both are descended from one stock. The world has made this tribe famous. In following the distribution of the clans, it is necessary again to bear in mind that there are 41 Mer villages in Ajmer, 214 in the Beawar tahsil, and 55 in the Todgarh tahsil.

Anhul settled at Chang in the north-west of Merwara, and his descendants in course of time exterminated the Gujars, who had given an asylum to Anhul and his mother. The clan waxed strong and multiplied, and gradually occupied all the strong places of Merwara, where they founded the villages of Jhāk, Shāmgarh, Lūlwa, Hāthūn, Kukrā, Kotkerāna, Nāi and others. They appear to have held the remaining Mers in subjection, for they enumerate 16 castes of Mers, who, they say, used to pay them one-fourth of the produce of the soil, and of all plundering expeditions. The clan now holds 117 entire villages in Beawar, besides portions of 53, and 10 entire villages in the Todgarh tahsil, including the pargana of Kotkerana. In Ajmer there are 21 entire khālsu and jāgār villages belonging to Chitās, and they are to be found in all the Ajmer villages except four.

Of the sub-divisions of the clan, by far the most important and numerous is that of the Merāts, a term which is generally used as synonymous with Muhammadan Mer, but which is a patronymic derived from Mera, the common ancestor of the Kathāts and Gorāts. Harrāj, grandson of Mera, a Chita in the reign of Bābar, took service under the Emperor at Delhi. During a night of terrific rain he remained firm at his post as sentry, with his shield over his head. The Emperor, to whom the matter was reported, is related

to have said: "In the Marwar tongue they call a brave soldier Katha; let this man be henceforth called Katha." Harrāj soon after became a convert to Islam and is the progenitor of all the Kathāt Merāts, a very large family, who hold 78 villages in Beawar, including all the principal places to the north and east of the talistl. Gora was brother of Harraj, and his descendants are Hindus, and hold 21 villages in the centre and south-west of Beāwar, of which Kālinjar and Kabra are the chief. The Gorats spread southwards, and have occupied 13 villages in the north of Todgarh; one village in Ajmer, Makhopura, belongs to them. The Kathāts, the most pushing of all the Chitās, spread northwards, and hold 9 of the 21 Chita villages in Ajmer. There they formed new gōts, of which the Bahādur Khāni, generally called par excellence Chitās, is the principal. Besides the khālsa and jāgīr villages, 4 villages in Ajmer proper are held by Kathāts on istimrāri tenure, viz., Nausar, Rajosi, Ajaisar and Kharekhri. The villages were given them by the Mughal Emperors for protection of the city of Ajmer and the adjacent passes. The chief men of the Kathāts and Gorāts call themselves Thākurs, but in Beawar, the chiefs of Hathun, Chang and Jhak, who are Kathats, are called Khans. Of the remaining sub-divisions of Chitas, the most important are the Laget, who hold 6 villages in Beawar, and the Nanset, who own the villages of Bargāon, Pālrān, Phārkiā, Mānpura, and Hathibata in Ajmer, besides portions of several others. Other gots which may be mentioned are the Rajoriya and Bedariyat, the former holding 3 villages in Ajmer, and the Bajriyāt Borwāra, Bilādiya, Pithrot, Bālot and Nādot, who possess a village or parts of several. The other $g\bar{o}ts$ live scattered throughout Merwāra.

Anup, the brother of Anhal, settled in Todgarh, and founded the Barār clan. His descendants, less enterprising than the Chitās, have remained in Merwāra, and are not to be found in Ajmer. They hold 11 villages in Beāwar, the most important of which are Kālikankar, Sendra, Bailan and Khera Sangnotan. They occupy the whole of the south of the Todgarh tahsit and 48 entire villages. They are more unsophisticated, honest and straightforward than the Chitās. They call themselves Rāwat, a petty title of nobility, and do not like being called Mers. Their chief men are called Rāo, of whom the principal are the Rāo of Kūkra and the Rāo of Barār.

All these Chauhān Mīnas, with the exception of the Kathāts, are nominally Hindus. Formerly Kathāts and Gorāts ate together and nothing was forbidden food to either. But the tendency towards division is growing. Chitās and Barars used to intermarry, but a feeling has sprung up against it, and recently the Rāwats have agreed to forbid it. The Merāts of Ajmer have discarded the *dhotī*, although it is still worn by their brethren in Merwāra. Among all Merāts the Muhammadan nikāh form of marriage is now almost universal. The estrangement between them and the Rawats appears destined to grow wider, but the customs of the two clans regarding inheritance, adoption, re-marriage of widows and similar matters are still identical,

Among the Merwara tribes which boast other than a Chauhan Mina ancestor, the most important are the two which claim descent from Dhārānāth Powar or Pramar, who founded the city of Dharanagar in Mārwār before the Pramar Rājputs were obliged to give way before the Gehlots and Rahtors. Tradition says that Rao Bohar, a descendant of Dhārānāth, came and settled at Rudhāna, in the extreme south of the Beāwar pargana. From this place his descendants spread and founded the adjacent villages of Biliāwās, Jawāja Bihār, Barkochrān, Rāwatmāl, Lusāni in the Beāwar tahsīl, and Akhayjitgarh Naloi and others in the Todgarh tahsīl. The tribe is divided into six gōts—Delāt, Kallāt, Doding, Boya, Kheyāt, and Balkarina Of these the Delat is the most representation and helder Pokhariya. Of these, the Delat is the most numerous, and holds 14 whole villages in Beāwar and 5 in Todgarh. The Kallat clan hold only 1 village, Kalātankhera in Beāwar, while the others have no entire village in Merwāra. The Delāts appear to have pushed the other members of the tribe out of Merwara, who thereupon settled near Ajmer, and specially in the pargana of Pushkar. There are 11 villages in Ajmer held by this tribe, and they hold parts of 8 others. The Dodings hold Barla, Madarpura and Gwarri; to the Boya clan belong the villages of Hokran and Gudhli; Khwajpura and Kānākhera belong to the Kheyāts, and the Pokhariya clan hold the villages of Pushkar, Ganāhera, Naidla, and Naulakha. The men of this tribe affect the name Rawats, and return themselves as such at the census. They are an industrious race, generally taller and better built than the Chauhan Minas. Kathats will not give their daughters in marriage to this tribe, but will take wives from them, and they intermarry freely with Hindu Chitas and Barar and other Mer clans.

The second tribe which claims descent from Dharanath is that of the Moti Rāwats, who hold 14 villages in the pargana of Bhāilān. They own two villages, Fatahpur and Bhojpur in Beāwar, and only scattered representatives of the tribe are met with in Ajmer. The pargana of Bhāilān is supposed to have been originally inhabited by Brahmans. A descendant of Dhārānāth, Rohitas by name, came and lived at Bāghmāl as an ascetic in a cave in the hill now called Magatji. A Banjāra was passing near the hill with his wife, and deserted her at this spot; she lived for some time with the Jogi, and then descending the hill sought the protection of Khem Chand Brahman in Bamanhera, and in his house was delivered of twin sons, of whom one remained in Bhailan, and the other in Marwar. In the fifth generation one Magat was born, who expelled the Brāhmans from Bhāilān. The hill, which was the cradle of the race, was named after him, and he is still venerated by the Motis. A fair is held on the hill in September, at which time the hero is believed to traverse the 12

villages of Bhailan in the twinkling of an eye.

After the sack of Chitor by Ala-ud-dīn, two brothers, Rājputs of the Gehlot clan, fled to Bōrwa in the Sāroth pargana, where they intermarried with Mīnas. The tribe descended from them is divided into 16 clans, of which the most important are the Godāt, Medrat, Kāchi, Pinga, Baniyāt, Lahr, Bālot and Dhānkal. They hold 11

Gehlof.

entire villages in all parts of Beāwar, 1 village, Kūkar Khera, in Todgarh, and are found in 23 other villages in Merwāra. In Ajmer they own 6 villages, Parbatpura, Ansari, Mayāpur, Lachmipur, Borāj, and Amba Masina. They consider themselves Surajbansi Rājputs, and call themselves Rāwat. Like the tribes of Puar origin, they intermarry with Hindu Chauhān Mīnas. Merāts will take wives from

them but will not give them their daughters in marriage.

The Balāi caste holds 4 villages in Beāwar, Jāts and Gūjars hold 11, and Narsingpura and Dungar Khera belong to Mahājans. The remaining inhabitants of Merwāra belong to a few scattered clans who pass under the general designation of Mer, and who as usual claim to be descended from Rājputs, but have no clear history. The Pataliyāt clan claims to be of the stock of the Bhātti Rājputs of Jaisalmer, and hold one village, Bāriā Naga. The Chaurot claim the same descent and own one village, Kālikankar Kishanpura. They are also found in Mohanpura in Ajmer. The Bāch Mers inhabit Rājpur Būchān, and are found in a couple of villages in Ajmer. The Bharsal clan live in the village of Rāmkhera Dhanār, and are to be met with in Kotra, Sedaria, Bhawānikhera and Kishanpura in Ajmer. The Kharwāl Mers live in Nayānagar and Fatahpur 2nd, and the headman of the town of Beāwar is of this caste. Mamnots, Selots, Banats, and Bannas live scattered in a few villages.

Of the other castes in Ajmer-Merwara, the Malis number 15,852. They are good cultivators and hold the greater part of Kasbā Ajmer. A peculiar caste, Kir, very few in number, devotes its attention to the The Rebāris, also few, breed camels and cultivation of melons. cultivate rice. The menial castes are Bhangīs, Balāis and Regars. Balais are the most numerous, numbering 22,350, and consider themselves superior to the Regars, who correspond with the Chamars of the United Provinces of Agra and Oudh. Minas, Sānsis and Bhils are the thievish classes, but none of them are numerous in the district. The names of the remaining castes point to the occupation of each— Kumhārs (potters) number 11,248; Khātis (carpenters) are 6,373; Chākars and Darogas (domestic servants), 6,933; Nāis (barbers), 6,846; and Chamars (tanners), 19,350; Darzis (tailors), Dhobis (washermen), Kahārs (bearers), Lohārs (backsmiths), Sunārs (goldsmiths), Telis (oilmen), are below 5,000; Bhāts (bards), Chippas (chintz printers), Khārols (salt workers), are below 2,000; Dholis (drummers), Gadaris (shepherds), Lakherās (varnishers), Rangrez (dyers), Tamoblis (pan sellers), are below 1,000; Beldars (diggers), Bharbujas (grain parchers), Ghosis (milk and butter sellers), Halwāis (confectioners), Kalāls (liquor sellers), Silāvats (masons), Sikligars (steel sharpeners), and Thatheras (braziers), are under 500 in number.

Of the Muhammadans 31,972 are classed as Sheikhs; Sayyids are 5,703; Mughals 2,737; while Pathāns are numbered at 11,048. The latter two classes are scattered over the district, a large proportion being in the native army and the police. The remaining different classes number 20,571. Deswālis (1,442) hold two villages in the north of Ajmer and say they are Rājputs, who were converted in the time

Other Tribes.

of Shahab-ud-dīn. One village, Muhammadgarh, belongs on zamindari tenure to a Pathān. The Banjāras, who live in Ghegal are Musalmāns, and were, they say, converted at the same time as the Deswālis. The Musalmāns in the districts are chiefly the attendants on the Muhammadan shrines, and most of them hold revenue-free land in the $j\bar{a}g\bar{v}r$ villages attached to these institutions. They are generally poor and idle.

Religions.

Hindus constitute the bulk (79.77 per cent.) of the population. These include the Mers, who return themselves as Hindus. The collective numbers of those who follow the Brahmanical faith has fallen from 4,36,831 in 1891 to 3,80,453 in 1901. The agricultural and labouring classes who suffered most in the famine come within the category. The Jains, who now number 19,922 have decreased by 7,017 since 1891, but the decrease is probably chiefly due to incorrect enumeration. The Muhammadan population numbers 72,031 or 15.1 per cent. of the whole. Residing chiefly within the urban areas, they were less affected by the famines than the Hindus. The Christians number 3,712. The Arya Samāj claims 366 members, and the district also contains 264 Sikhs and 164 Pārsis.

The principal sects of the Hindus are the Vaishnavas, or worshippers of Vishnu, the Shaivas, or worshippers of Shīva, and the Shāktas, or worshippers of the Shaktis, who are the female associates or active "Powers" of the members of the Hindu Trinity—Brahmā, Vishnu and Shīva. Manu's Code is taken as the theoretical standard of right and wrong, but is not strictly followed in all its applications. Life in this world is considered as being one of 84,00,000. But whether all are eventually absorbed in the supreme being, or whether some will gain Vaikunth (Heaven) and others be relegated to Narak (Hell), is doubtful. The Jats worship a variety of Gods, including Mata and Mahadeo, but their chief object of veneration is Tejan, whose legend is as follows:-Teja was a Jāt of Karnāla, near Nāgaur, who lived 890 years ago, and had been married at Rupnagar in Kishangarh. While grazing his cattle he observed that a cow belonging to a Brāhman was in the habit of going daily to a certain place in the jungle, where the milk dropped from her udder. Further observation showed that the milk fell into a hole inhabited by a snake. Teja agreed with the snake to supply him daily with milk, and so prevent the Brahman suffering loss. Once, when preparing to visit his father-in-law he forgot the contract, and the snake appearing, declared that it was necessary he should bite Teja. The latter asked for permission to first visit his father-in-law, and the snake agreed. Teja went on his journey, and at Kishangarh rescued the village cattle from a band of robbers, but was desperately wounded in the encounter. Mindful of his promise to return, he, with difficulty, reached home and presented himself to the snake, who, however, could find no spot to bite, so badly had Teja been cut up by the robbers. Teja therefore put out his tongue which the snake bit, and so he died. The Jats believe that if they are bitten by a snake and tie a thread round the right foot while repeating the name of Tejāji the poison will prove innocuous. Ţejāji is represented as a

man on horseback with a drawn sword, while a snake is biting his tongue. Nearly all Jāts wear an amulet of silver with this device round their necks. Colonel Dixon singled out Tejīji as the patron of the fair he established in his new town of Nayānagar or Beāwar.

Any remarks as to religious beliefs and standards are more applicable to the Hindus of Ajmer than to various clans of Merwara. The latter do not trouble themselves much with the orthodox divinities of Brāhmanism. They worship incarnations of Shīva, under the names of Bhairunji and Mātāji. Šitla stones daubed with red paint and consecrated to the latter are to be met with on all sides. Allahji is a common deity, and the deified heroes Deoji and Ram Deoji also find worshippers. The hills of Magatji and Goramji, the highest in Merwara, share in the veneration of the people, and this is probably a relic of a pristine fetish worship, though now the hills have modern hero legends attached to them. But in truth the religion of these people is of a very undefined nature, and it is doubtful whether they go much beyond the observance of certain rites at marriages and funerals. Of recent years, however, there has been a growing tendency among the Mer population to split into two sections over religious customs and usages. The Kathat Merats, who have always eaten the flesh of cows and intermarried with Muhammadans, are tending to assimilate more and more with the orthodox followers of Islām. On the other hand the Hindu Merāts, or Rāwats of Todgarh as they are commonly called, are beginning to give a closer adherance to the social and religious rules of Brahmanism, as prevailing among surrounding Rajputs. In 1875 they had agreed to abstain from the flesh of kine and buffaloes, and to excommunicate all transgressors, and recently they have gone further and agreed no longer to eat or intermarry with Kathāt Merāts or Chitās. The origin of the recent movement, which began among the men serving in the Merwara Battalion and other regiments, has been social rather than religious; but it is safe to predict that in course of time the whole of Merwara will become Brahmanised or absorbed in the orthodox religion of Islām.

Of the total number of followers of the Arya Samāj, 331 belong to the towns. There was formerly only one Samāj, but it split into two over the question as to whether animal food was sanctioned by the

Vedas or not.

All the Sikhs, numbering 264, are found in the Ajmer district. They are chiefly employed in the Railway workshops, in the Deoli

Irregular Force and in the Police.

Of the Jains, 14,409 belong to Ajmer and 5,513 to Merwāra, 14,627 being numbered in rural and 5,295 in urban areas. Their standards of right and wrong and their ideas of ultimate reward and punishment are the same as those of the Hindus, but the Jains acknowledge no God, and substitute their tirthankars, or deified saints, 24 in number, for the Hindu devatas. They look forward to an unconscious, passionless, impersonal state, which they called nirvāna, and which can be reached only by liberality, forbearance, piety and remorse in this life. They are strongly averse to all forms of taking life. Like the

Hindus they burn their dead. Their temples, mostly of modern construction are often graceful in design, but are overloaded with tawdry ornamentation. Plaster and stucco are too often preferred to solid stone. In the Nasiyān Jain temple at Ajmer there is an allegorical representation showing the progress of the tirthankars through life to nirvāna.

Of the Muhammadans 56,378 belong to Ajmer and 15,653 to Merwāra. Sheikhs predominate and Pathāns come next. The Muhammadans, as a whole, follow the Korān, supplemented by their hadīs or books of tradition. But in the case of the rustic Deswālis, of Ajmer and Kathāt Merāts of Merwāra, circumcision of the living and burial of the dead is probably the sum total of religious observance.

Christian Missions.

The Christian community has increased by 1,029 since 1891, owing to conversions and to the natural growth among native Christians, who now number 2,362, as against 1,209 in 1891 and 799 in 1881. The principal and oldest Mission is the Rājputāna branch of the Scotch United Free Church Mission, which began work in Beawar in A.D. 1860 as the "United Presbyterian Church Mission," but recently changed its designation upon the amalgamation of that Church with the Free Church of Scotland. A station at Nasīrābād was founded in the following year. The Ajmer station was established in 1862, that of Todgarh in 1863. Deoli received a missionary in 1871. There are now also stations at Jaipur, Udaipur, Alwar, Jodhpur and Kotah. The Mission has nine angle-vernacular schools, six of which, including those at Ajmer, Beāwar and Nasīrābād, are High Schools, teaching up to the standard of the University Entrance Examination. Of these the Beāwar school is the largest with 389 pupils, Nasīrābād comes next with 302; Ajmer has 181. In addition, the Mission maintains 52 vernacular schools for boys and 37 vernacular schools for girls thoughout Rājputāna. Of these, 30 boys' schools and 18 girls' schools are within Ajmer-Merwara, with an average number on the rolls of 2,851. With the exception of grants-in-aid to the Beawar and Nasīrābād High Schools, the Mission bears the whole cost of these educational establishments. The Mission has also an orphanage for boys at Ashāpura, near Nasīrābād, in which there are nearly six hundred, and one for girls in Nasīrābād, containing nearly seven hundred. In connection with the former, workshops have been established for the training of boys as carpenters, blacksmiths, brick and tilemakers, leatherworkers, etc., under the management of a qualified man from the Technical School at Glasgow. A Mission training farm is also maintained in Kōtāh territory. The children in the orphanages are individually adopted by friends of the Mission at Home who pay an annual sum for their support. Government gave a grant-in-aid for children rescued in the famine of 1869, but no such grant is now made. A prominent feature of the Mission is its medical agency. There are five fully qualified practitioners (one of whom is a lady), five hospitals and dispensaries, where some 2,38,000 cases are attended to, and nearly 5,000 surgical operations are performed in the year.

Officially, the district lies within the diocese of the Bishop of Nāgpur. A Government Chaplain of the Church of England is stationed at Ajmer, and there are Church of England and Roman Catholic Military Chaplains at Nasīrābād. The Fordham Orphanage

at Ajmer is managed by the local Chaplain.

As far as the Roman Catholic Church is concerned, Ajmer-Merwāra is considered to lie within the Prefecture of Rājputāna, which was created in 1892, and is administered by the Capuchin Fathers of Paris. The Prefect Apostolic has his head-quarters at Agra. Within the district it has established churches at Ajmer and Nasīrābād, and a native school at Jorepura near Akhri. At Ajmer the Convent of St. Mary Magdalen is a boarding and day school for European and Eurasian girls. It is managed by a Lady Superior, assisted by 12 Franciscan nuns.

The American Methodists established a Mission in Ajmer in 1882. They have now an orphanage in connection with it, which, with that of the Church of England and that of the Scotch Mission, took charge of Ajmer orphans during the famine. The boys' school contains 161 boarders and day pupils, and is graded to the lower middle standard. There is a similar school for girls, with an attendance of 180. The Mission work is carried on in the city and district by a staff of Native catechists, Bible readers and teachers, who did good work in relieving distress during recent famines.

It appears that all the Missions are making steady, if slow, pro-

gress.

The greater part of the population of Ajmer-Merwāra (54·81 per cent.) is agricultural. The industrial population amounts to 17·74 per cent. of the whole, and is chiefly engaged in cotton and leather industries, in the provision of food and drink and in the Railway workshops. General labour, as distinct from agriculture, supports 10·59 per cent. of the population. Personal service accounts for 5·91 per cent. and commerce for 4·21 per cent. The professions and Government service have 2·56 and 2·38 per cent. respectively. Persons of independent means without occupation number only 1·80 per cent. of the total population. To the famine is due an increase in the number of field labourers at the expense of the tenant class, and many occupations were severely affected; among others, many herdsmen, cotton weavers and dyers, cart owners and drivers and professional mendicants had to seek other means of livelihood

The social characteristics of the people in the rural areas are very simple. The ordinary peasants may be described as generally docile and ignorant. Their wants are few and debts very often many. The cultivators as a class are suffering from the effects of recent famines. The condition of the landless labourers approaches the border of the subsistence minimum. They literally live from hand to mouth. In the urban areas the effects of the famine are less felt, and the trading classes are generally prosperous.

The higher classes of Hindus, with the exception of Rajputs and certain Brahmans and Kayasthas, are vegetarians. The staple food

Occupation.

Food.

grains used are wheat, barley, gram, maize, $b\bar{a}jra$ and $jo\bar{a}r$, and various pulses. Wheat is generally used only by the richer classes of the community; the peasantry, except on special occasions, employ the coarser grains for their thick cakes or rotis. These are caten along with dal, whey, uncooked onions or radishes, or with chillies They use only the cheapest kinds of vegetables. The wealthier people spread ghī upon their wheaten cakes or chapāties, and cat them with one or more cooked vegetables, dāl and pickles. Dairy produce is used by all classes. The Muhammadans, Rājputs, Merāts and other castes who cat flesh differ otherwise very little in their dietary from the Hindus. In the towns generally only two meals are taken daily, one between 9 and 10 A.M. and the other before 8 P.M. In rural areas the Jats, Malis, Gujars and Mers eat three times a day. The early meal is called sirāwan, and consists of the food remaining over from the previous day. The mid-day meal is called bhat or rota, and consist of barley or maize bread, with greens and buttermilk. All castes smoke tobacco and eat opium, and present them to friends and strangers coming to see them.

The ordinary dress of a male Hindu of the higher classes consists of a turban, which is generally a piece of silk or cotton cloth 30 to 40 feet long and 6 inches broad, with gold embroidered ends, a shirt (kurtā), a long coat (angarkhā) reaching nearly to the ankles, a loin cloth (dhotī) worn round the waist, and a scarf (dupatta.) The kurtā and angarkhā are usually made of a fine-textured material resembling muslin, and are generally white. Sometimes silk is used. The loin cloth is a long sheet of a coarser material. The Rājput istimrārdārs are fond of wearing embroidered garments, and multicoloured turbans tied in narrow and picturesque folds, and have, especially on festive occasions, a martial appearance, which contrasts pleasantly with the silk and fine linens of other wealthy natives.

The dress of a Hindu female of the upper classes consists of a bodice $(k\bar{a}nchl\bar{\imath})$, a sheet or veil $(orhn\bar{\imath})$ as an upper garment, and a petticoat of chintz or coloured cloth. In the case of Mahajans and Rajput women the petticoat is very full, sixty yards of material being often employed in making it. From 15 to 20 yards of coarse cloth is sufficient for the petticoat of the lower classes. Agriculturists and labourers wear clothes made from a coarse fabric locally manufactured called rezu. They consist of a turban (pagri,) a coat (bakhtari) extending to the waist, a loin cloth (dhoti,) and a sheet (pacheora). Some castes invariably carry a comb, a mirror, a pipe and a flint stone. The comb and mirror are kept in the turban, and the pipe and flint stone in the dhoti. The peasants in Ajmer are usually better dressed than those of Merwara. In rural areas there is little difference in dress between Hindus and Muhammadans. The principal distinction is that Muhammadans wear trousers (paijāmās) and not dhotis. Merats and Chitas, however, though professing Muhammadans, retain the dhotī. Hindus, again, wear their coats with the opening on the right side of the chest, while the Muhammadans have it on the left side. In towns the latter can be distinguished by the buttoned-up coats of various lengths which they wear, together with trousers. A tendency to dress ir European fashion, retaining the turban or a small round cap as head-dress, is apparent in the towns.

The houses of the leading native bankers and traders in the towns, and in rural areas the residences of the leading istimrārdārs of the Ajmer district, are imposing buildings of masonry and stone, with roofs of the same material. As a rule they are two or more stories high, with one or more open courts to admit light and air. Every house has a jharoka or balcony, where the inmates can sit. The windows are small and the dwelling rooms often dark and ill ventilated. Though frequently covered with lavish and beautiful carving and ornamentation, these houses are generally built with little regard to ordinary rules of sanitation. In the reception rooms of the istimrardars the walls are often covered with paintings of their ancestors. In the villages the houses are small mud huts with tiled roofs. The entrance leads into a court-yard, round which are ranged the dwelling rooms of the family, according to its size and prosperity. Sometimes the cattle are kept in a shed in a corner of the court-yard, and sometimes in mud-fenced enclosures outside. The houses are generally clean. Signs, usually a square with the name of a deity entered in smaller squares within it, are painted at the entrance for good luck.

The Hindus burn their dead, with the exception of the Hindu worshippers of Rām Deoji in Merwāra, who bury them. Among Musalmāns burial is the rule. In the case of intermarriage between Hindu Mers (Rāwats) and Musalmān Mers (Kathāts), the wife is buried or burnt according to the religion of the hustand. Gūjars and Jāts have a curious custom of shaving the corpses of male adults before burning

Gymnastic exercises and athletics, sword and lance exercises are the principal games in the towns, apart from cricket, football and hockey, which are confined to the students in educational establishments. Chess, cards and a kind of draughts, known as chopad, are the indoor games. Hide-and-seek, kite flying, blind man's buff, a kind of touch in the ring, and a game called ghota (a kind of hockey), are played by children. In the village of Rāmsar a sort of organized fight with fists between two sections of the villagers takes place once a year. It is called mukkirār.

Among the lighter amusements, singing, playing on the fiddle $(sit\bar{a}r)$ and flute $(b\bar{\imath}n)$ and drumbeating are extensively practised. A kind of rude opera, called the $Rai-k\bar{a}-tam\bar{a}sh\bar{a}$, in which the characters sing and dance all night long to the accompaniment of a drum only, is performed in the streets, and is much appreciated by the people. Among the lower classes in the towns, a circus is always popular. In rural areas the grown-up people have no games. Their ordinary amusement is to assemble in the evening at the village $hat\bar{a}i$, or meeting house, and—sitting in the platform in front of it, usually built round a pipal or bar tree—to pass away a few hours

Dwellings.

Disposal of the dead.

Games and Amusements.

talking and smoking. The village children play games similar to those in urban areas.

Festivals.

The principal festivals are the Holī, the Dewāli, the Gangor and the Tejā-ji-kā-melā (the fair of Tejāji) among Hindus, and the Moharram, the two Ids, and Urs Dargāh Khwāja Sāhib among Muhammadans. The Holi and the Dewali are the two great festivals, held all over the country when the spring and autumn harvests are ripe. The Holi festival is attended with some local peculiarities of an interesting nature. The Oswals of Ajmer have a procession, which they call Rão: a man dressed as a bridegroom and seated on a cot is carried in procession through the Oswal quarter. Men and women play on the Rāo with long syringes, in which they use water and the red powder (gulal), which is the distinctive feature of the Holi. Women from the tops of houses use their syringes very effectively, while the Rão carries an open umbrella to ward off the deluge. In Beawar there is a procession of a much more dignified nature, known as Bādshā, in which a man dressed as a Kājā is carried through the streets, with people dancing and singing and occasionally throwing red powder. After passing through the town, the Rājā is taken to pay his respects to the Assistant Commissioner, Mer «āra.

Another peculiarity of the local celebration of the Holī in Merwāra is the game called ahera, which is held on the first and last days of the festival. A whole village turns out into the jungle, each man armed with two sticks about a yard long, called pokkri or kutka. The people then form a line and beat for hares and deer, and, as they start up, knock them over with a general discharge of sticks. The village headmen provide opium and tobacco, and the bag is cooked and eaten at the feast which ends the day.

The festivals of Dewāli and Dasahra are the same as in other parts of the country. The Gangor festival, which is celebrated by Mahājans, begins a week after the Holī and lasts for 20 days. It is held in honour of the return of Pārvati, wife of Shīva, to the home of her parents, where she was entertained and worshipped by her female friends. Images of Shīva and Pārvati are paraded through the streets with music, and the places where thy are kept are illuminated at night and worshipped. The festival of Tejā-ji is confined to the Jāts. This fair is held about September. The Jāts, both men and women, keep awake the whole of the previous night, and worship the deity by singing songs and bringing offerings of cooked rice, barley and fruit.

The principal Muhammadan festivals of the Moharram and the two Ids are the same as elsewhere. But an exciting spectacle is added by the sword dance of the Indarkotīs, the inhabitants of the Indarkot mohalla of Ajmer city, in which 100 to 150 men, armed with sharp swords, dance and throw their weapons about in wild confusion. The Urs Khwāja Sāhib is a fair held at the Dargāh in the Muhammadan month of Rajab, and lasts for six days. Muhammadans came from all parts of the country to worship at the tomb of the saint, Muin-ud-dīn Chishti, and the yearly number of

pilgrims approaches twenty-five thousand. The proceedings consist for the most part of recitations of Persian poetry of the Sufi School, at an assembly called the malfil. The recitations are kept up until 3 o'clock in the morning, by which time many pilgrims are in the eestatic devotional state technically known as hal. peculiar custom of this festival may be mentioned. There are two large cauldrons inside the Dargah, one twice the size of the other, which are known as the great and little deg. Pilgrims to the shrine, according to their ability or generosity, propose to offer a The smallest sum for which enough rice, butter, sugar almonds, raisins and spices can be bought to fill the large deg is Rs. 1,000. Besides this, the donor has to pay about Rs. 200 in presents to the officials of the shrine, and in offerings at the tomb. The small deg costs exactly half the large one.

When the gigantic rice pudding is cooked, it is looted boiling hot. Eight earthen pots of the mixture are first set apart for the foreign pilgrims, and it is the hereditary privilege of the people of Indrakot, and of the menials of the Dargah, to empty the cauldron of the remainder of its contents. After the recitation of the Fātiha, one Indrakotī seizes a large iron ladle, and mounting the platform of the deg ladles away vigorously. All the men who take part in this hereditary privilege are swaddled up to the eyes in cloths to avoid the effects of the scalding fluid. When the cauldron is nearly empty all the Indrakotis tumble in together and scrape it clean. There is no doubt that the custom of "looting the deg" is very ancient, though no account of its origin can be given. It is generally counted among the miracles of the saint that no lives have ever been lost on these occasions, though burns are frequent. The cooked rice is bought by Mahājans and others, and most castes will eat it.

Unlike the Madras and Bombay Presidencies, where three names are in general used for the identification of a male, the proper name, father's name, and family name, in Ajmer-Merwara as in all northern India, the practice is to use one name only. Occasionally it happens that two persons with the same name but of different castes, add their fathers' names for distinctive purposes; but this is raic. Each person has his zāt or family name, which in rare instances is derived from the place of his ancestors, but it is not used in addressing him

either by speech or by letter.

Every male of the "twice-born" classes has two names (a) the janam-rāsi-nām, only used at weddings, at death, and when the stars are consulted, and (b) the bolta $n\bar{a}m$ by which he is generally known. The system of nomenclature is simple, and the names are generally of religious origin, or are given out of affection or fancy. Instances of the former are Har Lāl, Rām Singh, Shiv Charan, and of the latter Sundar Lāl, Gulzāri Lāl, and Pritam Chand. But there is an almost infinite variety of such names. Among the usual suffixes attached to names it may be remarked that Chand, Mal, Bhan, Pal and Karan are principally used by Jains. On the other hand Datt (given) is exclusively a Brahman suffix.

Names and Titles.

Among the agricultural classes the males usually have one name only, which is a diminutive of a name of a higher class. For example, where a Mahājan or a Brāhman would call himself Birdhi Chand, Bherun Ram or Udai Mal, the agriculturist, whether Jat, Gujar, Mali or Mer, would be known as Birdha, Bherun or Uda. Except in rare instances the lower classes never use the suffixes Ram, Lal, Chand and the like. Among them the name of the wife often corresponds with that of her husband, as Udi the wife of Uda.

Childrens' names take diminutive form in "u," as Moru, Phūlu. Occasionally Muhammadan names are used by Hindus and Jains, apparently out of reverence for the Muhammadan saint, whose Dargah is at Ajmer. Or it may be a legacy of the conciliatory policy of Akbar. Some sections of Muhammadans, who were originally Hindus,

have retained to this day their Hindu family names.

Among the names of places, Nasīrābād is the only instance of the suffix "ābād." Many villages have names ending "wās," meaning place of residence, and in "wāra," which means enclosure. Examples

are Māngaliāwās and Bāndanwāra.

CHAPTER IV.

AGRICULTURE.

Ajmer and Merwara are physically very distinct from each other. In Ajmer, plain country is the rule and hills the exception. There are several ranges of hills, but they spring more or less immediately from the plains, and there is little cultivation among them. The Pushkar pargana, cut off from the rest of the district by the Nag-Pahār range, possesses a very peculiar character. It is entirely made up of hillocks of pure sand interspersed with depressions of rich soil. The sand hills absorb and retain the rainfall, prevent evaporation. and allow the water to percolate slowly to the lower ground. Here streams run but a short distance before they are finally absorbed. The soil is too sandy for irrigation tanks; but the hills contain the only two important natural lakes in the district. The Gangwana pargana occupies the plain between the northern extension of Nag-Pahar on the west, and the Srinagar and Kishangarh hills on the south. This plain drains to the north towards the Sambhar lake; the well land lies mostly along the main drainage channel, and, except under the hills to the south and west, there are few tanks. Along the lines where wells can be made, and under tanks there is much good cultivation, but in its general character the country is a broad unirrigated plain. East of the Srinagar hills and stretching south to Nasīrābād is the Rāmsar pargana. The broad shallow valleys or depressions in the plain offer better capabilities for irrigation than in Gangwāna. In some parts, especially towards Ramsar, there is much salt in the soil, as the old salt mounds or agars scattered over the country show. In Rajgarh, south and west of Ramsar, the villages under the hills have light and sandy soil, while in the plain there are some excellent tanks and good well cultivation. The plain of the Ajmer parguna is ill-adapted for tanks, but almost all the villages have wells dependent on the percolation of the Sagarmati, in which the supply is constant and good.

In Merwāra, in contradistinction to Ajmer, the hill country is the rule and the plain the exception. The two ranges of the Aravalli which meet near Jawāja, enclose a valley which tapers from its extreme width on the north to a point at the south. In this valley, about two miles west of the main range of the Aravalli, runs a low range through which in former times the drainage had forced for itself numerous passages. By blocking these a line of magnificent tanks from Dilwāra on the north to Lusāni II, on the south, has been made. Below these tanks villages are numerous and the

population is dense.

General Conditions.

South of Jawaja, except the outlying villages of Jaitgarh and Bheron Khera in Mewār, for some 35 miles, until Gudha Lakha is reached, the whole breadth of the district is a confused mass of hills, and the cultivation is confined to the valleys and terraces made on the hill-sides. There are many tanks, but few of any size. For some ten miles south of Gudha Lakha there is a narrow plain on the Mewar border bounded still on the west by the Aravalli range. South of Barjāl again the whole district, including the outlying villages, is hill. Tanks in this part are rare, and well cultivation the rule. The ranges culminate in the peak of Goramji, south of Todgarh, which rises to more than 3,000 feet above the sea.

In general, the cultivated soil of both districts is composed of a mixture of stiff yellow loam and sand, in proportion of one to two. No superficial portion of soil is absolutely clayey, and alluvial soil is only found in the beds of artificial tanks. In tracts where euphorbia are common, carbonate of lime is found in large quantities. The richest soil in the province is among the sand hills of Pushkar, where sugarcane is grown without irrigation. But elsewhere all the most valuable cultivation is irrigated either from wells or tanks. The rainfall throughout is too precarious for the dry cultivation to be much considered by the people. Where it is carried out, the fields are sometimes surrounded by low embankments to retain the rain moisture as long as possible. All dry crop land is classed together as bārāni, and no sub-classification has so far been attempted. Irrigated lands are classed as chāhi, tālābī and abi, according to the means of irrigation employed.

As the slope of the land is in every direction away from these districts, there is no permanent under-current of percolation to feed the supply in the wells. Both they and the tanks are dependent upon the rainfall. In Ajmer, where the beds of the nallas are sandy, a sufficient amount of water is absorbed during the rains to supply the wells on either bank; but wells can only profitably be made within a short distance of the stream. In Merwara the beds of the drainage channels are rocky and the slope of the country greater. Tanks are essential to catch the rainfall, which would otherwise flow off rapidly into Marwar and Mewar, and not give the wells any chance of filling by percolation. In many parts the soil is thin and the rock

very near the surface.

Among the hills and valleys of Merwara there is a system of petite-culture. Small fields have been made with great labour by terracing the hill sides and building up the lower end with stone walls to prevent the soil being washed away. Where the walls are sufficiently substantial to act as a dam and retain moisture, these fields, locally known as paraband are classed as abi. Abi strictly means land in the beds of tanks, which is everywhere cultivated

after the tanks have dried up in the spring or hot weather.

Halsara.

In the dry crop lands in many villages of Ajmer there exists a system-shifting cultivation called halsara, a survival of the original idea that the dry crop land was of little value and could be cultivated

by any one. The custom is that a village sharer or cultivator takes a plough each year in the halsara area, for which he pays a sum fixed by village custom, ranging from Rs. 2 to Rs. 7. In exchange he is entitled to sow a certain area, which again varies by village custom, between 6 and 28 acres. The owner of the plough settles on the bit he fancies, and as long as he uses only one plough, no one enquires what area he occupies. When the land is broken up, til is sown, or if the season promises exceptionally well, gram, and after this the land remains for one year the private land of the sharer, in which he may grow joār. In the third year the cultivator abandons this, and goes to another spot, and the first piece lies fallow until someone else takes a fancy to the whole or part of it. Such a custom could not exist in a tract where rain is plentiful and dry crop land valuable. Even in Ajmer halsara possession is in many villages crystallizing into ownership.

As the soil is light and deep ploughing exceptional, a single pair of bullocks is generally sufficient for draught. The agricultural implements are similar to these used in the United Provinces, and have no distinctive features. No new appliances have been introduced into the districts. In the kharif season succeeding the great famine of 1899-1900 hand ploughs drawn by men were tried, to make up for the deficiency of cattle. Some land was brought under cultivation by their means, but they never became popular, and have now disappeared.

According to the census of 1901 the agricultural population amounted to 2,54,763, as against 2,62,551 in 1891. The decrease was due to the disastrous famines of the decade. In Ajmer the agriculturists numbered 53·3 per cent. of the total population. The percentages of actual workers and dependents were 63·5 and 36·5 in Ajmer, and 62·3 and 37·7 in Merwära. The cultivators are principally Jāts, Gūjars, Mers, Merāts and Rāwats, whose numbers were returned in 1901 as 27,946, 36,248, 21,649, 8,554 and 32,209 respectively. The Jāts are the best cultivators, and the Gūjars come next in this respect.

In preparing for the *kharif* harvest, the land is ploughed up towards the end of April and beginning of May. It is then left till after the first rains have fallen, when it is re-ploughed and taken under various processes till it becomes ready for the sowing. For rabi the ploughing is generally done in September. The land thus ploughed is allowed to stand for a month, when it is ploughed a second time, and harrowed before the seed is sown.

In dry crop areas manure is not used, but in the irrigated lands, owing to the general poorness of the soil, especially in Merwāra, heavy manuring is absolutely necessary. Much of such land in both districts is cropped twice in the year; there is little scientific rotation and no rest, so the necessity is sufficiently apparent. The salty soil of the Rāmsar pargana gives excellent crops when heavily manured, but without it is almost worthless. A full manuring of chāhi or tālābi lands is considered to be 360 maunds to the acre every third year, but

Agricultural Implements.

Agricultural Population.

Sowing.

Manure.

this is a rate not often reached. The greater proportion of the cattle in the district are kept for purposes of manure. That of sheep and goats is more valuable, but their destructive habits made them unpopular until the heavy losses of cattle during the recent famine. Ashes, house sweepings and vegetable manures are also used to some extent. Nightsoil is in considerable demand as manure among the villages near the towns: it is not available elsewhere.

Principal Crops.

The principal crops, in order of extent of area cultivated, are maize, jour, or great Indian millet, barley, cotton, oilseeds, bajra, or bulrush millet and wheat. These occupied respectively 19.9, 18.4, 16.1, 10.1, 7.1, 6.5, and 3.5 per cent. of the average cultivated area during the ten years ending 1899-00. Maize is sown in June and July and is harvested in October and November. Where irrigation is available it is watered two to three times. Its average out-turn in ewts. per acre is 1.10 in barani land and 7.34 in irrigated land. It is rotated with barley and cotton, the land remaining fallow for the rabi harvest before the cotton is sown in kharif.

Barley is always a rabi crop. It is sown from 15th October to 15th November and is reaped in April. In irrigated lands it is watered from three to five times, and yields an average of 7:34 cwts. per acre. In dry crop lands the average out-turn is only 1.46 cwts. Joar is only grown as a dry crop; it is sown in June and July and harvested in October and November, and has an average yield of 173 cwts, per acre. $B\bar{a}jra$ is sown at the same season and also in dry

lands only; its average yield is also 1.73 cwts. per acre.

Rotation of Crops.

Cotton, though not first in point of area, gives of all the crops the most valuable return to the cultivator. It is sown in June and July, and the seed is mixed with cowdung and ashes, with the idea of increasing its germinating power. The crop is picked in November and December, and gives an average yield of 3:11 cwts. per acre in irrigated and 1:10 cwts, per acre in unirrigated land. In the former it is watered from five to seven times during the season. After the cotton is reaped the land is always left fallow for one harvest before maize is sown on it, as already described. Til is sown in dry lands in July and August, and is reaped in November; its average yield is 1 cwt. per acre. Gram is a rabi crop, and is sown in dry crop lands in October and harvested in April, with an average out-turn of 1.73 cwts. per acre. Wheat, also rahi, is sown in late October and early November. In irrigated lands it is watered from three to five times before the harvest in April, when its yield averages 7.5 cwts. per acre. In barani land the average out-turn is only 1.73 cwts. It is rotated with maize and barley, after which, with one intervening kharif fallow, it is again sown.

The other crops (food as well as non-food) are very limited. Sugarcane cultivation is confined to the rich soil of the Pushkar valley, where it grows without irrigation, and gives an average return of 8.84 cwts. per acre. Poppy is cultivated in the Todgarh tahsīl as a rubi crop in irrigated lands, where it is watered from six to eight times. The average yield of poppy heads is 2.75 cwts. per acre.

Chillies are sown as *kharif* in wet crop lands. They require much irrigation, from 15 to 20 waterings, but the average out-turn of 2:19 cwts. per acre gives a good profit to the cultivator. The remaining

crops deserve no special mention.

In all cases the cultivators endeavour to retain the best grain for seed. There is a prejudice in favour of local seed grains of all kinds as against foreign varieties. Seed of the previous year's crop is always used, as the local belief is that it loses some of its germinating properties if kept for longer. There are no model farms in the district, one started by Mr. Saunders having proved a failure; and it is feared that the influence of the Agricultural Department's publications has not done much towards the introduction of improved systems or new varieties.

Extension and decrease of cultivation is merely synchronous with good or bad seasons, so far as recent years are concerned. In the earlier history of the district, however, when tanks were being built and Merwara was being surveyed, considerable extension took place. There were 58,079 acres under irrigation in 1884, as against 51,949 in 1874, and the unirrigated area cultivated had risen from 1,19,467 acres to 1,32,242 in the same period. But after the great famine the total irrigated area in 1902-03 had fallen to 37,046, and the unirrigated cropped area to 1,33,686 acres. The cultivation of poppy has decreased in Todgarh since the introduction of the Excise Rules, while the demand for raw cotton and its profitable return have caused its cultivation to increase steadily in popularity. Its average of 12,426 acres between 1881-1890 had risen to 21,011 acres in the next decade. Famine and scarcity, however, caused a fall of these latter figures to 12,756 acres in 1902-03. In this year, while in some cases the area under cultivation of a particular crop had increased, the production had decreased; this was markedly the case with wheat, barley and cotton.

Fruit and vegetable production is chiefly confined to a few gardens cultivated by malis near Ajmer, although some vegetables are also grown in the municipal gardens at Beawar. The fruit is generally poor in quality, and no great variety of vegetables is obtainable. There are no model fruit or vegetable gardens in the

The introduction of the Land Improvements Act of 1883 and of the Agriculturists Loans Act of 1884 has, by making money available at a reasonable rate of interest, done much to modify the effects of recent famines. When the private lenders refused to advance money for seed and bullocks or for wells, and credit was severely contracted, the working of the two Acts was of the utmost value. Since they came into operation until 1902 Rs. 5,59,653 had been advanced under the Land Improvements Act, and Rs. 5,55,734 under the Agriculturists Loans Act. In good seasons punctual repayment of instalments is usual, but the famine, while making large advances necessary, made prompt repayment impossible, and at the end of September 1902

Extension and Decrease of Cultiva-

Land Improvement & Agriculturalists Loans Acts.

Rs. 2,04,106 were outstanding under the Act of 1883, and Rs. 2,08,131 under the Act of 1884. Under the former Act 917 new wells had been constructed at a cost of Rs. 74,984, which irrigated 1,951 acres; 4,230 old wells were deepened and repaired at a cost of Rs. 2,46,662, with an irrigable area of 9,328 acres; while 206 other irrigation works were constructed or repaired, costing Rs. 2,53,415 and irrigating 6,488 acres. The latter Act, supplying money for maintenance, seed and purchase of cattle, has formed one of the most valuable recuperative agencies after the ravages of famine.

Indebtedness.

The amount of private indebtedness both in Ajmer and in Merwāra is enormous. Accurate statistics are not available, but, from inquiries made in Ajmer in 1900-1901, it is believed that the amount of private debt is over Rs. 10,00,000. That in Merwāra is probably no less. In 1885, at the time of the last settlement, it was calculated that 30,319 acres (including 19,778 acres of land mortgaged at the previous settlement) of land were mortgaged for Rs. 12,38,755 and 3,857 maunds of grain.

Recent calamities therefore, have increased the indebtedness by about two-fifths. The Rājput estate holders, who cannot encumber their estates beyond their own lives, have a large amount of private debt, notwithstanding, and owed to Government for loans advanced in the famine the sum of Rs. 1,56,132, part of which has, however, been recently remitted. In 1872 a regulation was passed for their relief, and their debts, amounting to 7 lakhs, were taken over by Government at 5 per cent. interest. This debt to Government had been almost entirely liquidated before the recent famines made further loans necessary. The rates of interest on private debts vary from As. 8 to Rs. 2 per cent. a month. When given in kind it amounts to about one-third of the produce of the mortgaged lands. The large majority of money-lenders belong to the professional money-lending classes.

Years of famine give an opportunity to the grain-dealers to secure what would otherwise be bad debts. There is always a large amount of unsecured debt, which has descended from father to son, or consists of extortions of the grain-dealers which they could not recover in a civil court. A hungry man is not over-cautious as to what he puts his name to, and the grain-dealers find their opportunity in the necessity of the cultivators, who, if they require food, are obliged to sign bonds or mortgage their lands for the full amount which the grain-dealers state as due to them. Mortgage is generally of a usufructuary kind, and formerly the mortgagee only rarely took possession of the land. But of recent years it has become more common, the land being handed over to a third person for cultivation, owing to the difficulty found by the mortgagee in recovering his dues from the original mortgagor, who is protected by the courts from paying more than a certain amount of the produce by way of interest. Sales of land in execution of decrees are forbidden, except with the sauction of the Commissioner. In the present state of public credit, it is

difficult to see how Agricultural Banks can succeed in the province.

The question is, however, receiving attention.

Owing to the want of any large pastures and permanent water supply, the district is not well adapted for systematic cattle and horse breeding. Formerly large numbers were kept, and were grazed upon the hills and village pasture lands during good seasons, and were taken to Malwa and more favoured districts when the rains fuiled. The enclosure of the forests, however, tended to reduce their number to what was actually required for agricultural purposes, as the village pastures became more limited. But on the other hand the opening of free grazing in the forests leaves a valuable resource to save what cattle there are in famine times. Of recent years restrictions have been put by many Native States upon cattle immigration for grazing purposes, and emigration when necessary is usually in the direction of the United Provinces. There is no indigenous breed of cattle deserving special mention, and the cultivators get their cows covered by bulls of various breeds. The cattle, as a rule, belong to four stocks, the Rendi Khān, Dhāora, Mārwāri and Mewāri. The first breed supplies the best milch cows, while the last three are stronger and are generally used for field work. The average price of a bullock is Rs. 30, of a cow Rs. 25, of a she buffalo Rs. 40 and of a calf of either species Rs. 15. A scheme for stationing Government bulls in central villages to improve the breeds of cattle is under contemplation.

Horse breeding is rare, and more so since the recent famines. Until recently efforts were made to encourage it by keeping an Arab stallion at the Veterinary School at Ajmer, and by offering rewards at Pushkar fair for colts and fillies sired by him. The average

value of the local pony is about about Rs. 50.

Sheep and goats are kept everywhere, especially since the want of cattle has increased the demand for other manure. They are very hardy and are little affected by famine. Their average value is

Rs. 3 apiece.

The most important horse and cattle fair is held at Pushkar in November. Animals come from all parts, prizes are given by Government from the proceeds of the temporary tolls, and selling and buying are usually brisk. Two cattle fairs of minor importance are held at Beawar and Kekri at the time of the Teja celebrations in early

September.

Mention must here be made of the Rajputana Veterinary School, which was established in Ajmer in 1894, with the idea of supplying veterinary assistants for Rajputana. At the same time a Civil Veterinary Department was started with a view to improving the breeds of horses and cattle. A European officer holds the combined appointments of Principal of the Veterinary School and Superintendent, Civil Veterinary Department. He teaches medicine and surgery in the school, where he is assisted by three lecturers on bovine pathology, anatomy and physiology, and chemistry and materia medica, respectively. A hospital is attached to the school. Since 1894 131 veterinary assistants have been trained, and 4,774 animals Cattle.

have received treatment. A farrier teaches men who are sent from Native States to learn farriery. Under the Superintendent, Civil Veterinary Department, there are veterinary assistants attached to the Beāwar Municipality and the Ajmer District Board. The Superintendent goes on tour every year to inspect veterinary dispensaries, to visit horse and cattle fairs, and to give advice regarding horse and cattle breeding. He also investigates any cases of outbreak of contagious disease, and inspects the horse and cattle boxes and trucks on the railway. Government have recently decided to abolish the School, and place Räjputāna under the Civil Veterinary Department of Baluchistān and Sind.

Irrigation.

It is unnecessary to recapitulate the various physicial and meteorological conditions which make irrigation so important a factor in the agriculture of the province.

Tanks.

The idea of tank embankments was one which early presented itself to the minds of those conversant with the district. The Bīsla tank was made by Bisal Deo Chahān, about the year 1150 A.D.; his grandson, Ana, constructed the Anāsagar; the tank at Rāmsar was built by Rām Deo Pramar. In Merwāra the large tanks of Dilwāra, Kālinjar, Jawāja and Balād date from long before our rule. They have wide earthen embankments, generally faced on both sides with flat stones, and closing gorges in the hills. With ordinary care they will last as long as the hills which they unite, and their construction furnishes a substantial proof that before our rule the principles of subordination and co-operation were not unknown in Merwāra.

The tank embankments at present number 531, of which 377 are managed by Government, the remainder being in charge of the villages or the municipalities. There are 1,802 tanks in istimrāri and $j\bar{a}g\bar{i}r$ lands, which are managed as part of the estates: a few tanks constructed within $j\bar{a}g\bar{\imath}r$ and minor $istimr\bar{a}ri$ lands by Government are managed by the Public Works Department and are included in the previous totals. The majority owe their existence to Colonel Dixon, who ruled Merwara from 1836 to 1842 and the united districts from 1842 to 1857. He gives a very full account of them in his "Sketch of Merwara," Chapter XII, et seq. The best site for an embankment is a narrow gorge, where, by uniting the hills on each side, the drainage of the valley above can be stopped and the water thrown back to form a lake, which will irrigate direct by a sluice, and feed the wells below by percolation. Such sites are, however, limited, and since the famine works of recent years nearly all of them have been utilized, though in many cases the embankment is capable of much improvement. In the open parts of the districts, where Colonel Dixon made a large number of tanks, the embankments run a considerable distance from one rising ground to the other. Some are nearly two miles in length. The centre portion of the dam arrests the flow of a drainage channel, and the water spreads on each side to the rising ground. Every tank is provided with an escape to prevent the water topping the embankment during floods. These tanks are generally very shallow, and seldom retain any water after

the autumn harvest has been irrigated. Colonel Dixon attempted at first to form earthen embankments, but the oil is so devoid of

tenacity that the plan was early abandoned.

There are four kinds of embankments in the districts. First, a wall of dry stone backed by an earthen embankment and faced with a coating of mortar, generally combined with a dry stone retaining wall; secondly, a masonry wall backed with earth, the masonry and embankment being of greater or less strength in proportion to the weight of water to be retained. Thirdly, an earthen embankment, with or without a masonry core wall. Fourthly, a wall of masonry without any embankment. This last is the best, and is adopted in the more hilly parts of the district, where the gorges do not exceed 100 yards in width. Similar to these are the small masonry weirs thrown across a nalla in its course through the hills, in order to ensure a supply to the wells on either bank.

The embankments of the Government tanks are in charge of the Public Works Department. They are inspected annually in December, when estimates for necessary repairs are submitted for sanction. It was noted at the last settlement that new sluices and new ducts were very necessary in many cases. Thus the ducts of the large Rāmsar tank were formerly laid out on no system; for long distances two and even three and four ducts were running side by side, owned by different interests, and each wasting water by overflow, evaporation and percolation. Of recent years this has been remedied. Ducts are fed in general by the gravitation flow of the water from the tank, but in cases of deficiency the water is often raised by lifts to the mouth of the sluice.

In the time of Colonel Dixon the water revenue was added to the ordinary assessment of the village, and both were paid together. The system was to fix 6 per cent. upon the cost of construction of any tank within the village and add the amount to the previous assessment.

At the time of LaTouche's Settlement a change was introduced in the case of the first class tanks in Beāwar and Todgarh, and almost all the tank-irrigated villages in Ajmer. In their case the water revenue was entirely excluded from the khewat, and the villages were assessed at so much, plus a lump sum for water revenue. This lump sum was to be made good from the fields actually irrigated each year, unless its incidence on the irrigated area exceeded a certain fixed maximum, or fell below a certain fixed minimum. Out of a total of Rs. 55,432 water revenue, Rs. 37,172 was thus assessed. The balance, chiefly derived from smaller tanks, remained under the former fixed system, by which the water revenue, though separately recorded for the whole village and for each holding, was included in the khewat, or record of individual responsibility. In 1885 Government tank works were grouped into crop rate tanks, variably assessed tanks paying a fixed assessment maintained by Government, and tanks paying a fixed assessment and repaired by the villagers. There are now 45 crop rate tanks, 80 under variable assessment, 243 paying

Irrigation Revenue and Expenditure. fixed revenue, and 9 paying on a combination of the variable and fixed systems. In crop rate tanks the area irrigated is recorded each year, and assessed to pay revenue at certain rates which vary as the crop grown. In the variable system there is a rate which varies between a certain maximum and a certain minimum according to the standard area, which is fixed. The assessment is based on the total tank area, whether irrigated or unirrigated in the autumn harvest. In the spring harvest the water revenue is assessed at full rates if the tank water is above sluice level on 15th February. If the water is below sluice level on that date the revenue is assessed on the number of irrigations given. In the fixed assessment a lump sum is taken irrespective of the area irrigated. Besides the land irrigated by flow from the tanks, called $t\bar{a}l\bar{a}bi$, there is also yearly cultivation in the dry beds of many tanks called abi. The assessment of this class of land is also both fixed and variable. At the last settlement 16,106 acres of abi land came under the former system and 7,176 under the latter.

The average annual receipts from water revenue during the ten years ending 1890, amounted to Rs. 58,170.5. In the next decade the average had, owing to suspensions and remissions on account of famine, fallen to Rs. 56,869.9. In 1902-03 Rs. 35,626 were collected, while Rs. 38,900 were outstanding as arrears. These figures include the water revenue from well-irrigated lands situated within the limit of the tank areas. Before 1880-81 the total capital expenditure on tanks in Ajmer-Merwāra amounted to Rs. 14,23,794. Between 1880-81 and 1889-90 Rs. 2,22,887 were spent. In the decade ending 1900 the expenditure, owing to the large construction works carried out during famine, rose to Rs. 11,78,529. In 1902-03 the capital expenditure on tanks was Rs. 89,439. Up to the 31st March 1903 the total capital outlay had been Rs. 30,89,122. Except in years of drought the works average a return of about 3 per cent. on their capital cost.

Wells.

There are few permanent wells in the districts; in general they, like the tanks, depend upon the rainfall percolation for their water supply. In the Ajmer district the beds of the nallās are sandy, and a sufficient amount of water is absorbed during the rains to supply the wells on either side. In Merwāra, where the beds are rocky, the wells depend more upon the water which is retained in the tanks. Percolation tends to keep water in the wells as long as there is water in the tanks. When the water of a tank dries and the subsoil water sinks, the water level in the dependent wells sinks also. It is not, however, always the wells lying directly below a tank that benefit most from it. Percolation frequently, though by no means universally, shows itself along lines of natural drainage, but it always works along the line of least resistance, which may or may not be reflected on the surface. Instances of the latter frequently occur. In Bir there is some improvement to the wells for a short distance below the tank, but the same result shows itself ten miles away in Udaipur and Tikāorā in the Kishangarh State. In the British territory between there is no change, so that the water passes under Srinagar by

a natural syphon. The effect of the Kālinjar tank is not felt so much in the wells below it to the west, but the wells in the village of Pālān in Mewār, which lies to the east and is separated from it by the main range of the Arāvallis, depend on it for their water supply. Other cases could be cited.

A few wells which may, perhaps, be called "permanent" exist in both districts. But the term is here merely relative. The springs from which they derive their water depend ultimately upon the infiltration of rain water, and as there is no supply from the outside, it only needs a long enough drought to dry up every well in Ajmer-Merwāra. These comparatively permanent wells are most common at the foot of hills, such as Rājgarh and Kothāj of Ajmer, or along stream beds draining from such hills as those near Beāwar. In no place are they numerous. Gopālpura in Beāwar with seven, and Chāpliān in Dawair with twenty, are the villages best off in this respect.

Where the water is plentiful the Persian wheel, or dhimda, is generally used to draw it from the well. In other cases the ordinary water lift by bullocks with the long pull rope and bucket, called charus is employed. There are two kinds of charus distinguished locally by the names potliā and soondiā. The former requires four bullocks and three or four men to work it, and can irrigate an acre of land in about six hours. The latter, with only two oxen and a single attendant, takes twice as long. Irrigated fields are divided into small beds, some 60 or 100 per bigha, in order to distribute the water. Some five years ago an attempt was made to introduce iron buckets in place of the charus, but they were not found satisfactory. A kacha well, without masonry, averages about Rs. 50 in cost. The price of a masonry well ranges from Rs. 200 to Rs. 700, according to its depth, diameter and the nature of the soil. At the last Settlement there were 2,879 wells dependant upon Government

In 1901, so far as can be ascertained, the total number of wells in use in Ajmer-Merwāra (khālsa) was 13,655, of which Ajmer had 6,511 and Merwāra 7,144. From these, 28,033 acres were irrigated, paying assessment to Government of Rs. 43,193. The average irrigated area per well was, therefore, 2.05 acres, with an average water rate of Rs. 1-8-7 per acre.

tanks, out of which 2,622 were assessed to water revenue.

RENTS, WAGES, AND PRICES.

Rents.

The larger proportion of Ajmer-Merwara, with the exception of the istimrāri areas, is cultivated by resident landlords. Where tenancy exists, it is generally that of tenants-at-will or of exproprietary tenants. The latter are those who have mortgaged their lands, but are continued in possession under the terms of the mortgage. In all istimvari estates cultivators are considered to be tenants-at-will until the contrary is proved. They generally, however, hold under contract leases, and pay rent at fixed permanent rates, and are liable to ejectment only on breach of the terms of the contract. Rent is determined by agreement between landlord and tenant, and is usually paid in kind. The landlord's share varies from a half to a quarter of the produce of the land, according to the quality and capacity of the holding and the terms of the tenancy. So in the case of land irrigated from wells, where the landlord pays Government dues and supplies seed and manure, he gets half the produce. If he pays Government dues only, he gets one-third. If he pays nothing at all towards Government dues or expenses, his share will not exceed a quarter. In tank lands the landlord gets half produce where he pays Government revenue and half the expenses. If he pays the Government dues only he receives a third. In the case of dry crop land a third of the produce is the usual share of the landlord. Rent in kind is called banta. Its actual quantity is decided either by appraising the standing crops, or by dividing the produce after the grain has been threshed out. The former system is known as kānta and the latter as latāi. On certain crops, however, rents are paid in cash. In cases of cash rents the standing crop is measured at each harvest, and the rents are calculated either at fixed rates mentioned in the Record of Rights at the Settlement, or according to special rates agreed upon between landlord and tenant. The cash rents vary from Rs. 2-8 to Rs. 8 per acre according to the crop. In Ajmer among the *kharif* crops cotton, maize and sugar-cane in well lands usually give rent in cash. In the *rabi* season, cash rents are only paid for lands which grow melons, vegetables, garden produce and lucerne. In the case of opium the rents are paid partly in cash and partly in kind, and vary from Rs. 10 to Rs. 20 per acre. In Merwara rents paid in kind are almost universal; cash rents are rare.

The only local legislation regarding rents refers to exproprietary tenants. By a regulation passed in 1877, their rents are fixed at one-third less than the ordinary rents for similar lands in the vicinity. These rents are, however, usually fixed so as to bring to the mortgagee landlord interest at a specified rate on the money advanced by him, and are independent of the total produce of the land. They are locally called

ghūgri, and are due even if the lands remain uncultivated. Exproprietary tenants cannot be ejected for non-payment even by decree of a Civil Court, without the sanction of the Commissioner. Owing to consequent difficulties in recovering their dues, the tendency is becoming more and more for money-lenders to advance money only on terms of mortgage with possession. They then employ third persons to cultivate the land as tenants. In the Settlements a half of the gross produce is calculated as cost of production, one-sixth as Government revenue, and the remaining one-third as the landlord's profits. There is no tendency visible for cash rents to displace rents in kind. In the present circumstances the latter system seems both to tenants and landlords to possess the greater advantages. Under it, enhancements and abatements due to changes in area, to improvement and deterioration, or the

rise and fall of prices, are adjusted automatically.

The average daily wage of an unskilled labourer is 2 annas in rural areas and between 2 and 4 annas in urban areas. The wages of unskilled labour have not changed since 1881. They are usually paid in cash, but agricultural labourers are sometimes paid in kind, receiving grain of the equivalent value of the cash payment. During the three famine years ending in 1901, the dominating money wage has been that paid on the Government relief works, which is scientifically calculated and gives the worker enough to live on, and probably, when a family is on the works, a margin for saving. In the towns, masons, blacksmiths and carpenters get an average wage of 4 to 8 annas a day, as against $5\frac{1}{3}$ to $10\frac{2}{3}$ and $5\frac{1}{3}$ to 8 annas in 1881 and 1891 respectively. The Railway Locomotive and Carriage and Waggon Shops in Ajmer give employment to a large number of skilled hands. In the Locomotive Shops the maximum rates of their wages vary from Rs. 7-8 per day, in the case of European fitters to 5 annas a day in the case of strikers, the minimum varying from Rs. 2 to 2 annas. In the Carriage and Waggon Shops the daily wage varies from a maximum of Rs. 2-12 to 3 annas a day, the minimum being from Re. 1 to 2 annas according to the class of labour. The maximum daily wage paid in the Krishna Cotton Mills at Beawar is Rs. 1-4, and the minimum is 1½ annas. rural areas carpenters, blacksmiths, leather makers and other village servants get allowances of grain from the villagers in return for their services. Thus, carpenters, potters and blacksmiths are given 15 seers of grain per plough at each harvest. If a cultivator owns a well with a Persian wheel he has to give then 30 seers, owing to the greater amount of labour required for repairs. At the reaping time they are given in addition by each cultivator a sheaf of corn weighing about 5 seers. When the seed is being sown they receive a contribution of 2 seers of seed grain from each cultivator. If, however, a carpenter prepares a new plough for a landholder, he is given 2 annas extra for his labour. If he makes a new cart he is paid separately for it, or is fed for a time in lieu of payment. Tanners or balāis, for repairing shoes and assisting in the storage of manure, get from 5 seers to 20 seers of grain per harvest from each household. If they have to supply new shoes and other small leather articles, the allowance per harvest is from

Wages.

20 seers to a maund. If a new leather bucket is prepared, the cultivator has to feed the tanner in addition. The food allowance, consisting of a mixture of wheat, $gh\bar{\imath}$ and gur is called lash. Barbers are given 10 seers of grain per harvest for every adult male in the village. Drummers (dholis) get a share of grain per house per harvest, and the priests receive a smaller allowance. In addition, all are given something at the $Hol\bar{\imath}$ and Devali festivals and upon marriage occasions.

As wages in rural areas are to so large an extent paid in kind, they have not been much affected by the price of food grains. There has been no extension of the railway system since 1879, nor have factory and mining industries developed so as to affect wages. Times of scarcity and consequent temporary rises in prices have not resulted generally in increase of wages. The ordinary work available decreases, while the demand for it increases. The labourer is willing to accept his normal or even a decreased money wage in order to secure employment at all. As already noticed, in such times the price paid for labour on Government relief works, as representing the subsistence minimum, becomes the dominating wage. Only the wages of domestic servants in towns have risen considerably of late years.

Prices.

The prices of the staple food grains in 1902-03 at Ajmer, Beāwar and Todgarh respectively were in quantity per rupee:—wheat, 12 seers 11 chittāks, 13 seers 3 chittāks and 12 seers 3 chittāk; barley, 16 seers 11 2 chittaks, 17 seers 82 chittaks and 16 seers 2½ chittäks: joãr, 17 seers 13 chittäks, 18 seers and 19 seers 7 chittāks; bajra, 16 seers 6 chittāks, 15 seers 82 chittāks and 16 seers 31 chittāks; and maize, 18 seers 71 chittāks, 18 seers 12 chittāks and 18 seers 11 chittaks. In this year deficient rainfall had produced famine conditions in Merwara, and prices on the whole were higher than in the previous decade. It is noteworthy, however, that the absence of octroi and the prevalence of the saudu system of contracts among the merchants of Beawar made the grain prices in Merwara generally lower than those in Ajmer. Taking maize as a representative food grain of a large bulk of the population, we find that during the last three decades its average prices at Ajmer, Beawar and Todgarh respectively varied as below: between 1873 and 1880 they were 21 seers 12 chittāks, 23 seers 1 chittāk and 24 seers 15 chittāks respectively; between 1881-1890 they where 23 seers 3 chittaks, 25 seers 9 chittaks and 28 seers 12 chittaks. Betweeen 1891-1900 the average price rose considerably, being 18 seers 12 chittaks, 20 seers 11 chittaks and 22 seers 10 chittaks respectively. From 1871 to 1890 there had been a long series of prosperous years, the railway had given improved communication, and cultivation had extended, so prices ruled easy. But the natural calamities of the following decade more than counteracted the improvements in transport, and prices were bound to rise. In 1891-92 the rise was inconsiderable, as the scarcity was purely local, and imports promptly arrived to meet the demand. In all seasons a certain amount of importation is necessary, as the districts do not produce sufficient for their own consumption. Imports come mainly from the United Provinces and the Punjab, and famine in those provinces in

1896-97 raised prices in Ajmer-Merwara. In the famine of 1899-00 grain was always procurable in the most distant par of the districts at a price which nowhere exceeded 7 seers to the rupee. The extraordinary prices of the 1869 famine, due to imperfect means of communi-

cation, can hardly be seen again.

The material condition of the urban population is generally satisfactory. That it has been so little affected by the recent famine is due to the railway. The standard of comfort among the well-to-do has been gradually rising and European articles such as mineral waters and ice are widely used. Among the richer classes an increased use of articles of dress of European fashion is also to be observed. If a middle-class clerk be taken as an example, it is seen that he has sufficient income to enable him to live with comfort in a town. If he is in the service of Government he has a pension to look forward to, and if in that of the Railway, his Provident Fund savings. He can afford to dress well, to diet himself liberally, and generally to give his sons an English education. In rural areas, on the other hand, the effects of the famine are shown in a perceptible falling-off in the standard of living. The quantity of the daily food has diminished, the stores of ornaments and household vessels are depleted, and smaller amounts are spent on clothing. The less initial cost has caused many to clothe themselves in the cheap and flimsy foreign cottons rather than in the stronger rezu cloths of local manufacture. Little margin is left for luxuries such as liquor and opium. Expenses on social ceremonies have been curtailed considerably, rather from stern necessity than from natural habits of thrift. On the other hand many conveniences are available which were unknown to previous generations, and matches, kerosine oil and cheap cloths from Lancashire or Bombay mills are procurable in every substantial village. Indebtedness has increased largely among the cultivators, but the difficulty of recovering debt on the part of the money-lenders has recently led to a contraction of credit. Liberal grants of takāvi by Government have tended to rectify the situation; much revenue has been suspended and much remitted.

The labouring classes have been the most affected by recent famines, and since 1870 their position has probably never been worse. They are living upon the border line of the subsistence minimum, and any failure in their usual employments makes it necessary for Government to go at once to their relief. The recognition of this fact has had a bad effect upon their moral though adding to the security of their material condition. During the famine the istimrārdārs incurred considerable debts to Government, but their existence was not allowed to interfere with their standard of living, and in general their mate-

rial condition is unchanged.

Material condition of the People.

CHAPTER VI.

FORESTS.

History.

The history of the forest administration in Ajmer-Merwara deserves notice, as it explains the peculiarities which distinguish some of its rules from those of ordinary British districts. In ancient times the hills about Ajmer were probably covered with scrub jungle, but they were denuded of trees long before the commencement of British rule. The Marāthās are generally given the credit of the denudation. Merwāra, described as "impenetrable jungle" in 1819, had, after 50 years of peaceful Government, reached a condition not much better than that of Ajmer. The demands of the town of Beāwar, of the cantonment of Nasīrābād, and for wood to burn lime for the tank embankments, joined to the absence of all attempts at replacing what was destroyed, left but few trees in any accessible part of the district, and by 1870 wood of all kinds had become exceedingly scarce and dear. Colonel Dixon alone, in the intervening period, paid any attention to the planting of trees, and the gardens of Ajmer and the nim trees of Beawar owe their existence to him. After his death, no attempt was made either to plant in the plains or to re-forest the hills as they rapidly became bare. But in 1871 Government sanctioned the proposal to appoint an Assistant Conservator and Sub-Assistant Conservator of Forests, more for the purpose of creating than of conserving forests. The operations were not intended as directly profitable speculations on the part of Government; their principal aim and object was an indirect and climatic advantage, to prevent the rainfall rushing down the bare hillside carrying in its course what little soil remained, and to cause it to penetrate into the crevices of the rocks and fill the springs. It was hoped that the roots of the trees and the vegetation would retain and create soil on the steep slopes, and, by lowering the temperature of the hills, cause the clouds passing over the district to part with their moisture within its boundaries.

Apart, however, from the intrinsic difficulty of re-foresting the arid hills, it was not easy to obtain the land. The waste land had been made over to the village communities by the Settlement of 1850, and it had of old been made use of by them for grazing purposes, and as a support to fall back upon in years of distress by the sale of wood. And it was naturally the hills where there was most wood that the Forest Officer was most anxious to take up, and the people most loth to part with. It was therefore determined to resume the management of certain chosen tracts, and to take up the land under an ordinance of the Governor-General in Council. This was done under Regulation No. VII. of 1874, by which the proprietary right vests in Government as long as the land is required for forest purposes. To compensate them for the deprivation, certain rights in these lands

FORESTS. 59

are secured to the villagers. They are allowed to cut grass within the forests, and such wood as is reasonably necessary for their household requirements and agricultural implements, and their rights of way previously existing, are maintained for them. It was further stipulated that two-thirds of the net profits from the management of the forests should be distributed among those persons who, previous to the taking up of the land, were interested therein. As a matter of fact the revenue of these reserves has yet been insufficient to cover the expenses, so no profits have been distributed. Only in two years (1890-91 and 1891-92) has the revenue exceeded the working expenses. All other years have shown deficits. But the supply of grass and wood available for the right-holders has increased to such an extent that the people have in reality profited by the protection of these areas, and the benefits of the measure are beginning to be recognized by the more intelligent among them.

The forests, as at present existing, consist of three clsses—State Forests taken up under the above-mentioned Regulation and covering an area of 142 square miles, Protected Forests, covering 101 acres, and Village Estate Commons. The last are insignificant in area (6 acres), and are voluntarily placed under local conservancy by their proprietors. Formerly they amounted to 10 square miles, but in 1900-01 the greater proportion was, at the request of the owners. withdrawn from the management of the Forest Department. Nine hundred and forty-seven acres are appropriated for nurseries and plantation operations. Of the reserved forests by far the larger proportion (90,747 acres) is in Merwara, Ajmer having 17,974 acres. The forests are either fenced or efficiently demarcated by masonry pillars or by stone slabs at suitable distances. The culture operations are of two kinds, sowing during the rains and transplanting of young trees from the nurseries.

The principal trees found in the forests are the dhokra (anogeissus pendula), the salar (boswellia thurifera), the kumpta (acacia rupestris), the babul (acacia arabica), the khair (acacia catechu), the orinja (acacia leucophlau), the khejra (prosopis spicifera), the gol (odina wodier), the nim (azadirachta indica), the dasan (rhus mysorensis), the farangan (grewia pilosa), and the gangan (grewia populifolia). These indigenous trees grow easily from seed, and, if the rainfall is favorable, require no irrigation. The babul is the only tree which furnishes wood useful for any other purposes than fuel. The chief exotic trees, the acclimatisation of which is attempted, are the pipal (ficus religiosa), bar (ficus bengalensis), farās (tamarix orientalis), siris (acacia speciosa), mango (mangifera indica), jāman (eugeniu jambolana), shisham (dalbergia sissoo), and the cork tree (millingtonia hortensis). They are difficult to rear, as the young plants require much watering; none of them will grow on the hillsides, and they only thrive in good soil.

The Forest administration is under the control of the Commissioner and the District Officers. The former exercises the powers of a Conservator of Forests, while the latter have those of Deputy ConserTrees.

Management and Control.

60 FORESTS.

The District Officers are assisted by an officer of the Provinvators. cial Forest Service of the United Provinces, who is responsible for the technical part of the duties and for general supervision over the He exercises the powers of a Divisional Forest Officer. The forests are worked under a system of coppice fellings, with stand-The coupes are either sold in a lump sum to a purchaser, or the produce is removed at a fixed rate per cart, camel, or donkey load. The standards are marked by the Departmental subordinates, and fellings are conducted under the supervision of the foresters or range As, under the Regulation of 1874, the local villagers have considerable rights over the grass and timber in the forests, the produce available for sale to outsiders is correspondingly diminished. Unfortunately the relations of the people with the Department are far from satisfactory. This is due largely to discontent on the part of the villagers with the restrictions imposed on indiscriminate fellings The latter especially was a serious complaint of the and grazing. villagers, but steps have been taken to remove it by opening the forests to the grazing from March to June yearly, a period in which fodder on village lands becomes scarce.

Disposal of Produce.

In general the local demand for fuel is amply met by the State forests. But the large towns of Ajmer, Beāwar and Nasirābād create demands which the limited and right-burdened forest areas in their vicinity are inadequate to supply. There are no separate sub-divisions for fuel and fodder reserves: both are produced under the same treatment and within the same areas. In times of famine the reserved tracts are thrown open to the villagers for grazing, and for the removal of dry wood for fuel at nominal rates. The restrictions even upon lopping and felling for fuel have been removed in time of severe scarcity. Forest fires occur occasionally in the hot weather. The villagers generally furnish ready help in extinguishing them and in burning and clearing the preventive fire lines.

Forest Revenue and Expenditure.

During the ten years ending in 1890, the average annual revenue was Rs. 9,141, and the average annual expenditure Rs. 15,159. The average deficit was therefore Rs. 6,018. During the next decade the average annual revenue was Rs. 14,719, and expenditure Rs. 16,077, showing an average annual deficit of Rs. 1,358. In 1902-03 the figures of revenue and expenditure were Rs. 10,973 and Rs. 15,520, respectively, with a deficit of Rs. 4,547. The continued deficit is largely due to the amount of fodder, fuel and timber given away free to the right-holders every year, and the provision of which is the main object of the forest management in Ajmer-Merwāra. But for this, the results would show a surplus.

Mines and Minerals. Traces of many minerals are to be found among the hills of Ajmer-Merwāra.

Lead.

The Tārāgarh hill at Ajmer is rich in lead, and iron and copper mines have been worked, but did not pay their expenses. The lead mines of Tārāgarh were farmed by the Marāthās for Rs. 5,000 yearly, the custom being for the miners to receive three-fourths of the value of the metal as the wages of their labour, and to cover

FORESTS. 61

their expenses in sinking shafts. Mr. Wilder, the first Superintendent of Ajmer, took the mines under direct management, and they produced annually from 10,000 to 12,000 maunds of lead, which was sold at Rs. 11 per maund. The Ajmer magazine was the chief customer, and on its ceasing to take the metal in 1840, the mines were closed. The lead is admitted to be purer and of a better quality than European piglead, and it is chiefly owing to the want of fuel and of cheap transport that it has been driven from the market. There is no longer the same demand for the metal as in the troubled

times at the beginning of the last century.

Since 1899 progress has been made in developing the mining industries in other directions, mica and asbestos especially receiving Of recent years the demand for the former metal has increased enormously, owing to its valuable properties as an insulating medium for electricity. New sources of supply are being sought for everywhere, and as mica occurs very abundantly throughout the district, Ajmer-Merwara is being exploited by prospectors. The deposits consist mainly of muscovite of a similar quality to the Bengal ruby mica. Other qualities are, however, frequently to be met with, including biotite and phlogopite. Of these, the former is quite useless from a commercial point of view, while the latter, although of sound quality, appears to occur only in crystals of too small a size to be of much value. The same remark applies to the deposits of muscovite, the majority of which are too small to be worked with profit. Some specimens of larger crystals have, however, been found, and it is possible that more may follow. The value of two of the known deposits is considerably depreciated on account of all the crystals being densely stained by interlaminar inclusions of a ferruginous substance.

At present thorough prospecting work is being undertaken at some seven or eight different areas in the district, but it is thought probable that none of the deposits extend to a greater depth than 30 or 40 feet. In these circumstances, the work is carried on in the form of open quarries, which can hardly attain to the dignity of "mines."

At the moment of writing, about 400 labourers, men and women, are employed on mining operations within the district. They are mostly of the agricultural class, and come from the villages nearest to the deposit that is being worked at the time. The men earn on an average from 1½ to 2 annas per day, and the women 1 anna.

Asbestos occurs in some three or four deposits round Sendra, in Merwāra, and is now being mined in small quantities. The quality is, however, poor, and apparently the mineral is wanting in those textile characteristics which are so necessary for most of the uses to which asbestos is put. Most of these mining operations are carried on by two Companies, who have been granted licenses.

Hæmatite exists in considerable quantities in some of the hills, especially near Sāroth in Merwāra, but on account of the absence of coal it has not been considered worth working. Traces of copper are also to be met with, and lead is said to exist in the south of Merwāra

Mica.

Asbestos and other Minerals.

as well as at Tārāgarh. Garnets and aquamarines have been found in the Aimen district

in the Ajmer district.

Good building materials are abundant, and stone is largely used for purposes for which wood is employed elsewhere in India. Door frames are often made of stone, and the best roofing is formed of slabstones resting on arches or on stone beams, while thin slabs are sometimes used as slates. The best quarries in the Ajmer district are at Srinagar, where slabs 12 or 14 feet long by 3 or 4 feet in width can be obtained. Near Beāwar, slabs not quite so large, and generally too hard to be dressed with a chisel, are quarried at Atitmand. At Khetra Khera, about 6 miles north-east of Beāwar, limestone slabs are found which can be dressed. Near Todgarh good slabs have not been found, but beams 10 or 12 feet long and uneven in thickness are procurable.

For rubble masonry stone is everywhere to be met with. The best quarries are in the hills running between Ajmer and Nasīrābād, and down the east side of Merwāra. The stone here is found in slabs of almost any size, both sides perfectly parallel: and if it is carefully quarried one smooth face can generally be obtained. For ashlar work limestone and granite are procurable. Marbles of various colours are

quarried in the vicinity of Ajmer.

Lime.

Stone.

Lime is burnt from kankar and from limestone, and the latter kind is preferred by the natives. The limestone generally used in the city of Ajmer is a gray stone obtained near the village of Nāralli, about 6 miles from the city. The lime obtained from it is not very pure, but is tenacious, and bears a large admixture of sand. At Mākhopura, Kālesra Konlāi and other villages, a pure white limestone is found, but the stone is hard and difficult to burn. Limestone is also found in abundance near Beāwar. Kankar is to be met with in all parts of the district, but varies considerably in quality as a carbonate of lime. That which breaks with a blue fracture, and which when breathed on causes the moisture to adhere, is considered fit for lime burning. Kankar lime has higher hydraulic properties than stone lime, and is generally used by the Public Works Department. No material, however, producing good hydraulic lime has as yet been discovered in the district.

Road Metals.

Materials for road-making are everywhere abundant. For heavy traffic, broken limestone, the refuse of the slabstone quarries, or granite are found more suitable than kunkar, which, though it makes a smooth even road, will not stand heavy traffic. For the district roads any coarse, brittle stone if not too micaceous, or an inferior kind of gravel called barha is often substituted for stone or kankar. They are everywhere found, are easily dug, and answer the purpose very well where the traffic is light.

CHAPTER VII.

ARTS AND MANUFACTURES.

Ajmer is not remarkable for arts and manufuctures, while Merwara is even less so. Indian art has always required the stimulus of wealthy patronage, and such no longer exists in the province. It has been remarked that, as a rule, the accident of patronage has alone determined the home of artistic industries. The Mughal Emperors no longer rule in Ajmer, and the wealthy Seths are but indifferent supporters of art. The best artificers of Rajputana are to be looked for in Jaipur, Jodhpur, Alwar, Bikaner, and other Native States, where patronage is still available. The industries of Ajmer are similar, but inferior.

There is no silk weaving, and hand industries are limited. The cotton hand-looms in Ajmer and the larger villages turn out cloths known as reza, khes, dhotī, susi, and chārkhāna, for local use. Reza is a stiff white cloth made from native thread, used largely for garments by the peasantry. It is also the favourite medium for the dyers, who print designs upon it with wooden stamps, which are cut in Mārwār. The local industry is however, perishing in the face of foreign competition, and cannot revive. Khes cloth has a diagonal pattern, owing to the threads of the west being twined alternately with those of the warp. It is used for sheets and chādars by the lower classes. Susi is a narrow cotton fabric, used only by Muhammadan women for trousers: it has stripes lengthwise down the piece of a different colour from the groundwork. Chārkhāna is a sort of superior susi with a check pattern. Towels, table-linens and other cloths are made in the Ajmer Jail. Fabrics made there of country reza cloth, dyed red with al root, and stamped with patterns in black, are very popular in the rural areas. The cotton bed-covers and printed floor-cloths of Beāwar are the best in the district. Carpets and rugs are manufactured in the Ajmer Jail only. Considerable trouble has been taken to secure attractive designs, and the old Indian patterns, as well as those of Kashmir and of Persia, are reproduced here. There is nothing noteworthy or distinctive about the jewellery, most of its forms being well known in the adjacent Native States, such as Jaipur; and those of Ajmer are generally inferior. The Mers wear rough ornaments of silver or of base metal which sometimes preserve old forms, while ornaments bearing the figure of their hero, Tejāji, are common among the Jats. None of them deserve special mention.

Of artistic metal vessels there is practically no manufacture. The village blacksmith's art is limited to implements of husbandry of the roughest description. Gadulia lohārs of the wandering castes supply rough locks, knives, spoons, etc. The brass and copper vessels made in the towns are plain and without special characteristics. Artistic

The Hand Industries.

pottery is unknown. Though some of the houses of the wealthier citizens of Ajmer are adorned with rich carvings in wood and stone, the best workmen have to be obtained from outside the district. The turners of Ajmer are chiefly employed in making rosaries, combs, etc., of sandal wood, which are purchased by the pilgrims who resort to the Dargāh. They also turn bangles of ivory, the only description of ivory work known in the district. Bangles of lacquer work are also made, but are inferior to those of Delhi. Many of the carpenter class have obtained employment in the workshops of the Rājputāna-Mālwā Railway.

Cotton Mills.

The Krishna Cotton Mill at Beawar is the only factory. concern was floated as a Joint Stock Company in 1889, with a capital of Rs. 7,00,000, and the mill started working on 1st June 1891. In 1897 there were 250 looms and 12,312 spindles working, and 542 hands were employed. The out-turn was 13,81,080 lbs. of yarn, and 5,18,252 lbs. of cloth, of the total value of Rs. 6,58,323. In 1902 the number of spindles was the same, but the looms were 252, and the number of hands employed had risen to 606. The total value of the out-turn was Rs. 7,31,803, consisting of 13,91,290 lbs. of yarn and 7,78,292 lbs. of cloth. The yarn is spun in combs of from eights to twenties, and cloth of coarse quality is made from the local thread for use as dhotis, shirtings, chadars, and khadis. A small quantity of fine cloth is made from warp and weft imported from England. Such cloth and yarn as are not used locally are exported to Agra and Cawupore. The rates of daily wages paid vary from 21 annas to 20 annas in the case of men, from 2 annas to 5½ annas for women, and from $1\frac{1}{2}$ annas to $2\frac{1}{2}$ annas for children.

Cotton Presses.

There are six hydraulic cotton presses at Beawar, three at Kekri, and one at Nasīrābād. The annual profits on each of those at Beāwar vary from about Rs. 2,000 to Rs. 8,000. The three presses at Kekri are said to clear about Rs. 10,000 each every year, and the one at Nasīrābā i about Rs. 2,000. There is also a ginning factory at Kekri, with an annual profit of Rs. 3,000. Cotton from the States of Mewar, Kishangarh, Tonk, Kōtāh, and Bundi is brought to the presses at Kekri and Nasīrābād. The Beāwar market draws its supplies principally from Mewar, though some of the cotton used in the Krishna Mills is imported from Berar. According to the census figures of 1901, 13,908 persons were supported by the various branches of the cotton industry. There are no other factory industries in the districts besides those mentioned. As their range is so restricted, their influence upon internal migration is insignificant. The permanent employees in the mills and presses are few in number, and the supply is adequate. Their material condition is generally good. In the spring and summer large numbers of women come into the presses for employment as cotton With the first fall of the rains they return again to their The temporary occupation is of valuable assistance to the labouring classes in the season when agricultural operations are at a standstill.

CHAPTER VIII.

COMMERCE AND TRADE.

In ancient times Ajmer was an entrepôt for the trade between Bombay and upper India. As early as A.D. 1614 an agency was established there for the East India Company by Mr. Edwards of the Surat factory, and for many years the city was the principal mart for the exchange of European goods and the products of Rājputāna and northern India. But the dimensions of the trade are not known. It appears to have been at all times hampered by vexatious customs and duties, and many of these were continued until after the British

occupation of the districts.

Before 1879 the trade of Ajmer city had fallen off considerably, owing to the competition of the growing towns of Beawar and Nasirābād, but it has revived with the establishment of the railway. Whereas the transit trade of the district was formerly entirely carried by camels and banjāra bullocks, it is now mostly railborne. There is, however, still a certain amount of conveyance by camels and bullocks into Marwar on the north, and to the south down the main road to Deoli and the Native States beyond Deoli. Similarly the Merwara district is fed chiefly from Beawar, the grain being carried up the tract by road in carts. By the same agency the cotton from Mewar and the south arrives in the market at Beāwar. This is clearly shown by the export and import figures. In 1891 only 1,075 tons of raw cotton were imported by rail to Beawar, while 8,471 tons were exported. The difference between these figures must have come into the market by road. Ajmer, Beāwar, and, in a lesser degree, Nasīrābād are the three chief centres of trade. Kekri which in the early days of British rule bade fair to rival Ajmer as a trading mart has been long in a declining state. It is still, however, a considerable cotton mart, and its exports of that commodity amount to about half those of Beawar. As the province has but few manufactures, and produces but little in excess of its own requirements, the import and export An import trade in ordinary times is entirely one of transit. trade can only exist in proportion as the province has something to offer in exchange. Times of famine are of course exceptional, for in these years the enormous grain imports are paid for with the money spent by Government on works and other forms of relief.

Grain and pulses, followed at a distance by sugar and jagri, salt, metals and piece-goods form the chief imports of Ajmer. In 1881 the total imports were 7,138 tons, of which grain amounted to 1,971 tons, and sugar and jagri to 2,931 tons. Most of the grain comes from the Punjab and the United Provinces of Agra and Oudh, the sugar and jagri from Bhiwāni in Hissār and from the province of Agra. Pachbhadra and Sāmbhar in Mārwār supply the bulk of the salt. Metals, seeds and piece-goods come from the surrounding Native States, Calcutta,

General Character.

Exports and Imports.

and Bombay. Much of the sugar is re-exported to Mewar. The export trade for the same year amounted to 601 tons, of which grain formed the largest item. In 1891 the imports had gone up to 22,945 tons, chiefly owing to the increase in grain and pulses. Local crop failure was met by large consignments from outside, and 18,355 tons were imported into Ajmer city. Exports were again out of all proportion to imports, being 1,737 tons only. The year 1902, following the great famine of 1899-1900, found grain imports still at a high level, 18,022 tons. Sugar and jagri maintained their average with 2,184 tons. The total imports were 22,196 tons, and exports only 1,340 tons. It may be noted that in the famine of 1898-1900, 61,972 tons of grain were imported into Ajmer, and 53,539 into Merwara. All

these figures refer to railborne trade only.

The most valuable export of the district is raw cotton, and of this trade Beāwar is the almost exclusive entrepôt. Besides the local product, much of the cotton from Mewar and other southern Rajputāna States is brought to Beāwar, where it is pressed before export to Bombay. Messrs. Ralli Brothers, Volkart Brothers and many native The export of raw cotton rose from firms have agencies in Beāwar. 3,561 tons in 1881 to 8,471 tons in 1891. In 1900 difficulties connected with the Mewar border threatened the trade with extinction, and only 592 tons were exported, as against 8,424 tons in the preceding year. They were, however, surmounted, and in 1902 the figure rose again to 4,683 tons. The grain imports to Beawar in 1891 and 1902 show the same features as have already been remarked in the case of Ajmer, and were due to the same causes. The total figures of railborne import to Beawar in 1881, 1891 and 1902 were 16,015 tons, 31,011 tons and 25,032 tons respectively. The total export figures for the same years were 11,930 tons, 15,350 tons and 8,711 tons respectively.

It is difficult to form even an approximate estimate of the total exports from the whole province. The istīmrāri estates, with the exception of Junia, Pisāngan, Sathāna, Keybāniā, Prānhera, Kādhera, Goella, Shokla and Keronj, have never been measured, and there are no satisfactory returns of the crops grown in this portion of the Ajmer district. Their exports consist of grain, cotton and opium. Without reliable returns of the area under grain crops in these estates, which in area exceed one-half of the Ajmer district, it is impossible to calculate how much more grain is produced in an average year than is necessary to supply local consumption. Cotton is largely grown in the istīmrāri estates, but most of it finds export via Ajmer or

Beāwar

Trading Classos.

The Mahājans or Baniās are by far the most important trading class in the province. There are a few Pārsi shopkeepers in Ajmer and Nasīrābād.

CHAPTER IX.

COMMUNICATIONS.

The main line of the Rajputana-Malwa Railway, from Ahmadabad to Delhi, passes through Ajmer and the north of Merwara from west to east for a length of 59 miles. The Ajmer-Khandwa branch of the same railway runs through the Ajmer district due south of Ajmer for 41½ miles. The portion of the line north of Ajmer and the portion towards Nasīrābād were surveyed in 1869, and that south of Ajmer towards Ahmadābād in 1872. The construction was commenced in 1873 and completed in 1876. The portion connecting Nasīrābād with Chitorgarh was finished in 1881. The latter is constructed for a single metre-gauge track, but sufficient land has been taken up to admit of another track being laid, if necessary, hereafter. The line was constructed by Government, by whom it was worked until 1st January 1885. It was then taken over on lease by the Bombay, Baroda and Central India Railway and worked as part of that Company's system. The head-quarters of the railway have been located at Ajmer, and handsome offices and extensive locomotive and carriage and waggon shops have been constructed there in connection with the line. Ajmer city is 275 miles from Delhi, the terminus of the main line on the north, and 305 miles from Ahmadābād, the southern terminus.

The total mileage of railway in the district being 100½, the number of square miles of country per mile of railway is 26.97. The

average cost of construction per mile came to Rs. 81,551.

The local traffic has steadily increased since the line was opened. During the Pushkar and the Ajmer "Urs" annual fairs, there is a heavy pilgrim traffic in the direction of Ajmer. Via Beāwar it carries much of the cotton of Mārwār and Mewār to upper India and

Bombay.

The opening of the line has conferred great benefits on the district. The population of the towns of Ajmer, Beāwar and Nasīrābād has increased steadily since 1851; the railway workshops at Ajmer give employment to several thousands of hands; and the increased facilities for transport have resulted in the general cheapening of commodities. The recent famines were so widespread throughout India that prices of food grains were bound to rise high, but the railway has made it possible for local scarcity and even total crop failure to exist without an appreciable rise in the price of food. This phenomenon was a noteworthy feature of the famine of 1891-92. The value of the railway in thus preventing sudden and acute distress in any local area can hardly be over-estimated. A railway line is now projected from Bārān to Mārwār junction, and will pass through the Merwāra district at Pipli. The earthwork of this section was constructed in 1900. In the same year the earthwork of a projected line from Nasīrābād to

Railways.

Deoli was undertaken, and completed to a point fifty-five miles south, east of Ajmer.

Roads.

Most of the roads in the district have been constructed or metalled during years of famine. Prior to 1869 the only metalled roads were 14 miles between Ajmer and Nasirābād, and 7 miles between Ajmer and Gangwāna on the Agra road. But the famine of that year gave a great stimulus to their construction, and before 1875 the Agra-Ahmadābād road had been metalled throughout from the borders of Mārwār 44½ miles to the west of Ajmer, to the boundaries of Jaipur State, 30 miles to the east. From Nasīrābād a metalled road was made to the cantonment of Deoli, 57 miles, another in the direction of Nimach and Mhow, extending to Barl on the Khāri river, 28 miles, and a third from Nasīrābād to Māngaliāwās, 14 miles. The road to Nimach, beyond Barl, though once metalled is now falling into disrepair. No addition to the metalled roads has since been made in Ajmer. These roads are maintained from Imperial funds.

Merwāra was a country without roads before 1869, but during the famine a tolerable road to Todgarh, and fair roads over the Pakheriāwās and Sheopura passes into Masūda and Mewār were constructed.

structed. All of them are now metalled and in good order.

In 1891 the total mileage of roads maintained from Imperial funds was 187, costing Rs. 27,495 for maintenance. Maintained from District Funds were 304½ miles of road, costing Rs. 9,495 for upkeep. Of this total only the Ajmer-Pushkar road, 8 miles, was fully metalled.

Municipal roads extended to $26\frac{2}{3}$ miles and cost Rs. 3,035.

In 1901 the mileage of Imperial fund roads was unchanged, but that of Local fund roads had increased to 308½ miles, of which 33 miles were fully metalled. Their cost of maintenance was Rs. 47,914 and Rs. 3,264 respectively. The large increase in the former and decrease in the latter is explained by the fact that 1901 was a famine year, and famine labour paid from Imperial funds was employed in repairing the Local fund roads. In 1902, with the same mileage, Rs. 18,112 was spent on maintaining Imperial roads, Rs. 13,191 upon Local fund roads and Rs. 2,712 on Municipal roads. Owing to the necessity for providing work for famine labourers, the roads, especially in Merwāra, have tended to increase beyond the power of the District funds to maintain them, and some of them are falling into disrepair.

In addition to the roads, the district is served by a network of country-cart tracks, the quality of which varies according to the nature of the ground over which they pass. The country-carts are similar to those used in other parts of Rājputāna. They are smaller than those of the United Provinces of Agra and Oudh. Springed and

tyred conveyances are little met with outside the towns.

Post Offices'

Ajmer is the head-quarters station of the Rājputāna Postal Circle, which is controlled by a Deputy Post Master-General, and is divided into 4 divisional charges.

In the Ajmer and Merwara districts there are at present 39 Imperial and 11 District Dak post offices. The combined offices at

Beāwar, Deoli, Kekri and Pipli also perform telegraph work; all other head and sub-offices and certain selected branc's offices are empowered to receive telegrams for transmission to the nearest telegraph office. The District Post is maintained by funds derived partly from a local cess and partly from a grant from Imperial revenues. It has 11 branch post offices, and there are 193 miles of District Post mail line. The offices are all worked by extraneous agents, who receive small stipends as remuneration for this service. As each District Post office becomes self-supporting it is taken over by the Imperial Post, and with the funds thus set free another District office is opened.

Besides the Rājputāna-Mālwā. Railway telegraph offices at all stations on the line, there are telegraph offices at five places in the districts. Of these, Beāwar has a first class office, Ajmer, Nasirābād and Deoli second class offices, and Kekri a third class office. A telegraph office was also opened at Pipli for famine relief purposes on the 10th May 1900, and it is kept open pending the settlement of the question of the railway from Marwar junction to Lambia, which will pass through Merwara at this point. Proposals have been made to open an office at Todgarh, but the idea was abandoned, as it did not appear likely to be a financial success. Taking the four years before 1901 at the five district telegraph offices, we find that 29,746 telegrams were sent and 36,294 were received in 1897-98. In 1898-99 the numbers rose to 33,031 and 39,405 respectively. In 1899-00 there was a large increase, due probably to the necessities both of traders and of officials in a famine year. The number of telegrams sent was 45,088, and 46,380 were received. In the following year 1900-1901, under more normal conditions the figures were 40,230 and 46,143. The popularity of this means of communication is evidently advancing. Much use of the telegraphic system is made by the native merchants of Ajmer and Beawar, where a great deal of opium and cotton speculation goes on, necessitating the use of urgent wires.

Telegraphs.

CHAPTER X.

FAMINES.

What has already been written regarding the position, physical characteristics and rainfall of Ajmer-Merwara is sufficient to explain why the province has always been peculiarly exposed to recurring periods of scarcity, and occasionally to the ravages of famine in its worst form. As the debatcable laud between the two monsoons, and beyond the full influence of either, it is apt to fall a victim to the worst eccentricities of even an Indian rainfall. Deficiency in quantity and irregularity of distribution are both to be feared, as either may produce crop failure. Although Colonel Dixon has given it as his opinion that 12 inches of rain properly distributed in any village is sufficient to secure the payment of the assigned rent, the history of the province shows how hard it has been for nature to maintain that seemingly moderate standard. Scarcity is seldom absent from some part of the country. Formerly in such years the people in the afflicted tracts, taught patience by constant adversity, used to emigrate with their families and cattle to more favoured regions, and return to their homes in time for the sowings of the succeeding year. Modern measures of relief, promptly undertaken, have somewhat checked the tendency in Ajmer-Merwara, but in Native States it still continues, and the province, lying as an island among them, is on the high road of the yearly migration.

The fickle nature of the rainfall throughout the tract makes it difficult to distinguish any special part as peculiarly liable to scarcity; even history points to no definite conclusion. The monsoon is generally supposed to break at the end of June or the beginning of July, but a late commencement is less to be dreaded than a premature withdrawal. A heavy rainfall in September may, by filling the tanks and assuring the rabi harvest, save a situation which appears hopeless, but the bulk of the population depends on the autumn harvest for their food supply, and both this and the grass for fodder are imperilled by non-arrival of the early rains. When both the south-western and north-eastern monsoons fail, the province is destined to the miseries of a famine of the three great necessaries of lifeg—rain, grass and water—called in the country a trikāl or treble

famine.

Of recent years the opening of the railways and improved facilities for import of grain have counteracted the tendency to a rapid rise in prices in the case of local famines. Only a widespread scarcity over India, as in 1899, can lead to the sudden heightening in the price of grain, which does so much to intensify acute distress and

precipitate the crisis. Transport of fodder is, however, more difficult, and migration of the cattle-owning classes is one of the earliest warnings of the commencement of scarcity. It is often accompanied by an increase of crime against person and property. But much experience may be said to have given the people a knowledge of the requirements of the Famine Code, and loudly-expressed demands for the opening of local works can now be added to the list of famine

warnings.

The first famine in Rājputāna of which we have written record occurred in A.D. 1661. A memorial of it is preserved in the beautiful marble band erected at Kānkraoli in Mewār at the cost of a million sterling by Maharāna Rāj Singh of Udaipur, to save his people during the dire calamity. Other famines occurred in 1746 and in 1789, the latter of which is supposed to have exceeded in intensity even the terrible one of 1812, which is said to have lasted five years and has gained the name of panch-kāl Three-fourths of the cattle died, and, as stated also in the record of the famine of 1661, man ate man. Traces of the devastation caused by this famine were visible in Ajmer at the beginning of British rule.

Between 1812 and 1869 there was no general famine in Rajputana, but in 1819, in 1824, in 1833 and 1848 there was severe

scarcity in Ajmer.

For some years previous to 1868 the seasons had been irregular and the crop deficient in Ajmer-Merwara. Stocks of grain had been depleted, and there was no surplus with which to face the approaching crisis. The rainfall of 1868 was unfavourable from the commencement; the early rains were insufficient for sowing; from the 1st June 1868 to the 1st June 1869 the average fall from all the stations of Ajmer-Merwara was only 7.4 inches, or about one-third of an average fall. The state of Jaipur and Jodhpur was as bad The south-west monsoon failed entirely west of the East of the range Indore alone got rain, and the starving Aravallis. population of Central India and Bundelkhund flocked into Mālwā. In Gujarāt a terrible flood in August swept away cattle and crops and destroyed the stores of grain below the ground. The north-eastern monsoon had equally failed, and great scarcity overshadowed the North-Western Provinces (now the United Provinces of Agra and Oudh.) Ajmer-Merwara was thus isolated in the midst of a famine tract. It had no supplies of its own, and, owing to want of fodder, the ordinary transport by bullock-cart utterly broke down. Caniel transport was not available in the rains, and even when available was insufficient to cope with the demands of the situation.

Emigration began towards the end of August. Wheat was then selling in Ajmer at 10 seers; barley, jovar and grass were 12 seers per rupee. Such was the scarcity of fodder that cows were offered for sale at Re. 1 each, and good plough cattle at Rs. 10 a pair. Relief works were commenced, but by November the condition of the country was sufficiently deplorable. The kharif had failed entirely; half the cattle had been driven into Mālwā; water in the wells was

Earlier Famines.

Famine of 1868-69.

scanty and brackish, and the tanks were empty. As the season advanced, the situation grew worse. The few irrigated crops were destroyed by mildew and hail storms; the people were apathetic, and the money-lenders would make no advances. The distress was intensified by enormous immigration from surrounding Native States. People were reduced to the necessity of mixing bark and roots with

the grain which they ground up to make bread.

Poor-houses were established in April 1869. The rains did not set in until July, and were then insufficient; hope of the kharif failed, even roots and bark became scarce, and the mortality was frightful. Copious rain in September was discounted by a plague of locusts, which destroyed from 50 to 85 per cent. of the standing crops. Prices touched their highest point in September, when barley was sold for 3 seers per rupee in Ajmer city, but at times even men with money in their hands were unable to get food. This was the crisis. Thereafter, importation of grain commenced from Bhīwāni and Rewāri, and the tension gradually slackened until the rains of the following year brought relief. The losses were calculated at 25 per cent. of the population of 4,26,000, at 33 per cent. of the cattle, and 50 per cent. of the plough and milch cattle. Government spent altogether Rs. 15,20,074, out of which Rs. 2,30,000 were given in gratuitous relief.

As a direct result of these lamentable experiences, the system of famine relief had been considerably improved before the province had again to face severe scarcity in 1890-92. The Land Improvement Loans Act of 1883 and the Agriculturist Loans Act of 1884 had provided the cultivators with new sources of capital, and, unlike the operations of the native money-lender, these sources were allowed to flow more freely, according to the severity of local scarcity. The railways, too, had been opened, and importation of grain could be prompt and effective. In the local famine of 1891, grain prices rose very little. But the railway could do little to import fodder for eattle; this was the greatest difficulty of all, and large mortality among such as were not removed abroad for pasturage was inevitable.

Famine of 1890-92.

Twenty years of comparative prosperity had followed the disastrous season of 1869. But in 1890, although the monsoon opened auspiciously throughout the district, it stopped abruptly in the early part of August, the crops withered and indications of scarcity began to show themselves. It commenced as a fodder famine, and the emigration which started in October was confined to the owners of cattle. As regards the condition of the people themselves the period from October 1890 to August 1891 is more properly described as one of scarcity. The Famine Code was not applied. Relief by means of works was found sufficient. In Merwāra the first was opened in October 1890, but in Ajmer takāvi loans to the istimrārdārs and cultivators adequately met the situation up to January 1891. Until after the month of August the average number of labourers on the works never amounted to more than 6,700. By the failure of the monsoon of 1891, which gave an average rainfall of only 8.50 inches to

Ajmer and of 10.24 inches to Merwāra, the scarcity deepened into famine. The drought continued throughout September and October; the winter rains were also unfavourable, and the autumn crops of 1891 and the spring crops of 1892 both failed. More extended relief and the application of the Ajmer Famine Code became necessary. The numbers on relief works, which were 3,623 at the end of September, rose to 14,914 by the end of October, and reached their maximum (29,471) in the following May. In this month some 10,000 persons were in receipt of gratuitous relief. The works were closed in October 1892, when copious rains had fallen. The relief works in both districts were almost entirely managed by the Public Works Department. As a rule they were small and numerous, owing to the deficiency of large works in the sanctioned programme. Relief other than that on the works was distributed by the civil officers. There were only three poor-houses, and these proved unpopular. A system of home labour for the assistance of parda nashin women was tried in Ajmer city.

The total cost to Government of the relief operations amounted

to over 21 lakhs of rupees.

This famine had certain characteristics which distinguish it both from the preceding and subsequent famines. The comparatively stationary condition of food-grain prices, and the reasons for the phenomenon have already been noted. A curious outbreak in the shape of grain riots in many villages of Ajmer took place in September 1891. The village traders, who had stopped giving credit in August, were the victims, and the Mers are believed to have been the principal instigators of the disturbances. For a short time things looked serious, and the aid of cavalry from Deoli and Erinpura was called in to assist the police patrols. But a show of force was sufficient, and the lawlessness soon subsided. Again very few labourers from istimrāri estates came upon the relief works, and, compared with previous famines, the emigration into Ajmer-Merwāra from adjoining Native States equally affected by scarcity was very restricted. This was due partly to improved systems of relief available in those States, and still more to extensive emigration to Mālwā.

The water level in the wells also fell to an unprecedented extent. Many dried up, and the want of drinking water was a constant anxiety, which even threatened at one time to render it impossible for the people to live in Ajmer city. An epidemic of fever followed

this famine and caused great mortality.

The country was given but little breathing space before the next disaster came upon it. The seasons of 1892-93 and of 1894-95 were very fair, but that of 1895-96 was indifferent. The recuperative capacity of the districts was shown by the fact that at the end of the latter year the suspensions of Land Revenue given during the famine (Rs. 1,03,714) had been practically cleared off, and of the takāvi loans (Rs. 6,08,854) only Rs. 1,43,951 remained outstanding.

But thereafter the situation gradually deteriorated until it culminated in the great famine of 1899-1900. A partial failure of the

Famine of 1898-1900.

kharif in 1896-97 was followed by indifferent rabi in 1897-98. In 1898-99 there was a deficiency of rainfall, especially in Merwāra, and in this tract relief measures began to be undertaken in November 1898. Until September 1899 these were comparatively restricted; village relief was not found necessary until May of that year, and the total numbers in receipt of relief did not rise above 9,000 until the end of July. But by that time fears regarding the rains, only too well justified by results, intensified the general anxiety. Prices, which had shown an upward tendency since May, began to rise rapidly, and by the end of August the relief figures in Merwāra had been more than trebled.

September saw the rains ended in almost complete failure. Ajmer received 8 inches and Merwāra only 5. The tanks were empty, wells were drying up, and a total loss of both crops was seen to be inevitable. Nor was the disaster merely local. All western and central Rājputāna was similarly affected. Central India was declaring famine, and Gujarāt, where crop failure was hitherto almost unknown, was entering upon the most calamitous period in its history. Bombay was preparing for famine in all its districts south of Sind. The prices of food grains mounted steadily. They reached their highest point in October, when barley was at about 9 seers to the rupce. This, though high, is in striking contrast to the level reached in the 1869 famine, and shows the great prophylactic value of the extended railway systems.

Test works were opened in Ajmer in September 1899, and the numbers rose rapidly in October. Thereafter, until the cold weather of 1900, both districts were under the operation of the Famine Code. The numbers reached their highest point in June 1900, when 68,728 persons, or 16 per cent. of the population, were receiving relief in Ajmer. In Merwara the pressure was even more severe, and at one time 72 per cent. of the whole, or the entire rural population, was in receipt of Government relief, and the percentage was over 70 for a considerable period. The figures began to fall after the setting-in of the rains in July 1900, and thereafter declined until relief measures were stopped in November. The relief works undertaken consisted chiefly of the construction of new and the repair of old tanks, the making of new roads and collection of metal for existing ones. They were under the management of the Public Works Department. The civil officials arranged for the poor-houses, civil kitchens and distribution of gratuitous relief in the villages. Both departments were considerably strengthened for the purpose, as it is now recognized that ordinary district staffs cannot cope unaided with the special circumstances of severe famine. As compared with the famine of 1892, crime statistics were light, and the public peace was well maintained throughout.

A notable feature of the famine was the enormous immigration of famine-stricken wanderers from Native States. In the beginning of the scarcity, thousands had passed through the districts on the way to their usual migration grounds of Mālwā and Gujarāt. But they

found famine there also, their cattle died, and as they struggled homewards they helped to swell the death rate and tax the resources of Merwara and Ajmer. It is estimated that half the inmates of

the poor-houses in the districts were foreigners.

The mortality during the famine itself was dwarfed by that of a terrible fever epidemic which followed, and in the autumn of 1900 caused the deaths of 44,236 persons. During the whole year a death-rate of 150 per 1,000 was reached in Merwāra and one of 112 in Ajmer. Infant mortality was especially high. Great numbers of cattle died in both districts, and it is calculated that Merwāra lost a half, including many of the more valuable animals. The Government forests were thrown open to grazing, but the grass was scanty and of little assistance. State importation of hay was also attempted, but private enterprise on the same lines proved more successful. When the rains came in 1900 liberal grants of takāvi and of money from the Indian Famine Charitable Relief Fund were made, and did much towards replenishing the stock of cattle from outside the province, and giving the people a fresh start. The cost of the famine was Rs. 47,64,866.

The great famine ended in the cold season of 1900. The rains had been plentiful, and both autumn and spring crops were fair. But in 1901, although the rains began well in July and August and secured the grass crop, they failed later, giving Merwāra an average of only 10.81 inches and Ajmer 12.91 inches. The result was a recurrence of

scarcity in the latter and of famine in the former district.

Test works were opened in Merwāra in January 1902 and were converted into regular relief works in the succeeding months. They were kept open until October of the same year, when relief of all kind was discontinued. They consisted of three tank works, at Kūkarkhera, Asan and Makrera, while 5 sections of roads were also improved and repaired. The number of persons upon relief touched its highest point (30,446), in the month of August.

In addition to the works under the Public Works Department, civil agency works were opened between May and July. Gratuitous relief was confined to doles distributed in cash in the villages: it was found unnecessary to open kitchens or poor-houses. Hospitals were main-

tained in connection with all the relief works.

No difficulty was felt regarding fodder for the cattle, and there was very little emigration. As the famine was entirely local, prices ruled low throughout. The public peace was well maintained, and there was no appreciable increase of crime.

The scarcity in Ajmer was of so mild a nature that very limited relief measures were sufficient. Only two test works were opened, and the workers never numbered more than 860. Gratuitous relief on a limited scale was given in certain villages.

The cost of relief during the famine, including the grants of takāvi to cultivators up to the end of September 1902, was Rs. 2,49,311.

The effects of the calamities of the past decade upon the numbers of the people have already been detailed in the chapter on Population. Between 1891 and 1901 the population of the province has

Famine of 1901-02.

declined 12 per cent. In the last two famines active measures of relief have largely reduced the deaths from actual privation, but epidemics of disease and especially the autumn fevers proved excessively fatal. The effects upon the social condition of the survivors have been equally apparent, and it will be long before the previous standard of comfort is attained by the cultivating classes. A tendency towards loss of self-respect and reliance has also been remarked, and each succeeding famine finds the poorer classes more ready to clamour for and accept relief from Government. During the famine a loosening of family ties was sometimes evident; children were found showing greater signs of privation than their parents, while child desertion was a deplorably common feature among the wanderers from Native States.

Protective Measures. Protective measures, properly so called, are extremely hard to find in Ajmer-Merwāra. Irrigation can only be perfectly protective where the water supply is beyond being effected by the vicissitudes of rainfall. But the province has no large perennial rivers, and natural springs are rare. Increase of tanks and wells may do something, but most of them are dependent upon the monsoon for their water, and where that fails, remain dry and useless. What can be done, however, in this direction is being effected by loans under the Land Improvement Act of 1883. An attempt is being made to store grass in the forests as a provision against famine, and each villager contributes a head-load yearly. Such measures, however, can be only palliative in the face of severe scarcity. Fortunately the province is now well served by railways, and will shortly be even better. Importation of grain to meet local scarcity is easy, and unless famine is wide-spread throughout India, prices need hardly be affected. When the crops have failed, the further measures for protection of the people are prescribed in the Ajmer-Merwara Famine Code, now revised and improved according to the teachings of past experience. If the local officials are watchful and energetic they can hardly fail to be successful.

Ordinary private charity in times of famine cannot be much counted upon to supplement Government aid. This is due not so much to deficiency in quantity as to complete want of organization in distribution.

Langar-khūna of Dargūh Khwūja Sūhib. An exception is, perhaps, the institution attached to the Dargāh Khwāja Sāhib at Ajmer, known as the Lungar-khāna, the only permanent poor-house in the district. Two maunds and six seers of grain with six seers of salt are cooked and distributed to all comers before day-break in the morning, and the same quantity before 5 o'clock in the evening. The average daily attendance is about 900: no enquiry is made as to recipients. The expenses of the morning distribution are chargeable to the income from the Dargāh jāgīr villages, while those of the evening meal are met from a jāgīr given by the Nizām of Hyderābād. Besides the 1,570 maunds of grain which are thus yearly consumed, 644 maunds are annually distributed to infirm women, widows and other deserving persons at their own houses. During the last famine an extra amount of grain was added at each distribution, both morning and evening. Rs. 1,644 per

year are spent in fees to hakims and doctors for attendance upon the poor sick. The normal cost of the charity is about Rs. 5,000 per annum. It is controlled by two $d\bar{a}rog\bar{a}s$, under a manager appointed by the Dargāh committee. They receive their pay from the funds of the Dargāh. The cost of supervision is a somewhat high percentage of the total expenses.

centage of the total expenses.

The Indian Charitable Relief Fund, supplemented by local subscriptions and distributed by Government officers, did much to relieve

distress during the recent famines.

CHAPTER XI.

GOVERNMENT.

General Administration. The two tracts of Ajmer and Merwāra were originally distinct districts. After the British occupation they were administered by two Superintendents until 1842, when they were united under one officer bearing the title. Ajmer in 1832, and Merwāra in 1846, had been placed under the administration of the Government of the North-Western Provinces (now the United Provinces of Agra and Oudh), and in 1853 Colonel Dixon, who then had charge of them was appointed a Commissioner, and corresponded direct with that Government. From 1858 the united districts remained a Deputy Commissionership under the Agent to the Governor-General in Rājputāna and Chief Commissioner, Ajmer-Mewāra, who in his latter capacity was subordinate to the Government of the North-Western Provinces. In 1871 the province was taken under the direct administration of the Foreign Department of the Government of India and the arrangements then made still continue.

The Hon'ble the Agent to the Governor-General for Rājputāna is ex-officio Chief Commissioner, and performs the functions of chief revenue authority and the Local Administration, being also the highest court of appeal, both civil and criminal. In subordination to the Chief Commissioner, a Commissioner, whose head-quarters are at Ajmer, has direct charge of the districts. He has the powers of a Civil and Sessions Judge, and has the direct management of the Police, Forest, Jail and Education Departments. Beneath him are two Assistant Commissioners and District Magistrates, with head-quarters at Ajmer and Beāwar, and in charge of Ajmer and Merwāra respectively. Besides the Chief Commissioner, the administration is carried on by 36 officers, invested with various magisterial powers, while 23 are invested with various civil and revenue powers.

Sub-divisions.

Ajmer and Merwāra are further sub-divided into tahsīls, each in charge of a tahsīldār, who is assisted by a nāib tahsīldār. Ajmer proper has now only one tahsīl at head-quarters. Its area is 560°6 square miles; it contains 195 villages, with a population of 1,27,320. Formerly it had three tahsīls (Ajmer, Rāmsar and Rājgarh), which were established in order to provide constant supervision of the tanks. The Rājgarh tahsīl was abolished in 1858, and the Rāmsar tahsīl on the re-organization of the district in 1871. The owners of istimrār estates, which in area are more than double the khālsa, pay their revenue direct into the Ajmer Treasury without the intervention of a Sub-Collector. Under Ajmer is the sub-division of Kekri which is administered by an Extra Assistant Commissioner.

The urban area is 3:07 square miles and the population 7,053. It consists of one khālsa town, Kekri. The remaining parganās, Bhinai, Masūda, Sāwar, Pisāngan, Kharwa and Baghera, are held by istimrārdārs. The military cantonment of Nasīrābād with its surrounding hamlets also forms a civil sub-division measuring 8:58 miles, and with a population of 22,494. The parganās of Ajmer proper, or, as they are now called, chaklās, are five in number, Ajmer, Rāmsar, Gangwāna, Pushkar and Rājgarh. But for executive work the tahsīl is divided into five circles, Jethāna, Derānthu, Gangwāna, Srinagar and

Rāmsar, each under a circle officer, called girdāwur.

Merwāra is divided into two taheīls, that of Beāwar and that of Todgarh. A third tahsīl, Sāroth, was after Colonel Dixon's death amalgamated with Beāwar. The Beāwar tahsīl formerly contained four parganās, viz., Beāwar, Jhāk Chāng and Sāroth. Of these Beāwar was sub-divided again into Beāwar, Jawāja, Lotāna and Barkochrān. These names have now only a historical interest, and the term parganā is never used. Instead there are the three chaklās of Beāwar, Chāng and Shāmgarh, or for executive purposes the four circles of Beāwar, Shāmgarh, Kālinjar and Kotra. Each of these circles is under a girdāwar. The tahsīl has an area of 317·2 square miles comprising 228 villages, with a population of 49,132. The Todgarh tahsīl used to contain four parganās, of which Bhāilān was British territory, Kotkirāna belonged to Mārwār and Dewair and Todgarh to Mewār. It is now divided into the three circles of Todgarh, Bhāilān and Dewair, each with its own girdāwar. All revenue papers, registers and returns are prepared according to these circles. The Todgarh tahsīl contains 87 villages, has an area of 269·9 square miles and a population of 38,399.

Both in Ajmer and Merwāra all the purely revenue work is in the charge of an officer called the Revenue Extra Assistant Commissioner, who has his head-quarters at Ajmer. All the registers and files relating to revenue matters are kept by him, but in each district he

acts under the control of the Assistant Commissioner.

Beneath the tahsīldārs, who have general revenue executive powers within the limits of their tahsīls, come the girdāwars, whose duty is to supervise, verify and correct the working of the various village officers within their circles. Of these the patwāris are the village accountants. As a rule each has two or more villages in his charge, and is sometimes helped by an assistant patwāri. Except that they do not collect the revenue, their duties do not differ from those of the patwāri in ordinary British districts. They maintain the village accounts and registers, and watch the interests of Government within their limits.

Putels and lumbardars, with functions almost identical, are the representatives of the village communities. Their chief duty is that of collecting and paying the Government revenue and cesses. There may be one or two or more to every village, according to its size and the amount of revenue due from it. Their numbers were fixed at the time of the last Settlement according to this standard, and they

Revenue Officers. are paid five per cent. on the revenue collected by them. Patels pay 4 less than the ordinary rate in their holdings, and are further remunerated by Rs. 3-2-0 per cent. allowance on the crop-rate tank water revenue collected by them. They defray the village expenses in the first instance, supervise the accounts of the village common lands, and represent the community in all their dealings with Government.

The village autonomy of former times has almost entirely passed away. Perhaps the only existing survival is the management of the shāmlāt, or village common lands. This is carried on by the lambardārs, who render accounts to the villagers of all receipts, payments and sources of income. In a few places, such as Rāmsar, Kekri and Ajmer shāmlāt committees are appointed for a similar purpose. In other matters the intervention of the revenue officials or of the civil courts has superseded the village council.

CHAPTER XII.

LEGISLATION AND JUSTICE.

Ajmer-Merwāra has no local Legislative Council. Local rules and orders are framed by the Chief Commissioner, either under General Acts of the Governor-General in Council or under Local Regulations made under the statute 33 Victoria Cap 3. Among the more important of the former, since 1880, may be mentioned the Vaccination Act, the Land Improvement Loans Act of 1883, the Agriculturalists' Loans Act of 1884, the Excise Act of 1896, and the Epidemic Disease Act of 1897; and among the latter the Ajmer Municipalities Regulation of 1886 and the Ajmer Rural Boards

Regulation of the same year.

The system of administration of civil and criminal justice is the same as in force in other non-regulation British Provinces. On the side of civil justice the lowest courts are those of the Munsiffs, with civil powers up to Rs. 100. They are exercised by the tahsīldārs of Ajmer, Beawar and Todgarh, and by the naib tahsildars of the same places. The istimrārdārs of Bhinai, Pisāngan, Sāwar, Kharwa, Bāndanwāra and Deoliā have also these powers. Appeals from the Munsiffs' Courts lie to the Sub-Judge, 1st class, within whose jurisdiction they are, and from them to the court of the Commissioner as District Judge. The Chief Commissioner is the High Court for appeals from decisions of the Commissioner. Civil powers up to Rs. 500 are exercised by the Cantonment Magistrate, Deoli, and the Revenue Extra Assistant Commissioner, Ajmer-Merwara. appeals lie to the Sub-Judge, 1st class, entrusted with appellate

The following officers have powers as Subordinate Judges of the 1st class in all suits up to Rs. 10,000: the Assistant Commissioners of Ajmer and Merwara; the Cantonment Magistrate, Nasīrābād; the Judicial Assistant Commissioner, Ajmer; the two Extra Assistant Commissioners, Ajmer; the Extra Assistant Commissioner, Kekri; and the Deputy Magistrate, Beawar. Of these only the Assistant Commissioners of Ajmer and Merwara and the Judicial Assistant Commissioner, Ajmer, have appellate powers. Appeals lie from their courts to the Commissioner as District Judge, and thence to the Chief Commissioner as High Court. Small Cause Court powers up to Rs. 500 are also exercised by the Assistant Commissioner, Merwara; the Cantonment Magistrate, Nasirābād; the Extra Assistant Commissioner, 2nd grade, Ajmer; and the Deputy Magistrate, Beāwar; and up to Rs. 20 by the Registrar Small Cause Court, Ajmer. The applications for revision in Small Cause Court cases lie only to the Chief Commissioner.

Legislation.

Civil and Criminal Justice.

Civil Justice.

During the ten years ending in 1890, the number of suits for money or moveable property instituted annually in the subordinate civil and revenue courts averaged 2,675.2. In the next decade the average rose to 2,936.2, while in 1902, 3,190 were instituted. The steady rise may be ascribed to the increase in private indebtedness due to the famine. On the other hand the average number of suits for title fell from 376.4 to 264.4 in the last decade. In times of famine such suits in which both parties are usually of the cultivating classes, must diminish from want of means to pay the fees. A reviving prosperity is shown by an increase in these suits to 317 in 1902. Rent suits were similarly affected, and the average fell from 557.9 in 1880-90 to 461.7 in 1890-1900. In 1902, 451 were instituted. Litigation in Small Cause Courts also shows a steady fall. The average number instituted annually was 5,672 between 1880-90, 4,888 between 1890-1900 and 4,790 in 1902.

Criminal Justice.

The Chief Commissioner acts as a High Court for the purpose of appeals from the Commissioner, who exercises the powers of a Sessions Judge for Ajmer-Merwāra. Below him the Assistant Commissioners of Ajmer and Merwāra are District Magistrates within their respective charges. The Cantonment Magistrate, Nasīrābād; the Judicial Assistant Commissioner, Ajmer; the two Extra Assistant Commissioners, Ajmer; the Extra Assistant Commissioner, Kekri; the Deputy Magistrate, Beāwar; and the Assistant Commissioner of Didwāna are Magistrates 1st class. Their appeals lie direct to the Sessions. The Cantonment Magistrate, Deoli; the tahsīldārs of Ajmer, Beāwar and Todgarh; and the Honorary Magistrates, Ajmer and Beāwar, have 2nd class powers, from which appeals lie to the District Magistrates.

The nāib tahsīldārs have 3rd class powers, as have also the Honorary Magistrates of Bhināi, Pisāngan, Sāwar, Kharwa, Bāndanwāra and Deolia. With the exception of Bhinai, of which the istimrardar is a minor, the local istimrardars are Honorary Magistrates. During the ten years ending 1890 the annual averages of persons tried for offences against the Indian Penal Code and for offences against local and special laws were 6,218.7 and 2,782.8 respectively. In the next decade the figures were 4,227.1 and 4,074.9. In 1902 they were 3,356 and 3,997 respectively. It is a notable fact that, though the decade ending in 1900 included several years of famine and scarcity, the average annual number of trials for offences against persons and property had fallen as compared with the figures for the preceding 10 years of comparative prosperity. They were 3,8667 as against 5,519 7 for the previous decade. In 1902, 3,086 such cases were tried. Offences against special and local laws, however, rose from an average of 2,7828 between 1880-90 to 4,0749 for the next ten years. Taking all offences, the average annual number of persons tried and percentage of convictions were 9,001.5 and 42.6 for 1880-90, 8,302.0 and 65.0 for 1890-1900 and 7,353 and 68.1 for 1902. The steady decrease in cases and increase in percentage of convictions point to the growing efficiency of the police force.

There are seven Registration offices in Ajmer-Merwāra, the number remaining unchanged since 1881. The Commissioner is the Inspector-General of Registration, while the Assistant Commissioner of Ajmer is the Registrar of Assurances in Ajmer-Merwāra. The average number of documents registered annually between 1881-90 was 1,360.5 and in the next decade 1,681.6. In 1902, 1,711 documents were registered.

Registration.

CHAPTER XIII.

FINANCE.

Finance in former times]

Little can be said regarding the finance of the native rulers of Ajmer-Merwara before the British occupation. In Merwara, with its wild tribes and jungles, such record is of course blank. Even of Ajmer we have little information on the point before the time of the Marāthā invasions, and how much of the immense revenues of the "Great Mughal" came from that province, it is difficult to say. In the treaty of cession with Sindhia the revenue of Ajmer was valued at 5,05,484 Srishāhi, or 4,50,986 Farukhābād rupees. But this was admittedly a considerable exaggeration. Neither Tantia nor Bapu Sindhia had ever collected more than Rs. 3,76,740 from the district, and of this sum Rs. 31,000 was the amount at which the customs had been farmed, the remainder being land revenue. Of this land revenue the assessment of the istimrāri area was Rs. 2,16,762, that of the khālsa Rs. 1,28,978. The system of Marāthā financial administration was practically to exact all that could be paid, but about nine years before the cession a kind of settlement had been concluded in the istimrār and khālsa areas, in accordance with which it had been arranged that instead of recent arbitrary enhancements of the istimrar revenue, all future augmentations should take the form of taxes or levies, and the land revenue of the khālsa was shown as a fixed sum, Rs. 87,639, while the remainder was to be collected in the shape of a number of extra cesses. The object of this arrangement was two-fold. The istimrardars were anxious that the arbitrary exactions should not be consolidated with the original revenue, lest on a change of rulers it might be difficult to obtain their remission, and the Governor of Ajmer only sent to Gwalior the land revenue proper, and appropriated to himself the extra collections. The khālsa villages were farmed for the amount of the acn, and the extra cesses were levied under 44 heads. Of these, a tax called nandrak, equal to 2 per cent. over and above the aen, was the perquisite of Sindhia's wives. A similar tax was denominated Bhet Bai Sahiba, and was an offering to his sister; and his daughter and his Pir (spiritual director) received respectively Rs. 2 and Re. 1 from each village. The produce of these four cesses was sent to Gwalior and the Governor appropriated the produce of the remaining 40 exactions. The chief was Fauj kharch, levied on account of the expenses of maintaining troops for the protection of the villages. This was uncertain in amount, and varied with the ability of the people to pay and the power of the Governor to compel payment. Patel bāb and bhūm bāb were percentages levied from patels and blumias. There were numerous offerings at all the Hindu festivals. There were charges on account

FINANCE. 85

of every act of civil government and sundry arbitrary cesses uncertain in amount. The actual collections from the khālst area in 1818, the

year before the cession, amounted to Rs. 1,15,060.

The question of the currency caused considerable difficulty to the first British Superintendent of Ajmer. None of the East India Company's coins were current further south than Jaipur, but there were six principal mints, of which coin was current in Ajmer. The Ajmer mint had been established since the time of the Emperor Akbar, and turned out yearly about a lakh and a half of rupees called Srishāhi. The Kishangarh rupee was struck at Kishangarh, and the mint had been established about 50 years, although frequently suppressed by the rulers of Ajmer. The Kuchāwan rupee was struck by the Thakur of Kuchāwan in Mārwār without the permission of the Mahārāja, who was too weak to assert his rights. The Shāhpura mint had been established for some 60 years, in spite of the attempts of the Rana of Udaipur to suppress it. The Chitori and Udaipuri rupces were the standard coins of Mewär, and the Jhārshāhi rupee was struck at Jaipur. Mr. Wilder cut the knot of the coinage difficulty by concluding all transactions on the part of Government in Farukhābād rupees, and receiving only these in payment of Government revenue. The fixed revenue of the istimrāri estates he converted from Srishāhi into Farukhābād currency, and it is on this account that the istimrāri revenue payable by each Thakur consists of rupees, annas and pies.

The first few years of the British occupation saw few improve-ments in financial administration, and many old abuses, both in the customs and revenue departments, were continued merely because they brought in money. The Maratha taxes were at first retained in their integrity. Māpa was the most vexatious, being a duty levied on the sale of every article in every village. Originally it was levied at the rate of Rs. 1-6 per cent. from persons not residing in the place in which the articles were sold, so that the every-day transactions between the inhabitants of the same place were exempt, and the burden fell on what may be called the external trade of the village. Mr. Wilder levied the transit duty on the maund instead of on the bullock or camel load as had before been customary; but his successor, Mr. Cavendish, introduced other provisions which still further fet-He extended the $m\bar{a}pa$ tax to all towns as well as villages, and to the transactions between the inhabitants of the same place, and raised the rate to Rs. 2-6-0 per cent. He established a new duty in the towns of Ajmer and Kekri on the sale of sugar, tobacco, rice and ghi, and for the transit trade introduced a system of rawanas, which fell with unmitigated severity on all but the richer merchants. No goods were allowed to enter the district without a pass, and all merchants were required to file a petition to take out a pass, and again on the arrival of the goods within the precincts of the district, or at the city of Ajmer, to subject them to examination and weighment, and thus prove their exact identity with the species and quantity mentioned in the ranvana. In order to prevent their goods being stopped on the frontier, the mercantile firms at Ajmer

Currency.

Early Taxa-

were obliged to obtain from their correspondents previous information of any despatches of goods, particularizing every article, and then a pass had to be procured and sent to meet the goods on the frontier. On the recommendation of a Committee in 1836, Government abolished this system, and restricted the customs taxes to a transit duty to be levied once for all on the import of foreign goods into the district, whether intended for domestic consumption or for re-exportation. To avoid vexatious enquiries, the tax was directed to be taken on the bullock or camel load at a fixed sum.

These orders do not appear to have been acted on, for many of the old abuses seem to have been as rife as ever in 1859, when the Deputy Commissioner complained that if a cultivator in a village a mile from Ajmer wished to sell a seer of ght in the city, he had to procure a pass from the customs agent in his village, stating his name and abode, and specifying the goods taken for sale. On arrival at the town he was obliged to have his goods examined again to see if they agreed with the pass, and export duty was still levied. In 1860 Government sanctioned other reforms, all in the direction Export duties were abolished and the of the orders of 1836. customs tax remitted on 18 articles, while the duty on 17 articles was considerably reduced. The whole district was consolidated into one circle, whereby the separate duties formerly levied in Merwara and the pargana of Sawar ceased. By these reforms the dutiable articles were reduced to 37, of which the duties on cotton, $gh\bar{\imath}$, salt, tobacco, cloths, blankets and opium chiefly affected the produce of the district. The revenue from these customs before 1860 averaged about one lakh, and from that year till 1868 about Rs. 1,12,000.

In 1869 customs were entirely abolished and trade became free as far as Ajmer was concerned, excise being levied once for all on the North-Western Customs line.

Between 1868 and 1871; while Ajmer-Merwära was subordinate to the Government of the North-Western Provinces, the revenues of the districts were part of the financial system of that Government. But in 1871 the province was formed into a Chief Commissionership under the Foreign Department of the Government of India, and was given a Commissioner of its own, and since then, as it is directly administered by the Government of India, no financial contract applies to its revenue and expenditure.

The revenues are divided into Imperial revenue and Local receipts. The latter include the incorporated and excluded Local funds and Municipal funds.

During the decade ending in 1890, Imperial revenues averaged Rs. 11,10,405, and Local receipts Rs. 2,87,674, while Imperial expenditure averaged Rs. 5,00,230, and Local Rs. 2,83,264. In the next ten years the average of Imperial and Local revenues had increased. They were Rs. 11,56,278, and Rs. 3,53,565 respectively. In the Imperial

During the decade ending in 1890, Imperial revenues averaged Rs.

FINANCE. 87

balanced by a large increase in receipts from assessed taxes. In the Local receipts the advance was principally in the Municipal funds, which showed an increase of about Rs. 50,000. Expenditure had, however, risen also, and the average under the head Imperial stood at Rs. 9,91,990, under Local at Rs. 3,55,578. The former was due to the enormous expenditure on famine relief and public works rendered necessary by the calamities of the decade. In 1902-03, Imperial receipts stood at Rs. 11,86,187, while Local receipts rose to Rs. 4,13,012, Municipal funds again claiming the lion's share of the increase. Imperial expenditure in this year reached a total of Rs. 9,49,882. Local expenditure is shown as Rs. 3,64,073 of which Municipal expenditure amounted to Rs. 2,17,208. Much of the Municipal finance consists of book transactions, octroi being paid on import, and refunded upon re-export of the scheduled commodities.

In 1902-03, the khālsa land revenue, including water revenue in the Ajmer tahsīl, amounted to Rs. 1,04,957, the revenue from stamps to Rs. 1,47,774, from income-tax Rs. 64,589, and from local cesses Rs. 20,240. Opium and excise gave Rs. 1,16,322. In the Beāwar tahsīl for the same year the land revenue—including water-revenue—came to Rs. 25,525; Rs. 31,997 were derived from the sale of stamps, Rs. 7,899 from income-tax, and Rs. 1,852 from local cesses. Miscellaneous receipts amounted to Rs. 1,115. Owing to bad harvests in the tahsil much of the land revenue and local cesses had to be suspended. In the Todgarh tahsīl the land revenue for the year was Rs. 33,402; Rs. 2,501 were received from the sale of stamps and Rs. 4,888 from excise. Income-tax gave Rs. 1,246 and local cesses Rs. 10,322. Rs. 565 were derived from other sources of

general revenue.

CHAPTER XIV.

LAND REVENUE AND TENURES.

Tenures.

The land tenures of Ajmer are, as might be expected, entirely analogous to those prevailing in the adjacent Native States, and though they have been often misunderstood, yet the vis inertia of the province has sufficed to prevent their being interfered with, except in the one instance of the mauzāhwār settlement of 1850. The soil is broadly divided into two classes: khālsa, or the private domain of the crown; and zamīndari, or land held in estates or baronies by feudal chiefs who were originally under an obligation of military service, but who now hold on istimrar tenure. Khatsa land again might be alienated by the Crown, either as an endowment of a religious institution, or as a reward for service to an individual and his heirs. Such grants, when they comprised a whole village or half a village, are termed jagins, and fifty-one whole villages and three half villages have been alienated in this way.

Khālsa.

The basis of the land system is, that the State is in its khālsa lands the immediate and actual proprietor, standing in the same relation to the cultivators of the soil as the feudal chiefs do to the tenants on their estates. The jāgīrdārs, who are assignees of the rights of the

State, have the same rights as the State itself.

From ancient times, however, it has been the custom in the khālsa land of Ajmer that those who permanently improved land by sinking wells and constructing embankments for the storage of water, acquired thereby certain rights in the soil so improved. These rights are summed up and contained in the term biswāhdāri, a name which is synonymous with the term bapota in Mewar and Marwar, and with the term mirās in Southern India, both of the latter words signifying "heritable land." A cultivator who had thus expended capital was considered protected from ejectment as long as he paid the customary share of the produce of the improved land, and he had a right to sell, mortgage, or make gifts of the well or embankment which had been created by his capital or labour. The transfer of the well or the embankment carried with it the transfer of the interaction words signifying "heritable land." A cultivator who had thus expended capital considered owner of this as well as of the waste. A cultivator without a well, or at any rate an erabankment, was looked on as, and must always be, a wrif with no tie to bind him to the viliage where he may reside. No man, in fact, cultivated the same unirrigated fields continuously, the village boundaries were undefined, there was always more unirrigated land round a village than could be cultivated by the number of ploughs, the State exercised the right of locating new hamlets and new tenants, of giving leases to strangers who were willing to improve the land, and of collecting dues for the privilege of grazing over the waste from all tenants, whether bisvāhdārs or not

The first two Superintendents of Ajmer were of opinion that waste lands were the property of the State. Their successor, whose experience was gained in the North-West Provinces, considered them to belong to the village community. Mr. Edmonstone, who made a ten years' settlement in 1835, investigated the question, and was clearly

of opinion that the State was the owner.

When Colonel Dixon commenced the construction of his tank embankments in 1842, he acted as steward to a great estate. He founded hamlets where he thought fit, he gave leases at privileged rates to those who were willing to dig wells, and distributed the lands under the new tanks to strangers whom he located in hamlets in the waste. In no instance did the old biswāhdārs imagine that their rights were being invaded, nor did they consider themselves entitled to any rent from the new-comers. The latter had the same rights as to sale and mortgage of improved land as the old biswāhdārs.

Such was the tenure of the khālsa land of Ajmer till the year 1849, when the village boundaries were for the first time demarcated, and under the orders of Mr. Thomason a village settlement was intro-This settlement effected a radical change in the tenure. It transformed the cultivating communities of the khālsu, each member of which had certain rights in improved land, but who, as a community, possessed no rights at all, into bhyāchāra proprietary bodies. The essence of the mauzāwār system is, that a defined area of land—that, namely, which is enclosed within the village boundaries—is declared to be the property of the village community, and the community consists of all those who are recorded as owners of land in the village. change, however, was unmarked at the time, and was only slowly appreciated by the people. In many cases where Colonel Dixon established a new hamlet, he assessed it separately from the parent village, i.e., the revenue assessed on each resident of the hamlet was added up and announced to the headman of the hamlet. The waste remained the common property of the parent village and of the hamlets. In 1867 these hamlets were formed into distinct villages, the waste adja-The biswahdars of the cent to the hamlet being attached to it. parent village retained no right over this land, nor do they imagine that they possess any. In this way there are now 195 khālsa villages in Ajmer, against 85 at the time of Colonel Dixon's settlement.

Until the mauzāwār system of 1850, the tenure in the khālsa was ryotwāri. The State owned the land, but allowed certain rights to

tenants who had spent capital on permanent improvements in the land so improved. This collection of rights gradually came to be considered proprietary right, and since 1850 the State has abandoned its exclusive and undisputed right of ownership over unimproved land.

Istimrār.

The tenure of the feudal chiefs was originally identical with that of the Chiefs in the Native States of Rājputāna. The estates were $j\bar{a}g\bar{\tau}rs$ held on condition of military service, and liable to various feudal incidents. Colonel Tod, in his Rājasthān, Volume I, page 167, thus sums up the result of his enquiries into the tenure:—"A grant of an estate is for the life of the holder, with inheritance for his offspring in lineal descent or adoption, with the sanction of the Prince, and resumable for crime or incapacity; this reversion and power of resumption being marked by the usual ceremonies on each lapse of the grantee, of sequestration (zabti), of relief ($nazarān\bar{a}$) of homage and investiture of the heir."

The original tenure of the mass of the istimrār estates in Ajmer is exactly described in the above quotation. The grants were lifegrants, but like all similar tenures they tended to become hereditary.

None of these estates ever paid revenue till the time of the Marathas in 1755 A.D., but were held on condition of military service. The Marāthās, however, wanted money more than service, and assessed a sum upon each estate, presumably bearing some relation to the number of horse and foot soldiers which the Chief had been liable to furnish. Naturally, however, the assessment was very unequal, as a much larger proportion of their income was taken from the weaker Chiefs than from the more powerful thakurs, whom it might have been difficult to coerce. On the cession of the district in 1818 A.D. the tālukdārs were found paying a certain sum under the denomination of māmla or āen, and a number of extra cesses, which amounted on the whole to half as much again as the māmla. These extra cesses were collected till the year 1841, when, on the representation of Col. Sutherland, Commissioner of Ajmer, they were abandoned. In 1830, 1839, and 1841 the Government of India had declared that the estates were liable to re-assessment, and had given explicit orders for their re-assessment, but these orders were not acted on, nor apparently communicated to those concerned. The Chiefs who at a very early period of our rule, perhaps even before it, had acquired the title of istimrārdars, no doubt considered themselves as holders at a fixed and permanent quit-rent. This belief of theirs was strengthened by the action of Government in 1841, when all extra cesses were remitted avowedly on the ground that they were "unhallowed Marāthā exactions," and the demand of the State was limited to the amount which had been assessed by the Marāthās nearly a century before. Finally, in 1873, Government consented to waive its right in the matter of re-assessment, and to declare the present assessments of the Chiefs to be fixed in perpetuity. This concession was accompanied by declaration of the liability of the estates to pay nazarānā on successions, and the conditions on which the istimrārdārs now hold have been incorporated in the sanad which was granted to each of them.

There are in all 66 estates, containing 230 villages, with an area of 8,19.52.3 acres. The istimrār revenue is Rs. 1,14,734-9-11, and the estimated rent roll of the istimrārdārs is Rs. 5,59,1 8. In 60 estates, all held by Rājputs, the custom of primogeniture now prevails. Of these, however, 11 only are original fiefs, the remainder having been formed by sub-division in accordance with the rules of inheritance. Originally all the sons divided the estate, although the elder got a larger share than the others. In the next stage the eldest son succeeded to the estate as well as to the gādi, while provision was made for the younger sons by alienation to them of villages on grās tenure. The last instance of such alienation occurred in 1823. In the third stage the provision of the cadets of the house is limited to grant of a well and a few bighās of land for life. But nowadays the younger tend to become mere hangers-on at the elder brother's table. Some provision for them is considered imperative on every istimrārdār.

There are six estates, each of a single village, the tenure of which differs from that above described. Five of these are held by co-parcenary bodies, succession is regulated by ancestral shares, and both land and revenue are minutely divided. In one village, Karel, belonging to a community of Rāhtors, the property of the two chief men of the village is distributed on their death into one share more than there are sons, and the eldest son takes a double share. Rājosi stands apart from all other istimrār estates. It belongs to a Chita, who is sole istimrārdār, but the land is owned not by him but by the actual cultivators from whom he collects a fixed share of the produce, and himself pays a fixed revenue to Government. One of these villages, Kotri, belongs to Chārans or Bhāts, and was originally separated from the istimrār estate of Bhinai. The other five were stated by the kānāngos in the time of Mr. Cavendish to be khālsa villages, and they probably

should not have been included in the istimrār list.

The subordinate rights in the *istimrār* area have never formed the subject of judicial investigation, nor with the exception of six small estates, have settlement operations been extended to the *istimrār* area. The principle followed under our rule has been to leave the *istimrārārdārs* to manage their own affairs, and to interfere with them as little as possible. It is well known, however, that in most of the larger estates there are villages held by Chārans, Jogis, and others, and villages held by sub-tālukdārs, relations of the *istimrārdār*, who generally pay an unvarying amount of revenue to the head of the family, and who are succeeded in the sub-talukās by their eldest sons. As a general rule *jāgir* villages are not resumable, nor can the sub-tālukās be resumed except for valid cause assigned.

The istimrārdārs have always claimed to be owners of the soil, and their claim has been allowed. The prevailing opinion is that all cultivators are tenants at will, but there are good grounds for hesitating to adopt this opinion. Mr. Cavendish's enquiries extended to 296 villages, and in 158 villages the thākurs disclaimed the right of ouster of cultivators from irrigated and improved lands where the means of irrigation or the improvement had been provided by the

labour or capital of the cultivators. In 161 villages were found hereditary cultivators whose rights were the same as those of the owners of wells. Unirrigated and unimproved land was universally admitted to be held on a tenure at will from the istimrardur. Disputes between an istimmardur and his tenants seldom come before our courts. Whatever rights of ouster the former possesses are rarely

put in practice by him.

The subject of jagar estates was investigated by a mixed committee of Government officials and jagirdars in 1874, and their report contains a history of each estate. Out of a total area of 1,50,838 acres, yielding an average rental of Rs. 91,000, 65,472 acres belong to the endowments of shrines and sacred institutions. The remaining jagira are enjoyed by individuals and certain classes specially designated in the grants. No conditions of military or other service are attached to the tenure of any *jāgīc*.

In all jugar estates the revenue is collected by an estimate of the produce, and money assessments are unknown. As was the case in the khalsa before Colonel Dixon's settlement, the ideas of rent and revenue are confounded under the ambiguous term hāsil, and until the year 1872 the relative status of the jägirdörs and cultivators as regards the ownership of the soil was quite undefined. In that year it was decided that all those found in possession of land irrigated or irrigable from wells or tanks, which wells or tanks were not proved to be constructed by the jägürdür, were owners of such land. The jāgīrdār was declared owner of irrigated land in which the means of irrigation had been provided by him, of unirrigated land, and of the

Bhām.

Jügir.

The tenure known as blown is peculiar to Rajputs. The word itself means "the soil," and the name *bhāmiā* properly signifies "the allodial proprietor," as distinguished from the feudal Chiefs and the tenant of crown lands. According to Colonel Tod's Rajasthan, Vol. 1, page 168, the *bluimins* in Märwär are the descendants of the earlier princes who, on the predominance of new claus, ceased to come to court and to hold the higher grades of ranks. They continued, however, to hold their land, and became an armed husbandry, nominally paying a small quit-rent to the crown, but practically exempt. In course of time the various kinds of bloom grew up, which, unlike the original allodial holding, were founded on grants, but had this apparently in common, that a hereditary, non-resumable, and inalienable property in the soil was inseparably bound up with a revenue-free title. Bloom was given as moradkati, or compensation for bloodshed, in order to quell a feud, for distinguished services in the field, for protection of a border, or for watch and ward of a village. Whatever the origin of a blown holding, however, the tenure was identical, and so cherished is the title of bhāmiā that the greatest Chiefs are solicitous to obtain it even in villages entirely dependent on their authority. The Mahārāja of Kishangarh, the Thākur of Fatehgarh, the Thākur of Junia, the Thakur of Bandanwara, and the Thakur of Tantoti are among the bhumius of Aimer.

There are in Ajmer 109 $bh\bar{u}m$ holdings, and except in those cases where a Rājā or $istimr\bar{a}rd\bar{a}r$ is also a $bh\bar{v}mi\bar{a}$, the property passes to all the children equally. It is probable that none of these holdings are original allods, but belong to the class of assimilated allods. These $bh\bar{u}mi\bar{a}s$ are nearly all Rāhtors, descendants of younger branches of $istimr\bar{a}r$ families, and cannot claim an origin higher than that of the estates from which they sprang. Whatever the origin of the holdings, however, the rights and duties of all $bh\bar{u}mi\bar{a}s$ came in course of time to be identical. At first the land was revenue-free, subsequently a quit-rent was imposed but irregularly collected, and this quit-rent was abolished in 1841 along with the extra cesses from the $istimr\bar{a}rd\bar{a}rs$. The duties of the $bh\bar{u}mi\bar{a}s$ were three in number: first, to protect the village, in which the $bh\bar{u}m$ is, and the village cattle from dacoits; secondly, to protect the property of travellers within their village from theft and robbery; and thirdly, pecuniarily to indemnify sufferers from a crime which they ought to have prevented.

This last incident is a peculiar feature of the Ajmer tenure, and grew out of the custom of Rājputāna that the Rāj should compensate losses of travellers by theft or robbery committed in its territory. This custom is still carried out by the inter-statal Court of Vakils. Where the theft or robbery has occurred in a village belonging to a fief, the chieftain to whom the village belongs is called on to indemnify the sufferers; and the istimrārdārs of Ajmer have always been compelled to indemnify sufferers from thefts and robberies committed on their estates. Similarly a jāgārdār, to whom the State had transferred its rights and duties, was pecuniarily liable. In case of theft in a khālsa village the State was called on to pay compensation. In Ajmer, the State finding this responsibility inconvenient, transferred it to a bhāmiā as a condition of the tenure; but in khālsa villages, where there were no bhāmiās, the State remained

responsible.

However useful the system of pecuniary indemnification may have been, and, however well adapted it was to the times of anarchy in which it had its birth, there is no doubt that in Ajmer it had long been moribund. When the average rental enjoyed by a bhūmiā is only Rs. 17 a year, it is hopeless to expect that more than a very few bhūmiās could compensate even a moderate loss. As soon as the Native States adopted a system of regular police, this distinctive feature of the bhūm tenure vanished, and Government in 1874 sanctioned a proposal to abolish the pecuniary responsibility, and to revert to what seemed to be the original incidents of the tenure, to hold the bhūmiās liable as an armed militia, to be called out to put down riots and to pursue dacoits and rebels, and to take from them a yearly quit-rent under the name of nazarānā.

The above sketch shows that in khāka villages the State still possesses considerable proprietary rights. In istimrār estates, on the other hand, it has few or no rights beyond that of taking a fixed revenue and of a royalty on minerals. In jāgīr villages it has assigned its rights to others. To the State belong in sole proprietary

right all mines of metals in khālsa villages, while for its own purposes it can quarry free of payment where and to what extent it pleases. Two ranges of hills near Ajmer, that of Tārāgarh and that of Nāgpahār, have been declared to be the property of Government. The tank embankments of Ajmer have nearly all been made by the State, and Government is the owner of the embankments, and all that grows thereon. Under the forest ordinance the State has reserved to itself the right to resume from the village communities the management of any tract of waste or hilly land, the proprietary right subject to certain conditions being vested absolutely in Government as long as the land is required for forest purposes.

Tenures in Merwāra.

Merwara possessed no settled Government till 1822, when it came under British management. The people found the occupation of plunder more profitable and congenial than that of agriculture. No crops were sown except wha was actually necessary for the scanty The tanks were constructed and used solely for the population. purpose of providing water for the cattle. No revenue nor rent was paid. The Rajputs were never able to get a firm footing in the country. Whatever small revenue they could get from it was obtained at a cost both of life and money far exceeding its value. In such circumstances tenures could not spring up. Colonels Hall and Dixon, to whom the civilization of the Mers is due, treated Merwara as a great zamīndāri, of which they were the managers and Government the owner. Their word was law, they founded hamlets, gave leases, built tanks and collected one-third of the produce of the soil as revenue. At the settlement of 1851 all cultivators who had recently been settled in the villages were recorded as owners of the land in their possession equally with the old inhabitants.

Non-proprietary cultivators.

At the settlement of 1875 nearly all cultivators were recorded as proprietors, and a non-proprietary cultivating class hardly exists in the khālsa of either Ajmer or Merwāra. When they are tenants they pay generally the same share of the produce as the proprietors themselves paid before the regular settlement. Custom and not competition regulates the rate of rent. The istimrārdārs and jāgīrdārs collect their rents without the intervention of the Courts, and in these estates there is still more land to be brought under cultivation than there are cultivators for. The population has been periodically decimated by famine; and as no Rājput will, if he can possibly avoid the necessity, ever touch a plough, cultivators are still at a premium.

Revenue in former times.

Figures are not available to show what tribute Ajmer paid to the Mughal Emperors. The Marāthās never collected more than Rs. 3,76,740 from the district, and of this sum Rs. 31,000 was the amount at which the customs had been farmed; the remainder was land revenue. Of the land revenue amounting to Rs. 3,45,740, the assessment of the istimrār was Rs. 2,16,762, that of the khālsa Rs. 1,28,978. Under British rule the administration of the istimrār estates in Ajmer has been confined to collecting from them a fixed assessment, the thākurs and jāgīrdārs being left to manage their own affairs. The

following retrospect therefore will be restricted to the administration of the khālsa or Government villages in the province.

The actual collections from the knālsu in the year before the cession of Ajmer to the British on the 26th July 1818, amounted to Rs. 1,15,060. Mr. Wilder, Assistant to the Resident at Delhi, was the first Superintendent appointed to Ajmer. In the first year of his administration he decided to take the revenue in the khalsa at the rate of one-half the estimated out-turn of the crop. The collections for the year were Rs. 1,59,746, and Mr Wilder writes that the measure of an equal division of the crop had been productive of all the benefits The people had acquired confidence in the he had anticipated. moderation and justice of their no government, and though it would not be advisable for the next two years to demand any great addition to the increase that had already taken place, yet he was confident that on the third year the jana might be raised to double what it had reached under any preceding government without at all pressing on the inhabitants. He accordingly proposed a three years' progressive settlement-in the first year Rs. 1,79,437, in the second year Rs. 2,01,691 in the third year Rs. 2,49,303 His dominant if not sole anxiety appears to have been to increase the Government revenue. He furnished no information of the principle on which the demand had been fixed, nor of the grounds on which a progressive assessment had been resolved, and the settlement was confirmed with some hesitation by Government, who remarked on the proved disadvantages of an assessment framed on anticipated improvement, which checks the rising spirit of industry and the accumulation of capital.

Owing to two bad harvests the settlement broke down the first year. Mr. Wilder proposed to relinquish the balance and to make a settlement on a fixed annual jama of Rs 1,64,700. Both proposals were sanctioned by Government, the term of the settlement being fixed for five years. The assessment was fairly collected for the first four years, though in the last year the people were obliged to borrow to pay their revenue; but the fifth year was one of famine. Recourse was had to collecting one-half the produce, and the amount realized was Rs. 31,927. The next year was a good one, but the people objected to pay according to Mr Wilder's settlement, and the revenue was again collected kheim. Mr. Wilder had been transferred in December 1824, the middle of the famine year His six years' administration had not been productive of any great results. He took little pains to ascertain the value of the land he assessed, or the condition of the people, and the era of material improvement had not yet dawned. His administration was rather starved: the whole cost of the revenue and police establishment of the district was Rs. 1,374 a month, or less than half his own salary of Rs. 3,000.

Mr. Henry Middleton, also a North-West civilian, succeeded Mr. Wilder in December 1824. He was of opinion that monetary assess-

ments of any kind were unpalatable to the people, and if confidence could be reposed in the subordinate officers, the system of taking in

kind would be best. The experience, however, of the year 1825-26

Mr. Wilder's administration.

Re-adjustments between 1818 and 1841. rendered Mr. Middleton loth to adopt this system. Accordingly he proposed a five years' settlement, and reported its completion on the 26th November 1826. He had rough measurement rolls prepared, but he chiefly relied on the collections of the previous year as a criterion of resources. He remarks on the poverty of the people and the extortions of the money-lenders. Many cultivators who had come to the district in the first years of the British rule had been driven away again by bad harvests and high assessment. The wells had fallen into disrepair, and the people had no money to repair them. Mr. Middleton's settlement was sanctioned at Rs. 1,44,072 for five years.

The assessment, however, was only collected in the first of the years the settlement had to run, and that with considerable difficulty. Mr. Middleton did not remain long enough in the district to collect the next year's revenue, and made over charge to Mr. Cavendish in October 1827. He cannot be said to have initiated any useful

measures.

Mr. Cavendish, his successor, was a great reformer, and left the impress of his energy on every department of administration. To him the district is indebted for a very valuable collection of statistics regarding istimrar, bhūm and jāgīr tenures. He carried out, however, little of what he put his hand to, and the sanction which had been accorded to Mr. Middleton's settlement prevented his interference in the assessment of the khālsa. Mr. Cavendish considered that Mr. Middleton's assessment was too high for several reasons: "because the cultivated area has remained stationary since the time of the Marāthās, who only collected Rs. 87,689; because the rate of assessment exceeds half the produce; because no cultivator in the soil of Ajmer, which requires much trouble and expense, can afford to pay one-half the produce; because the assessment is collected not from the produce of the soil, but by a fluctuating and arbitrary tax; and because the assessment has been made on the basis of a favourable year's collections when corn was dear." Mr. Cavendish applied the rates to which he had been accustomed in Sahāranpur to Mr. Middleton's areas, and calculated that the assessment ought to be Rs. 87,645 instead of Rs. 1,44,072.

Along with other reasons, he gives what seems to be the real key to the over-assessment of the district, viz., that 1818-19 was a very good year in Ajmer, while, owing to the devastations of Amir Khān in the territory of Mewār and Mārwār, there was a large demand on all sides for grain, and prices were very high. Indeed, the first assessments of British revenue officers in newly-acquired districts almost invariably broke down through the error of over-estimating corn prices. They used to take the old war prices that prevailed during the anarchy preceding annexation, and they forgot that with peace and order came plenty and open markets. Mr. Cavendish recommended that people should not be pressed for their revenue in bad seasons. He also partially introduced an assessment of individual holding, a measure unknown to Mr. Middleton's settlement. He

lays stress on the point that remissions granted in a lump sum benefit not the real sufferers, but the tahsīldārs, kānāngos, patwārīs and patels. He introduced for the first time patwārīs' accounts, appointed them for many villages where there were none, and directed every patwārī to give a receipt. Although Government refused to revise the assessment, they directed that diligent enquiry as to the resources of each village should be made during the unexpired period of the settlement. Under Mr. Cavendish, however, remissions were regularly applied for and granted where there was a difficulty in paying, and the settlement was not worked up to in any year. He left the district at the end of 1831, the year of the expiry of the settlement. He writes that he had intended to make the settlement with patels, and to give to each tenant a statement showing the amount for which he should be individually responsible.

His successor collected on the principle established by Mr. Cavendish. Major Speirs did not attempt a settlement. He collected all he could, and the remainder was remitted by Government. In 1833-34, however, even the pretence of working on the settlement was abandoned. The season was a disastrous one. The *kharif* instalments were collected by an equal division of the scanty produce, and it was proposed to allow the people to keep the *rabi* revenue. In December 1833 charge was made over to Mr. Edmonstone, who in the following year made a summary settlement with reference to the deteriorated state of the country owing to drought, the demand of which was Rs. 1,19,302. If the villagers did not consent to his terms

the revenue was collected khām at half produce.

In the cold weather of 1835-36, Mr. Edmonstone proceeded to make a regular settlement, which, as it was subsequently sanctioned for ten years, is generally known by the name of the decennial settlement, and which was reported on the 26th May 1836. He was of opinion that the district had receded rather than advanced under the previous administration, and he adopted a method of his own for assessment. The villages were measured, and the cultivated area, amounting in all to 36,257 acres, classed into: chālī (well land), 8,989 acres; tālābī (tank land), 2,180 acres; and barani (dry land), 25,088 acres. He then assessed the cash-paying produce (Indian corn and cotton) area at the current money rates at the central market, and estimated the average produce per bigha of other crops. The Government share of one half, except in the case of putels and Mahajans, he converted into money by the average price current of the previous five years. He thus obtained a rough jamabandi amounting to Rs. 1,57,151, and then visited each village and fixed his demand with reference to the past fiscal history, present circumstances, and future capabilities of each estate. No villages were given in farm. Two small ones were held on the system of half produce, as they could not be brought up to his standard; the rest accepted his terms. The amount finally assessed was Rs. 1,27,525, or adding the khām villages Rs. 1,29,872.

Mr. Edmonstone describes the people as reckless, improvident, poverty-stricken, and much in debt. They were entirely in the power

of the Bohrās who furnished no accounts, and the debt to whom ran on from generation to generation. The settlement was made with the headman of each village in the belief that he generally acted in accordance with the wishes of the village community. The incidence of the assessment was Rs. 3-9 an acre, while the unirrigated area was nearly 69 per cent. of the cultivated. The settlement returns show 5,621 cultivators, 2,675 non-cultivators, 3,185 ploughs, and 1,575 wells.

Although the assessment of individual villages appears to have been fair and judicious, the great defect of the settlement was the very imperfect and inequitable manner in which the village assesssment was distributed over the holdings. Mr. Edmonstone introduced for the first time the principle of joint responsibility of all cultivators. It is evident that a cultivator who is assessed at half his produce in good and bad years alike cannot afford to pay for others who have migrated or given up agriculture. In the first year of the settlement the distribution over the holdings was proved to be quite inequitable, and the people began to clamour for a return to collections from the actual produce. Mr. Edmonstone had left Ajmer at the end of 1836, and his successor proposed to make a fresh distribution of the revenue, and to give each cultivator a separate lease specifying what rent he had to pay. As this was tantamount to changing the settlement from mauzāwār to ryotwār, Government would not sanction the proposal. But the villages were effered the option of returning to direct management, and 41 out of 81 villages accepted it.

In the meantime Colonel Sutherland became Commissioner. He took great pains to make himself acquainted with everything concerning Ajmer, and his reports on the khālsa administration and on the istimirardars are standard papers of reference. He strongly condemned the village assessment system as inapplicable to Ajmer, and looked to the repair and construction of tanks for a remedy. He advocated the mode of assessment which had been carried out by Captain Dixon in Merwara as that suited to the country, and consonant with the wishes of the people. Under this system lands under cotton, maize, sugar-cane and opium were charged with a money rate. Other rabi and kharif crops were estimated and measured, and onethird of the produce was taken as the Government share by a money assessment fixed according to the average yearly value of produce in the principal neighbouring markets. Land newly broken up paid one-sixth of the produce for the first year, one-fifth for the second, and one-fourth for the third and fourth years, after which the full rate of one-third was charged. A remission in the amount of the share was given to those who constructed embankments and dug new

It was evident that some remedial measures were necessary. The four years from 1837 to 1841 were years of severe distress, and at the time of Colonel Sutherland's report, 26th January 1841, the *khālsa* villages had reached the lowest depths of poverty. Many families had left the district owing to the pressure of revenue which they were unable to pay. The tanks were broken, the wells out of repair,

and the people were thoroughly demoralized. They preferred paying half the produce to accepting the reduced assessment of Mr. Edmonstone. For these deplorable results the previous settlements were largely responsible. The last and highest of them had an incidence per acre about twice as heavy as that made in the North-West Provinces. With the experience gained in these settlements the Government of the North-West might have concluded that its "trust that the settlement would prove moderate and be realized without distress to the people" was fallacious.

The success of Major Dixon's administration of Merwāra had for some time attracted the attention of Government and the Commissioner, and in February 1842 he was appointed Superintendent of Ajmer, in addition to his other duties as Superintendent of Merwāra

and Commandant of the Merwara Battalion.

From the date of his assuming charge a new era commences in the history of the administration of the country. Within the next six years Rs. 4,52,707 were expended on the construction and repair of embankments. Advances were made for agricultural improvements, and the Superintendent succeeded in infusing a good deal of his personal energy into the people. To enable Government to reap a benefit from the new works, sanction was procured to allow such villages as desired it to abandon their engagements. All were invited to return to *khām* management, and when a tank was made or repaired in one of the few villages which insisted on retaining their leases, a percentage of the cost was levied in addition to the assessment. The rate of collection at the same time was reduced from one-half to two-fifths, and the cash rates were also lowered. On the expiry of the ten years' settlement, the whole district was held *khām*, and managed as Major Dixon had managed Merwāra.

The system, however, depended for its success largely upon the energy and experience of one man, and was unsuited for general adoption. It was considered expedient to return to the system of village settlements, as the people had learned to recognize the principle of joint responsibility, and their land, from the means of irrigation with which it had been provided, possessed a higher and more uniform value than was previously the case. Arrangements were therefore made for a revenue survey, and instructions were issued to Major Dixon for the formation of a village settlement. Moderation was inculcated, and the standard to be aimed at was the punctual realisation of a jama equal to Mr. Edmonstone's assessment, and yielding over and above that amount a moderate profit on the money invested in tanks and reservoirs. This moderate profit was afterwards put at 5 or 6 per cent. These orders were followed by a year of severe scarcity, and at one time it was doubtful whether engagements for a fixed period could be entered into. The succeeding year, however, was a favourable one, and the settlement commenced from the kharīf harvest of 1849.

In making his assessment Colonel Dixon was guided chiefly by the experience he had gained of the capabilities of each village while Col. Dixon's Settlement. it was held under direct management. His method of assessment was as follows:—

He took Mr. Edmonstone's assessment and added to it 6 per cent. of the sum expended on tanks in that village. This was the standard. If the past history of the village warranted Colonel Dixon in believing that it could be paid, he assessed the village at this amount. If he thought it could pay more he assessed it at more; if he thought that it could by no possibility pay this amount, he reduced the standard. No rates were worked out till after the assessment, nor was any attempt made to compare the incidence of the revenue in different villages, or to explain its variations. The inequality of the assessment was no doubt tempered by Colonel Dixon's intimate knowledge of the district, but the system necessarily produced inequality. For all practical purposes of assessment the measurement of the villages in Colonel Dixon's time was superfluous. If 6 per cent. of the outlay on the tanks were added to the assessment of Mr. Edmonstone, the amount would be Rs. 1,58,273, and this was the amount proposed as a fair amount to distribute. The highest amount which had ever been collected was in 1847-48, when, at two-thirds the produce, the revenue stood at Rs. 1,67,237, and this included all the cesses. Colonel Dixon's actual assessment, excluding the 1 per cent. road cess, but inclusive of the tank cess of 1 per cent., which was merely a deduction from the Government revenue set apart for a particular purpose, was Rs. 1,75,756, or, adding the assessment which was subsequently made on Nearan and Karanipura, Rs. 1,85,161. The assessment was lighter than Mr. Edmonstone's, but the unirrigated area had increased in greater proportion than the irrigated, and the average rate of assessment on a total area, including 28 per cent. of irrigation, was Rs. 2-0-3 per acre.

The best description of the settlement is that given by Colonel Dixon himself in a demi-official letter to Sir Henry Lawrence, dated 25th January 1856:-"If the season be moderately favourable and the talaos be replenished, the rent will be paid with ease and cheerfulness by the people. If drought ensues, we have been prepared to make such a remission that distress in paying the revenue shall not reach the people. It is necessary to bear in mind that we have given the profits to the people, ourselves bearing the onus of loss. In a country like Ajmer-Merwara, where the seasons are so extremely irregular, to burden the zamīndārs with arrears of rent on account of what was not produced would check the energies of the people, and render them less industrious than they now are, when they know we shall only claim the rent or a portion of it, when it has been assured to them by Providence. To have made the jama less would have been to have left the zamīndārs only partially employed, while in a season of scarcity we must still have relaxed the demand." This extract clearly sets forth the nature of the settlement. It was not intended to be an equal annual juma to be collected in all years, except what in other parts of India would be called famine years, but the assessment was pitched at the highest amount that Colonel



LAND REVENUE AND TENURES.

Dixon believed should be collected in good years, and he was prepared

to apply for remissions whenever they were required.

The people accepted the settlement with reluctance, but as proposed, it was sanctioned for 21 years. The Lieutenant-Governor, however, desired it to be understood "that except after report to Government and special sanction, no other penalty was to be attached to the non-fulfilment of the settlement contract than annulment of the lease and return to khām management." The settlement thus sanctioned was a mauzāwār settlement only in name, and the system of collection adopted by Colonel Dixon rendered it practically a ryotwāri one. Before the instalments were due the villages were divided into circles and a chap: asi was appointed for each circle. It was the duty of this official, in company with the patel and patwari, to collect from each individual tenant the sum recorded against his name in the patwari's register. If the cultivator himself could not pay, the bania with whom he kept his accounts was called up and the money generally produced. When the revenue could not be collected, Colonel Dixon made up his mind as to how much should be remitted about the month of May, and applied for sanction for the remission of the amount proposed. It was a matter of common tradition in the district that when the revenue of any village was found to come in with difficulty, the Deputy Collector was sent out and arranged for a re-distribution of the assessment. Such a mode of administration, though the best suited to the district and perfectly consonant with the wishes of the people, differs very considerably from the mauzāwār system, and could only succeed where the Collector was intimately acquainted with the resource of each village.

Having completed the settlement of Ajmer, Colonel Dixon took up the assessment of Merwāra. He was embarrassed with no instructions, as he was rightly considered the best judge of what should be done. He went into Merwāra in the cold weather of 1849-50 and reported his settlement of the district on the 27th September 1850. It was sanctioned for 20 years at a net demand of Rs. 1,81,751 and a gross demand of Rs. 1,88,742. The incidence of the assessment was Rs. 2-11-2 per acre on an area which included 38 per cent. of irrigations

For several years after the settlement there was a succession of favourable seasons, and remissions for which Colonel Dixon had to apply were but small in amount. Many tanks and wells were made by the people themselves, and the country was prosperous and contented. With Colonel Dixon's death, however, in 1857, the era of material improvement may be said to close, and the era of inflexible realization of revenue commenced. The principle of his settlement was forgotten, and the idea gradually gained ground that the assessment was an equal annual demand to be collected in full each year.

An account of the further progress of the settlement is given by Captain J. C. Brooke, the first Deputy Commissioner of Ajmer, in his report of the 24th July 1858. He found that there had been no banchh or distribution of deficiencies caused by defaulters over

the village community since the settlement. No account has been kept of the profits of common land, and any remissions received from the State were appropriated by the whole village, giving a very small modicum of relief to those really requiring it. The patwārīs were miserably paid, and generally acted as money-lenders to the people. Captain Brooke revised the patwārīs' establishment, and doubled up the smaller villages so as to enable a more fitting remuneration to be given to those who undertook the duties. He called attention to the manner in which land submerged in the beds of tanks had been assessed at high rates, and proposed to strike out of the settlement all lands liable to constant submersion, and to take revenue from them only when they should be cultivated. He was of opinion that the settlement had pressed heavily, and showed that the price of wheat and barley had fallen 50 per cent. below what they were for the three years preceding the settlement. Many of his suggestions were valuable, but nothing was done.

Major Lloyd, Deputy Commissioner in 1860, was struck by signs of growing prosperity, but it is significant that five villages had come under khām management in Ajmer and seven in Beāwar. Major Lloyd arranged for a systematic revision of the settlement records and a fresh distribution of the revenue. But the season of 1860 was a bad one, and remissions and suspensions were necessary in most estates. The work of re-distribution of the revenue was held in abeyance and never recommenced. Thereafter until 1867 the revenue was collected in full. In 1866 an important change was introduced into the system of collecting the revenue. The whole revenue was ordered to be collected from the headmen alone, and

the system initiated by Colonel Dixon was abolished.

In 1868-69 came the great famine, the most disastrous since the one of 1812. In 1869 the Deputy Commissioner reported that the state of apathy and demoralization of the people was such that nothing availed for the collection of revenue save active coercive measures. In Merwāra it was found utterly impossible to collect the revenue during the famine years, and eventually the arrears were remitted. A summary settlement was made for Merwāra from the year 1872-73, which was at a reduction of 32 per cent. on the settlement demand.

Mr. La Touche's Settlement. In 1871, as the existing settlements were nearing their term of expiry, Mr. J. D. LaTouche was appointed to make a new settlement of the districts. Operations began with a complete village survey of the three tahsīls of Ajmer, Beāwar and Todgarh, which was finally completed in 1873. Various improvements were introduced into the settlement registers, one of the most notable being that the fields were numbered in the khasra so as to show the various holdings as recorded in the khasra so as to show the various holdings as recorded in the khatūnī. The system of assessment also had distinctive features, as compared with those of previous settlements. Up to that time the assessments had never been founded on or checked by rates, but had been exclusively based on the history of past collection. Rates for the various kinds of land

had never been worked out from the total assessment on a tract, nor had the assessment on a village been decided by inductive process from the rates decided for lands. The assessment of each individual village had been a deductive guess on the part of the assessing officer.

The principle now to be followed was laid down in the instructions from Government. The Settlement Officer was first to divide the villages to be assessed into groups, so as to avoid applying a uniform rate to those of which the characteristics were markedly different. In every group he was then to select some specimen villages, in which the records of the Deputy Commissioner's Office and local enquiry would show him that the revenue had be nepaid with a fair amount of ease. From the statistics of these specimen villages he was then to work out fair rates for the different kinds of soil. These soil rates were then to be applied to the remaining villages, after carefully examining the accounts of past collections and remissions in the villages to see if the amount indicated by the soil rates could fairly be paid. In deciding thus, he was not to consider years of exceptional drought, extraordinary bad seasons being left to be dealt with by the application of extraordinary remedies. In order partly to surmount the difficulty of an equal annual demand being assessed in a tract where the seasons are so irregular, water revenue was assessed separately from the land revenue on the irrigated aspect. The assessment on the dry area included the full assessment on well land, but in each village where the tanks failed to fill, the water revenue was to be proportionately remitted each year.

Tanks were divided into classes according to their irrigating capacity, and a lump sum was fixed as the assessment of each tank. This was to be made good from the fields actually urigated in each year, unless its incidence on the irrigated area exceeded a certain fixed maximum or fell below a certain fixed minimum. When the incidence maximum per acre was exceeded, only the maximum was charged and the balance remitted; when the incidence per acre fell below the minimum, the minimum rate was charged and the excess over the total lump sum was credited to Government. A certain amount of stability was thus secured for the water revenue. Extended irrigation was also encouraged, as within the minimum the more the water was economized and spread, the less per acre each cultivator had to pay. The total revenue thus fixed in Ajmer-Merwara amounted to Rs. 55,432. Lands were divided into tālābi—irrigated from tanks and abi land in the dry beds of tanks. The maximum, minimum and average rates for tātābi land per acre at this settlement were Rs. 5-5, Rs. 1-9, and Rs. 3-8 respectively. For abi lands the figures were Rs. 1-14, Rs. 1-4, and Rs. 1-9.

Including the water rates the total net land revenue demand amounted to Rs. 2,61,557, of which Ajmer contributed Rs. 1,42,896 and Merwāra Rs. 1,18,661. Owing to a new arrangement for the collection of cesses, this net amount cannot be compared with the previous demand of Colonel Dixon. By the new system six per cent, was

deducted from the Government demand, 5 per cent. being allowed as the pay of lambardārs and 1 per cent. as the pay of zaildārs or circle headmen, the remainder constituting the net Government demand. To this was added 10 per cent, $3\frac{1}{8}$ per cent. belonging to the District Funds, and $6\frac{7}{8}$ per cent. belonging to the Patvārī Funds. The gross demand exclusive of this 10 per cent. addition may be compared with with Colonel Dixon's figures. Doing so, we find that in Ajmer the assessment was a reduction of 14 per cent. on Colonel Dixon's settlement, and in Merwāra of 25 per cent. For Ajmer-Merwāra the total demand of Colonel Dixon was Rs. 3,56,231, as compared to Rs. 2,86,548 under Mr. LaTouche's settlement. The total assessable area was 311,314 acres and the average holding 5·32 acres.

The principle of joint responsibility was not formally abolished, but one of the main objects of the settlement was to reduce its evils to a minimum. All well-known and recognized divisions of a village were allowed to choose a headman, and each cultivator was permitted the option of deciding through which headman he would pay his revenue. The total amount payable through each patel was added up, and a list of each headman's constituents given to the headman and filed with the settlement record. In this way the headmen become the strictly representative body that they ought to be.

The settlement was sanctioned for ten years and expired in 1884. The period, though marked by severe droughts in 1877 and 1878, was on the whole a series of average years, and under the moderate assessment of the settlement, the district made substantial progress. In 1877 the rainfall did not come up to 12 inches, and yet the revenue was paid without any difficulty. All but Rs. 5,857 were collected within the year, and Rs. 1,117 only remitted. Between 1880 and 1884 only Rs. 655 had to be remitted in Ajmer and Rs. 591 in Merwara. Combined with the progress and prosperity of the district, these figures give ample proof of the general success of the settlement.

That Government were of this opinion is evident from the instructions issued to Mr. Whiteway upon his undertaking the work of re-settling the districts in 1883. In view of the precarious condition of the climate they considered that it would be unwise and dangerous to venture upon any material enhancements of a permanent character. In the circumstances a revision of assessment might not have been necessary at all, had not Government been anxious to take the opportunity of placing the assessment of the province upon such a footing that any future revisions that might be required might be effected on the basis of existing records, upon known principles, and without any addition to the existing establishments of the districts. secure these objects thoroughly, correct maps and records were to be prepared, and a proper system of maintaining up to date such records established. It was further desired to introduce into the revenue system the principles of suspensions and remissions as approved by Government.

An account of the methods by which the maps were completed and the records framed will be found under the chapter on surveys.

Mr. Whiteway's settlement. Whether permanent correctness can be claimed for these maps may be doubted. No survey of unculturable ground and topographical features was attempted, and hillsides which were classed as unculturable may in course of time become cultivated by a system of terraces.

The chief innovation in the new settlement was the division of the districts into fluctuating and non-fluctuating areas. It was an extension of the principle already introduced by the previous settlement in the case of the water rate on tank irrigated areas, and its object was the same, to surmount the difficulty of assessing an equal annual demand upon tracts liable to the constant vicissitudes of indifferent seasons. The arrangement, as sanctioned, refers the revenue to a dry rate which can at a future time, should the rise in prices warrant the change, be raised; while, whenever a revision of the revenue is decided on, such revision will merely consist in raising the standard cultivated area, and consequently the standard revenue. On the basis of the assessment rates of the other classes of soil, which are multiples of the assessment dry rate, the areas irrigated from wells or tanks can be expressed in terms of the dry rate. That is to say, if the well rate be ten times the dry rate, then a well-irrigated acre is worth ten dry acres. The total cultivated area of a village, referred by these means to the dry rate, is called the dry unit area. The dry rate to which the revenue is referred is not fixed, but varies within certain limits, and the rate of the year is determined by the standard revenue divided by the dry unit area. When the rate exceeds the maximum, only the maximum is taken and the balance of the revenue is remitted, while when the rate falls below the minimum the minimum is taken and the balance credited to Government. The advantages of the system are that Government and the zamindar share equally in the prosperity of good years and losses of calamitous The fluctuating system was applied only to the villages considered most liable to scarcity. In a tract like Ajmer-Merwara such a distinction was difficult to make. According to the final result of the settlement there are no fluctuating villages in Merwara. In the Ajmer talist out of 142 villages, 61 were assessed as fluctuating. Of these 26 were situated in the Gangwana circle and 23 in the Rāmsar circle. The system required constant supervision on the part of superior officers, and to it was largely due the appointment of a Revenue Extra Assistant Commissioner sometime later.

In the non-fluctuating villages all increase of cultivation was assessed at the dry rates of the previous settlement, and no increase of irrigated area under wells was to be assessed at well rates. All increase of irrigation from Government tanks, or cultivation in the bed of such tanks, was assessed at tank and $\bar{a}bi$ rates respectively. But the rates paid for irrigation from such tanks and those paid for bed cultivation were revised and raised where necessary. The Settlement Officer also went into the question of tank improvement, and suggested rules for their better management.

The final result of the settlement showed a total assessment of Rs. 2,98,927, as compared with Rs. 2,78,281 of Mr. LaTouche's settle-

ment. The percentage of increase was 8.9 in Ajmer, 4.8 in Beāwar, and 6.9 in Todgarh, without considering the fact that areas in the bed of tanks amounting to 7,176 acres were excluded from the fixed assessed area, and made variable to pay a certain rate on the yearly cultivation. Out of the total assessment, Rs. 61,147 represented the

share from the variable villages in Ajmer.

The cultivated area showed a satisfactory advance upon the figures of the previous settlement. Land under well irrigation had increased by 6,304 acres, or 18.9 per cent. In dry cultivation the increase was 12,270 acres, or 11.9 per cent. The total increase of cultivation over the area assessed at Mr. LaTouche's assessment was 10.7 per cent. The number of proprietors had increased by 12 per cent. and that of cultivators decreased by 42 per cent. Taking only the cultivated and fallow land and omitting waste, the average holding was, in Ajmer 7.9 acres, in Beāwar 3.1 acres, and in Todgarh 1.6 acres.

Throughout the district the maximum assessment per acre on land irrigated from wells $(ch\bar{a}hi)$ is Rs. 8-2 and the minimum Re. 1-8. In tanks land $(t\bar{a}l\bar{a}bi)$ the maximum is Rs. 6 per acre and the minimum Re. 1. In tank bed land $(\bar{a}bi)$ the minimum is As. 8, but the maximum rises to Rs. 6-12 per acre. In dry crop land $(b\bar{a}r\bar{a}ni)$ the assessment varies from a maximum of Rs. 1-4 to a minimum of 3 annas 9 pies per acre. As a rule the rates are highest in the Ajmer and Todgarh $tahs\bar{\imath}ls$.

The settlement was sanctioned for 20 years, and is still in force, although with certain modifications in the case of the variably-assessed villages. In the opinion of the local authorities, this system has proved a failure in practice, in spite of its excellence in theory. It has been unpopular with the people, and Government has at various times consented to allow a fixed assessment to be substituted for the variable system in certain villages. The number of those variably

assessed is now only 37.

According to the Government order at the time of the 1874 settlement, extraordinary bad seasons were not to be considered in deciding the ordinary assessment; they were to be left to be dealt with by the application of extraordinary remedies, and it has only been by means of generous suspensions and remissions that this settlement has come successfully through the recent famines. In 1895 special rules were introduced for the suspensions and remissions of land revenue. They had previously been granted, but under no well-defined system. By the new rules such a system was initiated, and proposals to suspend or remit now follow promptly upon the occurrence of any local calamity, scarcity, or famine.

Between 1884 and 1890 only Rs. 785 were remitted in Ajmer and Rs. 3,718 in Merwāra. But the next decade tells a different story. During the 10 years in Ajmer Rs. 40,041 were remitted and the collection of Rs. 2,09,694 temporarily suspended. Of the latter amount Rs 46,045, Rs. 67,378 and Rs. 75,838 were suspended in the famine years of 1891-92, 1892-93 and 1899-1900 respectively.

Suspensions and Remissions of Revenue. In Merwara during the same period Rs. 6,769 were remitted, and the large amount of Rs. 4,29,701 was suspended. In 1891-92 Rs. 53,526, in 1892-93 Rs. 88,492 in 1893-94 Is. 61,881 in 1894-95 Rs. 36,993, in 1898-99 Rs. 37,389 and in 1899-1900 Rs. 1,37,319 remained uncollected at the end of each year respectively. At the end of 1902-03 the outstanding balances of revenue stood at Rs. 1,34,389 in Merwara and Rs. 89,219 in Ajmer, although remissions to the extent of Rs. 2,55,000 were granted over the two districts on 1st April 1902.

The figures quoted above bear eloquent testimony to the difficulty of assessing an annual demand from a tract like Ajmer-Merwāra to be recovered in good and bad years alike. A general recognition of the principle of suspensions and remissions in famine years, combined with a settlement based on the results of average harvests, is now agreed to be the best form of revenue administration for the

districts.

CHAPTER XV.

MISCELLANEOUS REVENUE.

Opium.

The Opium revenue is obtained from the duty on opium exported. Ajmer-Merwara is an opium-growing tract on a small scale, the cultivation being almost entirely restricted to the hilly tracts of Merwara. Ajmer is nominally a supply centre for the Bombay Presidency, via Indore, but no opium has been exported in that direction for some Large quantities are still exported to the Panjab. import and export of opium to and from Ajmer-Mewara is regulated under passes, import by rail being permitted only to prescribed railway stations, and export by rail being allowed from the Ajmer railway station only. The levy of an import duty and of a corresponding excise duty upon locally produced opium has recently been sanctioned with effect from the 1st April 1904 and 1st April 1905

During the 10 years ending in 1890, the average number of acres under opium cultivation in the khālsā area was 2,683. During the next decade the average fell to 1,351 acres. In 1902-03 only 852 acres were so cultivated, the decrease being partly due to more stringent measures for prevention of opium smuggling. During the same period the average numbers of chests exported were 181 and 463 respectively, while 466 were exported in 1902-03. The average Imperial opium receipts, viz., the duty on opium exported during the decade ending in 1890 came to 1:15 lakhs. In the next ten years they were 1:03 lakhs, and 1:31 lakhs in 1902-03. In 1903-04 the duty on opium

exported amounted to Rs. 1,01,220.

Salt.

The salt consumed in the province comes from the Government works at Sambhar and Pachbhadra in Rajputana, and pays revenue

Excise.

By rules introduced in 1901 the cultivation of poppy is permitted only under a license to be obtained from the Collector. The licensee may possess crude opium and poppy-heads produced from his land, and dispose of them wholesale to a farmer or licensed vendor or to a person authorized by order in writing of the Collector. The possession of opium, other than preparations used for smoking, in quantities exceeding 5 tolās, and of preparations used for smoking in quantities exceeding one tola, is prohibited throughout the area except to licensed The right of retail vend is farmed in the four urban areas of Ajmer, Beāwar, Kekri and Nasīrābād, and in the rural areas. In 1900-01 there were ten shops in the urban areas, and the vend fees amounted to Rs. 6,983. In 1903-04 there were 47 shops throughout all Ajmer-Merwara, and the receipts from farm and vend fees amounted to Rs. 16,079. The quantity of opium issued from the shops was 115

maunds 27 seers 2 chittäks, the incidence of taxation being Rs. 3.75 per seer. As already stated, an excise duty on locally-produced opium

will come into force on 1st April 1905.

The arrangements for the control of the spirits resembles the district monopoly system of Bombay. The privilege of manufacturing liquor is leased for a number of years to a contractor, who must have the liquor distilled at the central distillery near Ajmer city. He issues the liquor from the distillery on payment of still-head duty, and removes it to a main depôt, whence it is supplied to the various depôts and shops in the districts. The distillery premises and fittings are the property of the contractor for the time being, but a new contractor is bound to purchase them at a valuation, to be fixed by the local authorities. The distillation is carried on under the supervision of a Government excise inspector. The materials used for distillation are mahua, molasses and toddy. The liquor is either 15', 25°, or 50° under proof, the duty on which is Rs. 2-4, Rs. 2 and Rs. 1-4 per gallon respectively.

There is a minimum guarantee fixed If the receipts from still-head duty fall below it in any one year, the Abkari contractor has to

make up the deficiency.

The average annual receipts from the still-head duty during the ten years ending in 1890 were Rs. 93,190 and in the next decade Rs. 93,950.

In 1902-03 the receipts were Rs. 76,681.

The number and locality of shops for the retail sale of country liquor are fixed by the Collector, with the sanction of the Commissioner. There are now 145 in the province. The shop-keepers are appointed by the contractor, with the approval of the Collector, and the maximum prices of liquor are fixed by the latter.

The spirit distilled from mahua is by far the most popular; there is little demand for toddy. A preparation of mahua liquor mixed with sugar, aniseed, cardamom and orange, of the strength of 15° and 25° under-proof is sold in sealed bottles under the name of masala.

The 15 tāzīmi istimrārdārs in the Ajmer district are allowed by Government to maintain private stills for distillation of liquor from mahua or molasses, but solely for their own consumption. These stills are open to inspection by the superior officers of the Excise Preventive staff, and the liquor distilled is subject to limits fixed by the Collector.

In addition to the receipts from liquor, excise revenue is also derived from the vend of the right to sell by retail the intoxicating drugs—gānja, charas, bhāng and majhān. The cultivation of the hemp plant in Ajmer-Merwāra has been prohibited absolutely by rules introduced in 1899. Majhān, however, is manufactured locally. A duty of Rs. 4 per seer on gānja, Rs. 6 per seer on charas, and Rs. 5 per maund on bhāng is levied upon their import into the district. The import must come by rail through the Ajmer Railway Station, must be consigned direct to the Collector of Exise Revenue, and must be removed to a bonded warehouse in Ajmer, where it remains until the duty is paid and it is issued for consumption.

The average receipts from drugs during the ten years ending in 1890 were Rs. 4,904. In the next decade the average rose to Rs. 6,976. In 1903-04 the total receipts from duty and vend fees of drugs amounted to Rs. 11,022. There were 17 retail shops in the districts, and the incidence of hemp drugs revenue per head of the population came to 4! pies.

A preventive establishment is maintained at a monthly cost of Rs. 910, of which half is paid by Government and half by contributions from the liquor, opium and drugs' contractors. The staff tours in the districts on inspection duty during 3 weeks in every month.

Arrangements have been made with neighbouring Native States by which the latter refrain from placing their liquor shops within three

miles from the Ajmer-Merwara border.

The consumption of liquor has decreased considerably during the last 13 years. The liquor revenue which was Rs. 1,36,997 in 1891-92 had fallen to Rs. 76,681 in 1902-03. For this various causes may be assigned. The depletion of people's resources by famine has made them resort to the cheaper intoxicants, such as drugs, and the surplus available for luxuries has been considerably restricted. Certain classes are debarred from drinking by religious and moral principles, and among others a tendency is said to be growing to confine the consumption of liquor to the occasions of festivals. The excise measures of the Government have the same effect, and the facility and ease with which liquor could formerly be obtained no longer exist.

English education and the general spread of modern ideas is leading, especially in the towns, to an increased demand for imported and European spirits in preference to country liquors, so far as the richer classes are concerned. The duty paid on imported spirits rose from Rs. 2,168 in 1886-87 to Rs. 10,974 in 1896-97, but fell to Rs. 9,426 in 1902-03. In this year 2,355 gallons were imported as against 567

in 1886-87.

The system of stamp revenue is under similar rules to those prevailing in the rest of British India. Licenses are granted to vendors, who are allowed discount upon the sale of stamps, according to a fixed schedule. The Assistant Comissioners of Ajmer and Merwara are Collectors for the purposes of the rules.

Between 1880 and 1890 the average receipts were Rs. 1,13,543 for non-judicial stamps, and Rs. 86,171 were derived from judicial stamps. In the next decade the average receipts from the latter had risen to Rs. 89,798, while the former had fallen to Rs. 1,10,123. In 1902-03 receipts from judicial and non-judicial stamps were Rs. 86,209 and Rs. 45,129 respectively. The increase and decrease in the revenue from judicial stamps is due to causes affecting the popularity of litigation. In times of famine, civil suits diminish, as little can be recovered from a debtor upon relief works. On the other hand liabilities are contracted which when prosperous seasons return, result in increased litigation. Over an average of ten years, therefore, the figures are not much affected. Among causes affecting revenue from non-judicial stamps may be mentioned the growing popularity of the money order system and the

mps.

use of currency notes, leading to a decreased demand for foreign bills and hundi stamps, and the growing appreciation of the advantages of legal security for debts resulting in an increased sale of impressed sheets.

The Assistant Commissioners of Ajmer and Merwāra are the Collectors of Income-tax in their respective charges. An appeal to the Commissioner lies from their decisions.

The net revenue from income-tax from 1886-87 to 1889-90 amounted to Rs. 3,87,686, and in the next decade to Rs. 736,390. In the former period the incidence per head of the population averaged 3 annas $3\frac{1}{2}$ pies per annum, while the number of assessees per thousand averaged 6.5. In the latter period the average annual incidence per head of population came to 2 annas $2\frac{1}{5}$ pies, and the average number of assessees per thousand to 4.2. In 1902-03 the income-tax yielded Rs. 63,245, showing an incidence of 2 annas 1 pie per head of population. The number of assessees amounted to four per thousand.

Income-tax.

CHAPTER XVI.

LOCAL AND MUNICIPAL.

District Board. There is one District Board for both Ajmer and Merwāra, which came into existence on the 1st December 1888. The District Magistrate of Ajmer is chairman, and there are 40 members. Of these 9 are nominated by the Local Government, 6 are elected from Ajmer and 10 from Merwāra. The remaining 15 are composed of the $t\bar{a}z\bar{z}mi~istimr\bar{a}rd\bar{a}rs$ of Ajmer, who are "ex-officio" members. The electorate body is restricted by various qualifications of property

and position.

The principal functions of the Board are the upkeep of Local Fund roads, roadside trees and dak bungalows, and the general management of fairs and tolls throughout the district. It also assists to maintain out of its funds the district dispensaries and the village schools, and decides questions connected with them. In times of scarcity it has frequently started road works in order to relieve local distress. In 1895-96 the Sendra, Kotra, Bhīm-Tītrī, and Beāwar-Nayanagar roads were undertaken chiefly with this object, and in 1896-97 the Chachiāwās-Ararka road was improved for the same reason. But in times of real famine, these obligations are more restricted; regular relief works are started by Government, and it frequently happens that even Local Fund roads are repaired by famine labour paid from Imperial Funds. The Board holds a position of responsibility with reference to the well-being of the district, and upon occasion it has made free distributions of quinine throughout the villages during the prevalence of fevers.

During the ten years ending 1900 the average receipts amounted to Rs. 35,121 and the average expenditure to Rs. 36,541. The largest source of receipts was Provincial rates, which averaged Rs. 20,081. In the expenditure the heaviest items were education (Rs. 8,284), medical (Rs. 6,277), and public works (Rs. 13,667). This last item was exceptionally heavy owing to the number of works undertaken to relieve local scarcity. In 1902-03 the receipts rose to Rs. 76,622 and the expenditure to Rs. 41,188. Only Rs. 4,014 were spent on public works in 1900-01, as Government had undertaken relief operations on a large scale, and, as explained above, the usual repairs to many District Fund roads were carried out from Imperial Funds by famine labourers. Medical expenses were, however, heavy, amounting to Rs. 8,814 and were necessitated by the epidemic of fever which swept the country during the cold weather. In 1902-03 the charges under public works and medical were

Rs. 16,543 and Rs. 7,038 respectively.

There are three municipalities in the district, at Ajmer, Beāwar and Kekri. Beāwar was first established in 1867, sjmer followed in 1869 and Kekri in 1879. Until 1889 they were under the provisions of the North-West Provinces and Oudh Municipalities Act, but in that year it was repealed and replaced by Regulation V of 1886, which continues in force at present. Local rules applying to each municipality have been framed under the various sections of the Regulation.

Until 1884 the Ajmer municipal committee, consisting both of Europeans and natives, was entirely nominated by the district authorities. Its chairman was the District Magistrate. After 1884 the elective system was introduced, and in the year 1888 the municipality came under the provisions of Regulation V of 1886. Under the rules the Committee consists of 18 elected members, including a chairman and a number of members nominated by the Local Government who cannot exceed one-fourth of the total number of the Committee. They usually amount to five. For elective and executive purposes the municipality is divided into four wards, viz., the City, Kaisarganj, Suburban and Railway wards. These wards are entitled to return nine, two, three and three members respectively. The electorate body is restricted by residence, educational and property qualifications. There are no ex-officio members among them. As a rule the committee contains some 6 or 7 Europeans, including the nominated members.

The chief source of the municipal revenues is the octroi, the incidence of which, per head of the population of 73,839 persons, amounts to Rs. 1-12 per annum nearly. Its average for the ten years ending 1900 was Rs. 1,16,617. The average total income for the same period was Rs. 1,94,286. The year 1902-03 showed a decrease from this average, only Rs. 1,83,551 being received. The expenditure during the decade averaged Rs. 1,84,286, out of which conservancy claimed Rs. 32,203, and administration and collection of taxes Rs. 38,752. The expenditure on public works averaged Rs. 11,621. In 1902-03

municipal expenditure amounted to Rs. 1,56,913.

The efficiency of the working of the municipality is shown by the various improvements that have taken place since 1885. In 1886 a conservancy tramway were constructed at a cost of about Rs. 1,00,000, by which the sweepings and nightsoil are taken 3 miles away from the city to the trenches. An Assistant Health Officer has been appointed, the conservancy staff has been strengthened, and the number of public sanitary conveniences increased. The health of the town has further been ensured by the completion upon sanitary lines of the suburb of Kaisarganj, which has relieved the congestion in the city. The Rājputāna-Mālwā Railway has built good houses for its employees near the workshops and in the suburb known as Jones Ganj. New roads have been constructed giving easy access to the Railway Station from all parts of the city. In 1900 the Trevor Town Hall was built, and provides a large hall for public purposes as well as a municipal office. The municipal committee subscribed Rs. 19,000 towards the cost of its construction,

Municipalities.

Ajmer.

The water supply of the town has received attention. The Foy Sāgar scheme was completed in 1892. In 1886 the dhōbis' ghāts, bathing ghāts, and a cattle trough in the Bīsla tank were constructed at a cost of Rs. 40,000, and ensure a supply of clean water for washing clothes, bathing and watering cattle. The drinking supply has been further extended by sinking a large well in the Daulat Bāgh. The Ana Sāgar catchment area was increased in 1885-86 by the mak-

ing of the east feeder.

Other departments have also improved. Vaccination has been made compulsory, and a special staff is employed for the registration of vital statistics. A bonded warehouse has been constructed for storing dutiable articles which are intended re-export. Five new police outposts have been established and the force has been strengthened. Cattle pound and slaughter-house arrangements have been improved. Trees have been planted along the roads and in the public gardens. Owing to municipal supervision the class of hackney carriages available has risen considerably. Larger grants are now made for educational purposes. The municipal accounts are audited by the Examiner,

Public Works Accounts, Rājputāna and Central India.

The population within Beāwar municipal limits in 1901 was 21,928 persons. The town was first given a system of municipal government in 1867. Before 1881 the municipal committee consisted of 15 members, of whom 12 were elected and 3 were ex-officio members. After 1888 the committee was increased to 20 members, at which strength it now stands. Out of these 4 are "ex-officio" members, one is nominated by Government and the rest are elected. The Assistant Commissioner, Merwāra, is the chairman. Of the elected members there must be 9 Hindus, 4 Muhammadans and 2 Christians. Including the chairman there are generally two or three European members. The electorate is restricted by a tenancy or property qualification. Prior to 1888 elections were held triennially; thereafter till 1897 a third of the elected members went out of office annually; since 1897 elections are held triennially, when all elected and nominated members go out of office.

During the ten years ending in 1900 the total annual income averaged Rs. 49,525, of which octroi accounted for Rs. 39,184. The annual expenditure averaged Rs. 49,712, of which the largest item was Rs. 18,603 for charges on account of administration and the collection of taxes. In 1902-03 the receipts and expenditure were Rs. 57,016 and Rs. 60,196 respectively. Of the latter figures the chief items, besides administration and collection charges (Rs. 29,263), were public safety (Rs. 6,072), education (Rs. 5,387,) and conservancy (Rs. 7,360). In this year the incidence of octroi taxation per head of the popula-

tion was Rs. 2-7.

Since the changes of 1884-85 came into operation, considerable improvements have been effected in the working of the municipal system in Beāwar. They are to be found in all the departments. Vaccination has recently been made compulsory instead of optional, and the contributions paid to the medical institutions have increased

Beāwar.

steadily. The police force has risen from a strength of 36 to one of 48. Improved rules for the registration of vital statistics were introduced in 1894. Taxes are still collected by direct agency, but changes in detail have taken place leading to increased powers of check and efficiency, specially in the octroi department. The limit of refunds of octroi was raised from 4 annas in 1891 to Rupee 1 in 1896, and recently has been further raised to Rs. 2. Conservancy arrangements have been improved, iron carts have been substituted for those of wood, and the nightsoil sweepings are sold as manure. Wells have been deepened to secure a more permanent water supply, and the town has recently come through a period of prolonged drought without serious inconvenience or any epidemic arising. In 1900 it was decided to entertain the services of a paid European secretary, with qualifications as engineer and overseer, in order to secure efficient control over the various departments.

Tho population of Kekri municipality according to the 1901 census was 7,053. The only municipal taxation is the octroi. The average income from the tax during the ten years ending in 1900 has been Rs. 9,182, which gives an incidence of Rs. 1-4-8 per annum per head of the inhabitants. The average income from all sources during the ten years has been Rs. 11,112, and the average expenditure Rs. 10,690. Of the latter amount administration expenses and refunds account for Rs. 4,069, while expenditure on public works averaged Rs. 1,578. In 1902-03 the total income was Rs. 14,874 and expenditure Rs. 13,982. The incidence of octroi taxation per head of population was Rs. 1-13-5.

The Extra Assistant Commissioner in charge of Kekri is the chairman of the municipal committee, which consists of 8 members besides himself. The members are not elected, but are nominated by the Chief Commissioner on the recommendation of the chairman, through the Assistant Commissioner, Ajmer. They retire by rotation every three years, but the outgoing members are eligible for reappointment. The sanitary condition of the town and the water supply are fair, and no epidemic disease has so far occurred within its limits. The town owes its importance and the establishment of a municipality to the fact that at one time it bade fair to become a chief entrepôt for the cotton trade of Mewār. In this respect it is now eclipsed by Beāwar.

Kekri.

CHAPTER XVII.

PUBLIC WORKS.

Public Works Department.

Ajmer-Merwāra is, for purposes of Public Works, a Provincial division under an Executive Engineer, assisted by three sub-divisional officers. The sub-divisions are Ajmer, Nasīrābād and Merwāra. The two first are in charge of two upper subordinates, and the last is under the charge of a lower subordinate, who has his head-quarters at Beāwar. Five sub-overseers are attached to the division to assist the three sub-divisional officers. The Public Works Department looks after all the civil Government buildings, the roads and irrigation tanks in the Division and military buildings, except at Nasīrābād. District Fund and municipal suburban roads are also in its charge, the Executive Engineer being the professional adviser of the president of the District Board, and of the chairmen of the Ajmer, Beāwar and Kekri municipalities respectively.

Road and tank construction.

Between the date of the British occupation of the district and 1869 the attention of the Public Works was mainly confined to the During these years the Nasīrābād-Deoli road, the Grand Trunk road from the Jaipur border to Mārwār, the Ajmer-Nasīrābād and the Ajmer-Pushkar road were constructed. Before 1869 all the tanks built in Ajmer and Merwara were constructed by the Civil Department, and chiefly through the energy of Colonel Dixon. In this year an Irrigation division was added to the Public Works Department, and all tank works since constructed have been carried out by it. Among the more notable may be mentioned the Nadi Nala tank in 1872, Balād in 1873, Jāliā in 1875, Bīr in 1876, Dānta in 1877. Makrera in 1879, Lādpura in 1881, and Kāir tank in 1892-93. During the famine years 1898-00 the department carried out the doubling of the railway embankment line between Tilaurnia and Madarpura and between Ajmer and Kharwa. It also constructed the earthworks of the projected lines between Nasīrābād and Kekri. Kekri and Sāwar and part of the embankment for the Bārān-Mārwār

The department is also responsible for the construction of the fine public buildings erected in Ajmer during recent years. The Ajmer Government College was built in 1869-70, and the Ajmer District Courts between 1873 and 1876. The Mayo College was constructed in 1878-1885, the Ajmer Court of Wards Office in 1890-91, the Victoria Jubilee Clock Tower in 1891-92, the Ajmer General Hospital in 1894-95, and Trevor Town Hall in 1899-1900.

Water schemes.

The only large municipal water scheme completed by the department is that which supplies Ajmer with water from the Foy Sagar reservoir, situated 3 miles to the south-west of the town. The

reservoir was constructed from municipal funds in 1892 by throwing a dam across the Bāndi river. The tank when full is 30 feet deep, and has a cubic capacity of 150 million cubic neet, sufficient to supply all the requirements of Ajmer city, civil station and railway for about two years. The water flows by gravitation through a 12-inch iron pipe, and commands the general level of the town. If, however, the depth of the water in the reservoir falls below 6 feet, the height of the outlet bed, it has to be raised into the pipe by pumping operations. It is sufficiently pure for most purposes, and undergoes scarcely any filtration. During the past decade the severe droughts have seriously affected the Foy Sāgar, and it has twice been found necessary to bring water from the Budha l'ushkar lake, 5 miles to the northwest of Ajmer. The water there is of a very pure quality, and is never known to fail, but as a high barrier exists between it and Ajmer, it can only be obtained by costly pumping. For this reason the line of iron piping between this lake and the town is only used in case of any temporary failure of the Foy Sāgar supply.

In the case of famine the provision of a programme of works, and supervision of them when started, are duties of the Public Works

Department.

CHAPTER XVIII.

ARMY.

Nasīrābād.

There are three military stations in the district—Nasīrābād, Deoli

and Ajmer, the two latter being garrisoned by local corps.

The cantonment of Nasīrābād is situated on a bleak, bare plain, which slopes eastward from the farthest range of the Arāvalli Hills in this direction. The drainage is good, but there is a great lack of sweet water. All the wells in the cantonment are brackish and many are quite bitter. Water for the troops is carried a distance of about three miles. There is also a pipe, by which water is brought

from the wells at Danta some four miles away.

The lines of Nasīrābād were laid out in 1818 by Sir David Ochterlony, who early in the year had marched into Rājputāna with a force of eight regiments of infantry, one of cavalry and a proportionate amount of artillery, with a view of effecting the dispossession of Amīr Khān's forces, and confirming the newly-formed and renewed treaties of alliance and protection with the States of Rajputana. Two accounts are given of the origin of the name. According to one it was after a fakīr, Nasīr Shāh, whom the General found living in the place. According to the other the name is derived from the title of Nasīrud-daula, which Shah Alam conferred on Sir David Ochterlony for his defence of Delhi against Holkar in 1804. The cantonment is laid out in a continuous stretch of over a mile in length, the lines of the troops being to the windward of the officers' bungalows, to the leeward of which is a large irregularly-built open town with about 20,000 inhabitants. The garrison consists of a battery of Royal Field Artillery, 6 companies of British infantry, a regiment of Bombay infantry and a squadron of Bombay cavalry from the regiment at Nimach. It is directly under a Colonel on the Staff, but forms part of the Mhow division of the Western Army Corps.

As a military station Nasīrābād is important in being most centrally situated for operations in Rājputāna. It is the nearest considerable military station to Jaipur and Jodhpur, and well placed for the rapid despatch of troops in the direction of Udaipur, Bikaner

or Indore.

The cantonment is administered by a cantonment committee, under the Cantonment Code of 1899, and the Cantonment Magistrate exercises civil and criminal jurisdiction within its limits. Nasīrābād possesses a chaplain of the Church of England appointed by the the Bishop of Bombay, and a Roman Catholic chaplain. The former is supposed to minister to the spiritual wants of the European

inhabitants of Tāragarh, Beāwar and Deoli also. The Cantonment Magistrate is the Registrar of Birtha and De the under the Commissioner, Ajmer-Merwāra, as Registrar-General. The Administrator-General of Bengal takes charge of the estates of persons dying intestate.

The cantonment of Deoli is about 70 miles from Ajmer, in the midst of native territory, but the cantonment itself is considered part of the Ajmer district. It is garrisoned by a local crops called the 42nd Deoli Regiment, formerly called the Deoli Irregular Force. After the Mutiny a regiment of Bengal cavalry was also stationed at Deoli, but it was removed at the time of the last Afghān war.

The 42nd Deoli Regiment consists of a squadron of cavalry and and a battalion of infantry, with a total of 7 British officers and 812 native rank and file. The infantry is recruited from the Mīnās, a predatory tribe who have been enlisted with a view to weaning them from unlawful pursuits; the sawārs are principally Sikhs. The commandant of the force is also Cantonment Magistrate, and disposes

of the few magisterial cases which arise from time to time.

The 44th Merwāra Infantry, formerly known as the Merwāra Battalion, whose head-quarters were removed from Beawar to Ajmer in 1871, deserves a more extended notice, as it was largely instrumental in the pacification and civilization of Merwara; and the Resolution of the Governor-General in Council, dated 20th June 1822, which directed the formation of a local corps in Merwara, yields to none in the importance among the measures adopted to reclaim the Mers from their predatory habits. The nucleus of the regiment then raised was composed of drafts from the Rampura local battalion, which in its turn had been formed from the remnants of the army of the notorious Amīr Khān. The total strength of the new battalion was fixed at 680 of all ranks, divided into 8 companies. Vacancies for 340 Mers as sepoys were reserved, and a certain proportion of the commissioned and non-commissioned posts were set apart for those Mers who should qualify themselves to hold them. The corps was cantoned near the old town of Beawar, about 30 miles south-west of Ajmer, then in the midst of a waste and uncultivated tract of country. At first there was considerable difficulty in obtaining recruits, but 100 Mers of ages from 50 to 14 years were induced to enlist by a largess of five rupees and the favorable influence of a general feast. Not only was it difficult to enlist men, but it was still more difficult to retain them after they had enlisted. Many returned to their villages, being unable to brook the restraints of military service. The regiment, however, soon found no difficulty in attracting men to its standard; some of the most smart and deserving recruits were rapidly promoted; the first feeling of mistrust soon gave way to one of attachment to the service, and while the battalion gained in popularity it also gained a creditable standard of efficiency from a military point of view.

During the early years of the existence of the battalion many Mer sepoys used to take their discharge on the completion of three years service, by which time they had generally managed to save sufficient Deoli.

Ajmer. 44th Merwāra Infantry.

They then returned to their money to purchase a pair of bullocks. villages and took to agriculture. In this way the number of those who in the new regiment had learned what duty was, and who had acquired habits of discipline, obedience, cleanliness, and good faith, was sufficiently great to influence the inhabitants of Merwara in the direction of industry and order. In 1835 a system of agricultural advances was established, and from that date discharges, though still numerous, were much less frequent. In 1823 the cantonments were moved 4 miles south, adjacent to what was subsequently the site of the town of Nayanagar. In 1825 the battalion was augmented by the addition of ten men per company, thus raising its strength to 760 of all ranks. The immediate cause of the augmentation was severe detachment duty on the outposts in the Merwara hills. This did not, however, prevent two companies being detached to Ajmer in 1832—one as the escort of the Agent Governor-General, the other as a city guard. In 1838 this quota was reduced by half on account

of the excessive strain on the corps.

It was not till the year 1839 that the battalion saw any active service, but in that year it was found necessary to despatch a force composed of the Merwara Battalion and the Jodhpur Legion against several outlawed thakurs of Marwar, who, under the leadership of one Chiman Singh Champawat, had for several years devoted themselves to pillage and highway robbery, and whom the Mahārāja of Jodhpur was unable to subduc. The outlaws had established their head-quarters in the wild country near the town of Kot in Merwāra, at the entrance of the Dewair pass. The two regiments, under the command of Captain Dixon, moved on the enemy from different directions, and after a sharp struggle succeeded in completely dislodging the outlaws and breaking up the band, many of whom with their leader, Chiman Singh, were killed in the action. The loss of the regiment was only 8 men killed and wounded, and the thanks of the Governor-General were accorded to Captain Dixon, while the conduct of the battalion met with high commendation. In the autumn of the same year the services of the regiment were again put into requisition for the expedition against Jodhpur, but as Mahārāja Mān Singh submitted to all demands, no hostilities occurred, and the force was marched back to its quarters at Beāwar. With this event ends all that need be said of the Merwara Battalion till the Mutiny of 1857.

The troops at Nasīrābād mutinied on the 28th May 1857. Early notice having been conveyed to Colonel Dixon, commanding the battalion at Beāwar, he at once ordered a company to move on Ajmer. By a forced march of 33 miles during the night, Lieut. W. Carnell, commanding the detachment, was enabled to occupy the magazine at Ajmer before information of the occurrences at Nasīrābād had reached the company of the 15th Native Infantry then garrisoning the magazine. It consequently permitted itself to be relieved and marched to Nasīrābād, and by this prompt measure the safety of Ajmer was assured. The detachment was subsequently strengthened by further re-inforcements from Beāwar. During the course of the

mutiny, a detachment of the battalion was employed with the Rāj-putna field force under Major-General Sir G. St. Patrick Lawrence, and moved against the mutineers of the Jodhpur Legion, who had established themselves in the walled town of Awāh in Mārwār. For its services and for the unshaken fidelity and loyalty displayed by the corps, all men serving with the battalion on 1st July 1857, were rewarded with the grant of the same pay and privileges for pension as soldiers of the line.

In December 1857 the Government of India authorized the formation of a second Mer regiment to be stationed at Ajmer. Merwara Battalion was reduced by two companies, which were drafted into the new regiment. The strength of the united corps was 1,500 men, but the new battalion enjoyed only a short existence. In 1861 it was reduced and amalgamated with the old Merwarz Battalion, which was raised to a strength of 1,000 of all ranks, the new battalion being called the Merwara Police Battalion, and put under the control of the Police Department of the North-West Provinces. By this measure the battalion, with the exception of the men on whom special privileges had been conferred as a reward for loyalty during the mutiny, was deprived of the advantages in respect of pay and pension, which were afterwards conferred on the local military corps of Rajputana. The men were consequently discontented, while the regiment was practically useless for police purposes. These among other cogent reasons induced Lord Mayo in 1870 to re-organize the battalion into a purely military corps. The numbers were reduced to 712 of native ranks divided into 8 companies. The pay of the men was raised from Rs. 5-8 to Rs. 7 a month, and they were granted the same privileges as regard pension and allowances as the other local infantry corps in Rajputana. At the same time the head-quarters were transferred from Beawar to Ajmer, where they are at present.

In 1878 the regiment took part in the Afghān campaign, and in 1901 were mobilized for service in Jubaland, but the expedition terminated without the necessity of sending re-inforcements. In 1897 the battalion was placed under the orders of the Commander-in-Chief in India. Its present strength consists of 4 British officers, and 712 native rank and file. The Civil Surgeon, Ajmer, is in medical charge of the regiment. Although during its earlier history many outsiders were found in the ranks, it is now recruited entirely from Mers and

Kathat Merats.

The regiment, however, has ceased to be what it was in former days, a school through which the greater part of the youth of the country passed; and more especially since the removal of the head-quarters to Ajmer, its influence on what may be called the home aspects of the corps has been much diminished. While the battalion was at Beāwar, the soldiers, who enlisted for the most part from the villages immediately adjacent, were allowed to go to their homes after parade in the morning, they worked all day in their fields, and were back to cantonments by night. Leave was often applied for by those whose homes were at a greater distance, and freely granted. The men

therefore continued practically to form a part of the agricultural population: they met their relations frequently, and their pay went often to the common stock, whereas soldiering has now become a profession. Men who enlist do so for their lifetime, and only take their discharge when invalided or entitled to their full pension. After their term of service is over, they invariably settle down on their ancestral land, and have probably saved enough to dig a well for its improvement. Here they spend the remainder of their days, and have generally considerable influence in the villages, especially those who have attained to the rank of subahdār or jamādār in the battalion.

Volunteers.

Ajmer is also the head-quarters of the 2nd Battalion, Bombay, Baroda and Central India Railway Volunteer Rifles. The corps originally formed part of the Agra Volunteer Rifle Corps, with the title of Rājputāna-Mālwa Volunteer Rifle Corps. In 1887 its title was changed to the present designation. It consists of 11 companies, including a cadet company at Mount Abu. Its strength in June 1903 stood at 344. The grand total of troops of all arms within the province on 1st June 1903 was 2,515, of which 789 were British and 1,726 Native.

CHAPTER XIX.

POLICE AND JAILS.

Before 1861 Ajmer-Merwara had no regular police. The general Early Police. peace of the district was maintained by the local military force, known as the Merwara Battalion, whose head-quarters were at Beawar: the village watchmen and the pecuniary responsibility of istimrārdārs, bhumias, and jāgīrdārs assisted to prevent crime in local areas. About Rs. 35,000 were spent annually upon the upkeep of the chaukidars in

the villages and fowns.

Owing to the loyal spirit shown by the Merwara Battalion in the mutiny, a second Mer regiment was raised in 1857, with head-quarters at Ajmer. Financial reasons, however, led to its reduction in 1861, or rather to its amalgamation with the old Merwara Battalion, the strength of which was raised to 1,000 of all ranks, the designation of the latter being changed to Merwara Police Battalion, the corps being removed from the military establishment and placed under the orders of the Inspector-General of Police, North-West Provinces. Out of the savings resulting from the abolition of the Mer regiment, an organized constabulary consisting of 548 men, under a District Superintendent of Police, was established from the 1st January 1862. From the same date the provisions of the Police Act (V of 1861) were extended to the districts.

The arrangement by which the Merwāra Battalion was classed as police was soon found to be unsatisfactory. It was extremely unpopular with the men, while for regular police purposes the regiment was practically useless. So in 1870 it was restored to its purely

military character.

In 1871 when Ajmer-Merwara was taken under the direct management of the Government of India, the local police force was and strength. transferred from the control of the Inspector-General of Police, North-West Provinces, to that of the Commissioner, Ajmer-Merwara. Since then the District Superintendent of Police has acted under his orders. Between 1862 and 1882 successive schemes of reorganization caused fluctuations in the numbers of the police force, but since the latter date there has been little change. In 1902 the strength was 704 of all grades, which gives a policeman to every 3.8 square miles, and to every 677.4 of the population of the district. The supervising staff consists of a District Superintendent and 3 Inspectors. There are 13 sub-inspectors, 93 head constables, 37 mounted constables and 556 foot constables. The force is distributed among 18 police stations and 38 outposts throughout the districts. Ajmer has 7 first class and 6 second class stations. In Merwara there are 3 first class and 2 of the

Organization

second class. The cost of maintenance has risen from Rs. 86,423 in 1881 to Rs. 1,14,689 in 1902. Of the latter amount Rs. 27,128 is

paid from sources other than Imperial.

The recruiting for the force is done locally, but men come in for service from the Panjāb, the United Provinces of Agra and Oudh, and the surrounding Native States. As a rule there is no difficulty in obtaining recruits. The men are trained at the Ajmer head-quarters before being drafted to other stations and outposts. The general attitude of educated natives towards the police is satisfactory, and men of good family and educational attainments are willing to take service in the force.

Rural Police.

As a connecting link between the villagers and the regular police, both for the detection of crime and supervision of bad characters, a good chaukidāri or village police is most valuable. This has always been recognized in Ajmer-Merwāra, and in 1871 the numbers of the rural police stood at 398. About that time the minimum pay was raised from Rs. 3 to Rs. 4 per month. In 1902 the rural police force in khālsa and jāgīr villages numbered 205 and in the istimrāri areas 191. The cost of the former was Rs. 11,044 and of the latter Rs. 9,564. Besides the chaukidārs there are in many villages menial classes, who for a small annual contribution of corn from the villagers perform in a perfunctory way some of a watchman's duties.

The railway police on the Rajputana-Malwa Railway belong to the Bombay establishment, and are under the orders of the Inspector-

General of Police of that province.

Cognizable Cases. During the average of five years ending in 1901 the number of cognizable cases reported was 4,699. Of these 3,445 were decided in the criminal courts, 237 cases ending in acquittal and 3,208 in convictions. The period includes the famine of 1898-1900, when the crime incidence was above the normal. The averages show one crime per 57 square miles of area and 101 of population. Detection is fairly successful, in spite of the facilities for criminals of escaping and hiding in the surrounding Native States. Finger impressions have proved useful in tracing previously-convicted offenders.

There is only one jail in the districts—the Ajmer central jail. The average number of prisoners daily was 540 in 1902, as compared with 407 in 1891 and 429 in 1881. The famine of 1898-1900 and the conditions in Merwāra in 1901 resulted in a criminality which

raised the jail population to the highest point yet reached.

Although the jail is built on one of the most healthy sites in Ajmer, it did not escape the epidemics of fever and pneumonia that swept the country in 1891 and 1902. In these years the death-rate was 27 per mille and 29.6 per mille respectively. In 1881 under normal conditions it was only 4.66 per mille. Carpets and rugs of excellent quality and good cotton durris are made to order in the jail. A coarse cotton cloth is also manufactured and dyed, which finds a good market locally for the clothing of the poorer classes. The profits in these manufactures have risen steadily from Rs. 2,883 in 1881 to Rs. 3,472 in 1891 and to Rs. 3,881 in 1902.

Jails.

The expenditure on jail maintenance was Rs. 18,769 in 1881, Rs. 26,686 in 1891 and Rs. 25,385 in 190? The cost per prisoner in each of these years works out at Rs. 43-15-9, Rs. 65-8 and

Rs. 46-15-4 respectively.

In addition to the central jail there are three lock-ups at Ajmer, Nasīrābād and Beāwar for prisoners under trial in the courts at these places. One at Kekri is also under contemplation for the same purpose. In the event of courts being held in other places the prisoners are kept in the ordinary lock-up- attached to police stations.

CHAPTER XX.

EDUCATION.

Education in former times.

In the early days of the British occupation of Ajmer, with the exception of a monthly subsidy of Rs. 300 to an English missionary who had established a school in the city, little attempt was made

by Government to provide for the education of the people.

Instruction was confined to the indigenous schools, which in the year 1845-46 numbered 56, of which 42 with a roll of 807 pupils were Hindi and Sanskrit schools, and 14 with 266 pupils Persian and Arabic schools. The cities of Ajmer and Shahpura, capital of the present Shahpura chiefship, had 13 Persian and 20 Hindi schools, and the rest were situated in the villages. It was noted as significant of the aversion of Rajputs to intellectual improvement, that very few of that caste were to be found in the Hindi schools and not one in the Persian schools. In the year 1836 a Government school was established in Ajmer, with a European head master and two native teachers for Hindi and one for Urdu. At the end of 1837 the number of pupils stood at 219, and for some years the school was fairly prosperous. But afterwards it declined both in numbers and efficiency, and was finally abolished in 1843. The next decade showed a desire for improvment on the part of the people, and Colonel Dixon points out that not only had the vernacular schools increased in Ajmer but one for teaching English had been started by private effort. The time appeared favourable, and Government decided to open a school in 1851, with an idea that it might ultimately become a college, if funds permitted. A Superintendent was appointed, with one English and nine Native assistants, and in the year 1853 there were 230 students, of which 44 were Muhammadans and 186 Hindus. In 1861 the school was affiliated to the Calcutta University, and in 1868 was raised to the position of a college, but with a staff of teachers limited to the requirements of the First Arts examination of the Calcutta University.

Ajmer Government College. The College at Ajmer is a commodious building, situated about a mile from the city. It teaches up to the B. A. standard, and in the same building the higher classes of a High School. The staff consists of a European Principal, a Vice-Principal, three professors and thirteen assistant professors and teachers. Attached to the College is a lower school, the staff of which consists of 9 English and 14 vernacular teachers. Also in connection with the College there is a boarding house for the accommodation of boys from the village schools who have obtained scholarships, and 54 boys resided here on the 31st March 1903. Provision is being made for the

accommodation of 20 more.

127

The number of students in 1891 was 411, and 266 in 1903. The efficiency has steadily in reased; the University results in 1881 were 4 Matriculation and 2 Intermediate passes in 1891 there were 15 Matriculation passes and 1 Intermediate. In 1903, 23 students passed the Matriculation examination and 10 the Intermediate, and 8 obtained the B.A. degree.

The cost of the College in 1902-03 was Rs. 32,119, of which Provincial revenues paid Rs. 23 539, District and municipal funds Rs. 2,580, while the balance come from fees and other sources.

Connected with the Government College at Ajmer through a system of inspection, are the secondary schools, aided and unaided, and the primary schools of Ajmer-Merwara. The inspection of those schools has long been a duty attached to the office of the Principal of the College, who is assisted in it by two Deputy Inspectors. The public secondary institutions in Ajmer-Merwara numbered Of these 5 are high schools 14 in 1903, with a total of 2,465 pupils. with 1,567 pupils, and 9 are middle schools. There were also 19 advanced private schools with 450 publis. The public institution figures showed a satisfactory advance upon those of 1891, which were 11 schools (3 high schools and 8 middle schools) with 1,837 pupils, but the famines had reduced the number of higher private schools, which

in 1891 stood at 33 with 1,168 pupils.

Primary education before 1850 was left entirely in the hands of the indigenous schools supported by the people, and without interference from Government. But shortly after Colonel Dixon's assessment in that year, 75 schools were established in Ajmer-Merwara, and the people were induced to defray a large portion of their cost by means of a cess. The number was subsequently reduced to 57, and the contributions were continued as long as Colonel Dixon lived. An in-pector for village schools was appointed for the Ajmer district in 1851, and one for Merwara in 1852. After Colonel Dixon's death, however, the clamours of the people against the cess became so violent, that Government authorized the cessation of the contribution, and all schools except those supported by Government were closed. The intensity of the unpopularity may be gathered from the fact that, when the sister-in-law of the Bhinai Rājā performed sati in 1857, the last request of Brahmans who surrounded the pyre was that she would use her influence for the abolition of the cess for village schools. The teachers in the indigenous schools were as a class badly paid and incompetent, and the Government inspector writing in 1858 gave it as his opinion that, as long as they continued to be so, "popular education through the indigenous schools existing in this province is a hopeless sham and a delusion." An earlier report had noted the small amount of knowledge acquired in spite of the great length of time during which the boys prosecuted their studies—"when they leave school after having spent some 10 or 12 years in the Persian, 12 or 13 years in the Arabic schools, they possess little beyond a mechanical knowledge of the Koran and an equally mechanical knowledge of office style."

Secondary Schools.

> Primary Schools.

In 1871 upon the transfer of the province to the direct control of the Government of India, the educational department was also severed from that of the North-West Provinces and was placed under the Commissioner, Ajmer-Merwara, as Director of Public Instruction. In 1891 there were 47 upper primary schools, with a total attendance of 3,082 pupils. Besides these public institutions 2,777 children were being educated in 83 elementary private schools. The famines of the next decade caused a distinct retrogression in primary education. But it was made up in 1903, when, though the number of private elementary schools had fallen to 71, the number of pupils had increased by 848. The public primary schools had risen to 50, but the number of pupils did not keep pace and had sunk to 2,843. Both years, however, show an improvement compared with 1881, in which year there were 67 public and 60 private primary schools, with a total attendance between them of 4,785 pupils. The proportion of boys under education to those of a school-going age was 12.8 per cent. in 1881, 13.5 per cent. in 1891, and 12.5 per cent. in 1903. The public primary schools are managed by the educational department, under the Commissioner as Director of Public Instruction. The department receives and disburses not only Government funds in the case of schools that are maintained entirely by Government, but also District Funds and municipal contributions towards the expenses of these schools. The department also receives the school fees and spends them. The pay of the teachers varies from Rs. 100 per month paid to the head-master of the Government Branch School at Ajmer to Rs. 6, the salary of the lowest grade masters in the department. Out of the 50 primary public schools, 7 are girls' schools and 42 are village schools (halkābandi). In 1903 the total cost of the primary public schools was Rs 17,722, of which Imperial revenues paid Rs. 6,105, cesses and municipal funds Rs. 7,351; Rs. 3,232 were derived from fees and Rs. 1,034 from other sources.

Normal and Industrial Schools. A training school for male teachers in the primary and secondary schools in the province was started in Ajmer in 1864. In 1867 a similar institution was begun for the training of female teachers. In 1890-91 there were 20 males and 4 females under instruction. The female normal school was found not to work well and was abolished in 1893. There were 9 pupils at the male normal school in 1902-03.

The United Free Church of Scotland mission at Beāwar maintains a normal school for training the teachers for its village schools. The same mission supports the only industrial school in the districts at its Ashāpura orphanage. Eight workshops are now established there, and the boys are taught carpentry, smiths' work, pottery, tailoring, masonry, shoemaking, weaving and gardening. In 1901 there was an average daily attendance of 481.

Female education.

As was to be expected among the conservative and backward population of Ajmer-Merwāra, female education has progressed but slowly. Even now it is confined to the public primary, and elementary private schools. Of the former there are, as already mentioned, 7

schools for girls only. In the ordinary village schools girls, when they attend, are educated along with the boys and in the same subjects. In the special girls' schools, besides reading, writing and arithmetic, they

are taught knitting and sewing.

Taking private and public institutions together, we find that in 1890-91 there were 567 girls being educated in 19 schools. Their percentage to the female population of a school-going age was 1.5. Similarly in 1903 the total number of female schools and scholars was 30 and 1,840 respectively, giving a percentage to the female population of a school-going age of 5.4. This progress shown in a decade of famine is satisfactory, and indicates that prejudices against female education are gradually disappearing. The tendency is most marked among the Brāhman and Mahājan communities. The Muhammadans with their traditional pardāh system, and the Rājputs with their invincible conservatism lag far behind.

In the year 1881 there was only one school in the province for European children—the Railway school at Ajmer. In that year the number of pupils was 29, and in 1891 it had risen to 94. In 1896-97, however, a school for European boys and girls was started by the Roman Catholic Convent at Ajmer. This at once attracted all the children of Roman Catholic parentage, and the numbers at the Railway school decreased accordingly. In 1903 they stood at 57, as against 88 pupils attending the Convent school. Both are classed as secondary schools and receive grants, the former of Rs. 75

and the latter of Rs. 100 per month from Government.

As the Hindu population is considerably in excess of the Muhammadan, it is only to be expected that their numbers in the various schools should also be greater. If, however, percentages of the schoolgoing population of either class be taken, the Muhammadans have, if anything, the advantage so far as male education is concerned. In 1891 there were 1,757 male and 2 female Muhammadans under instruction, as against 6,331 male and 415 female Hindus, but the percentages of Muhammadan males and females to their populations of a schoolgoing age respectively were 28.4 and .04, against 18.4 and 1.3 of the Hindus. Of Muhammadans attending the College the percentage was less satisfactory, being '7 as against 1'3 for the Hindus. In 1903 both in the College and in the schools, percentages of Muhammadan and Hindu males under instruction to their populations of school-going age amounted to 17.8 and 19.0 in both cases respectively. The number of Muhammadans in the College was 31, and in other public and private schools 1,015. Hindus, however, had the advantage in female education with 802 girls, representing 2.9 per cent, while the Muhammadans had only 67 or 1:3 per cent. The general conclusion from these figures appears to be that so far as the boys are concerned the common reproach of backward education among Muhammadans cannot fairly be applied to those of Ajmer-Merwara. Many of them are in the police, army or other branches of the public service, where the benefits of educating their children are brought prominently before them.

The direct cost of the Educational Department in the province in

Schools for European children.

Hindu and Muhammadan education.

Finances,

1903 amounted to Rs. 78,218. Of this Rs. 37,060 were paid from Imperial revenues, Rs. 18,155 were contributed from District and municipal funds, Rs. 12,961 were derived from fees, and Rs. 10,042 from other miscellaneous sources, including endowments and subscriptions. In the same year the average cost per pupil in the College came to Rs. 133-1-3, in training and special schools to Rs. 118-9-9, in secondary schools to Rs. 12-13-2 and in primary schools to Rs. 6-8-3. The census returns of 1901 showed that out of the total male population only 12 per cent. and of the total female

population only 8 per cent, were educated.

Mayo College.

Quite apart from the general education of the province there is the Mayo College at Ajmer. In the latter part of the year 1870 the late Earl of Mayo held a Darbar at Ajmer, and proposed to the assembled chiefs of Rajasthan that a College should be established at Ajmer, where their sons and nobles might receive such an education as would fit them for their high position and important duties. He invited subscriptions from the chiefs, promising on behalf of the Government of India a sum equal to the aggregate amount collected. Fifteen of the eighteen principalities in Rajputana responded by promising subscriptions amounting to over 6 lakhs, which was later increased to nearly 7 lakhs, the interest on which sum added to a subsidy from the Government of India forms the income of the College. Of the three States Dholpur, Jaisalmer, and Dungarpur, which did not subscribe originally, the two last have since contributed to the endowment. The States of Jaipur, Udaipur, Jödhpur, Kötäh, Bharatpur, Bikaner, Jhālāwār, Alwar and Tonk have also built boarding houses in the College park at a cost of Rs. 4,28,000, and maintain them at an annual cost of approximately Rs. 18,600, including the salaries of house motomids and servants. The most liberal donor was Jaipur, whose total contributions exceed 2 lakhs, while those of Jodhpur, Udaipur, Kötáh and Jhalawar exceed one lakh cach. The British Government on its part presented the College park, comprising 167 acres, formerly the site of the old Residency, built the main building, the residences of the Principal and Vice-Principal, and the Ajmer boarding house, which is occupied by boys from the Ajmer district and also by boys from elsewhere who have not been provided with accommodation by their own States - It also provides for the salaries of the English staff and the upkeep of the main roads and the four Government buildings.

The main building, which costs approximately Rs. 4,01,400, is built of white marble in the Indo-Saracenic style, after designs prepared by Major Mant, R.E. The foundation-stone was laid on the 5th January 1878 by Mr. (now Sir) Alfred Lyall, then Agent to the Governor-General for Rājputāna, and the building was opened by H. E. the Earl of Dufferin on the 7th November 1885. In front stands a statue of the founder, Lord Mayo, the work of Mr. Noble, and crected from funds subscribed by British and Native residents of Rājputāna. The ten boarding houses, of which 9 are Hindu and one Muhammadan, are arranged in the form of a horse shoe, with the

College in the centre of the base. The Jaipur house alone stands at

some distance apart to the south of the main building.

The first Principal to be appointed was the late Colonel Sir Oliver St. John, at the close of 1874. Major (now Colonel) Powlett, officiated as Principal for two months in the autumn of 1878, after which he was relieved by Colonel W. Loch, A.D.C., who held the post for over 24 years, retiring on 1st January 1903. Mr. H. Sherring, the Head master, officiated as Principal from that date to 3rd March 1903, when Mr. C. W. Waddington, late Principal of the Rajkumar College, Raj-

kot, was appointed Principal.

The College was opened for the reception of boys in October 1875. The first boy to join was the love Mahārāja Mangal Singh of Alwar. and the number of admissions up to August 1903, was 322, of whom 56 are now on the College rolls. The total includes the ruling chiefs of Alwar, Bikāner, Dholpur, Dungarpur, Jhalāwar, Jaisalmer, Karauli, Kōtāh, Manipur, Tehri, Farīd-kōt, and Panna, and the heirsapparent of Bharatpur, Partabgarh, Shahpura, Tonk, Kuch Bihar, and Lunawāra. The greater number come from Rājputāna, but some 20 have been sent from other provinces.

The different boarding houses are supervised by the English staff, and in addition there is a native resident guardian in each house. There is accommodation in all for about 100 boys, with stabling for about 150 horses. Riding is not compulsory, but the majority of boys

keep one or two horses.

The College curriculum is not fettered by having to conform to any prescribed code, but if desired, students are prepared for the Entrance examination of the Allahabad University. The teaching of Sanskrit and Persian is provided for, when a satisfactory test in the vernacular has been passed. With a view to making the course of studies as useful and practical as possible, instruction is also given in law, political economy, agriculture, veterinary science, physics and chemistry.

To the south of the Jaipur house is the College temple, built from subscriptions of Rs. 4,000 raised from among the boys, and a donation of Rs. 5,000, given by Mahant Dewa Dās of the Kāyasthās of Ajmer. All Hindu boys attend service at the Temple on Sundays, and sermons and general instructions are also given there by a Shāstri. The religious training of the Muhammadan boys is attended to by a Hāfiz attached to the Tonk boarding house.

The boys undergo a thorough course of physical training in riding, gymnastics, dumb-bells, Indian clubs, drill, target practice and athletic sports, to one or other of which an hour is devoted every morning. Cricket, foot-ball, hockey, lawn-tennis and racquets are played in the

afternoons and evenings.

In February 1902, a conference was held at Calcutta under the presidency of H. E. Lord Curzon, to discuss the question of increasing the efficiency of the Chiefs' Colleges in India. As a result of this the number of the English staff has been raised from 2 to 4, viz., 1 Principal, 1 Vice-Principal, and 2 Assistants. The Native staff has also been strengthened and improved and other reforms initiated.

In continuation of the same movement a conference of Chiefs was held at Ajmer in March 1904, under the Agent to the Governor-General in Rājputāna, and agreeing with its resolutions the Government of India have since reconstituted the Council of the Mayo College as follows:-There is a General Council, of which His Excellency the Viceroy is President and the Agent to the Governor-General in Rajputāna is Vice-President, composed of (1) all Chiefs who are now members, (2) such Chiefs from places other than the Bombay Presidency, the Punjab and the North-West Frontier Province as may be nominated by the Viceroy, after qualifying for membership by contributing Rs. 10,000 or more to the Mayo or Daly College, and by sending a son or ward to the former, (3) the Agent to the Governor-General in Central India, (4) the Principal of the Mayo College, (5) the Commissioner of Ajmer, (6) three Political Officers each from Rājputāna and Central India, nominated by their respective Agents to the Governor-General, and (7) such other members as the Viceroy may see fit to nominate.

There is also a Working Committee consisting of (1) not more than ten Ruling Chiefs elected by ballot from members of the General Council, (2) the Commissioner of Ajmer, and (3) one Political Officer from Central India. The members serve for two years and are eligible for re-election. Subject to the general control of the Vice-President and of the Committee, the ordinary business of the College is con-

ducted by the Principal.

Press and Newspapers. There is no indigenous literary class, nor was there any printing press in Ajmer till 1871, when a native gentleman from the Panjāb established one. From this press the Rājputāna Official Gazette issued in triglot form—English, Hindi, and Urdu, and the publisher was allowed to publish a supplement, which was an ordinary newspaper. The Rājputāna Official Gazette ceased to exist in 1880.

In 1891 the number of printing presses from which periodicals issued rose to thirteen. Two of these, the "Rājputāna Gazette" and the "Rājasthān Samāchār" were ordinary newspapers, one, the "Veda Bhashya," was a Vedic commentary in the form of a monthly magazine, while the others were periodicals relating to either social or religious reform.

In 1902 there were 12 printing presses in Ajmer and one in Beāwar. The number of periodicals fell to eight, of which five relate to social and religious reform.

The two newspapers above mentioned still continue, and one, the "Muin-ul-Hind," has been added. All these papers are in the vernacular of the district, one religious periodical only, the "Arya," having an English duplicate. Their circulation is purely local and very limited, and their influence corresponds with these conditions.

The registered publications in the province are for the most part merely pamphlets, frequently on religious subjects, and do not deserve detailed discussion. Eleven such pamphlets, amounting to 14,800 copies were registered in 1901, but seven of them were merely new editions of previous works.

CHAPTER XXI.

MEDICAL.

Since 1881 there has been no increase in the number of civil hospi- Hospitals and tals and dispensaries in Ajmer-Merwara. There are seven situated at Ajmer, Kekri, Pisangan, Deolia, Ramsar, Beawar and Todgarh. The first charitable public dispensary in the districts was, by the initiation of Colonel Dixon, opened in Ajmer on the 15th January 1851. It was constructed within the city, near the Agra gate, at a cost of Rs. 6,000, subscribed by the inhabitants. It had accommodation for 25 beds, 21 for males and 4 for females. For many years this dispensary did admirable service in giving medical and surgical aid to the inhabitants not only of Ajmer but of other parts of Rajputana. But after a time it became unable to meet the demands for increased in-door accommodation, for operations and for general hospital work, and in 1895 a larger "General Hospital" was built outside the city walls at a cost of Rs. 43,250. The sum was raised partly by subscriptions from wealthy citizens and from the municipality, and partly by sale of the old dispensary. The new hospital is a handsome building containing several large wards. It has accommodation for 55 in-door patients, 33 males and 10 females, and 12 beds were till recently allotted for men of the Ajmer police. They are now to be accommodated in a ward separate from the hospital. When the new hospital was opened, the old police hospital in the magazine was done away with, in consideration of which Government contributed to-wards the cost of the buildings. The dispensaries at Kekri, Pisangan, Rāmsar and Beāwar were all opened in 1869, the one at Todgarh in 1880, and the Deolia dispensary in 1890. There was a dispensary at Masūda between the years 1869 and 1890, but it was closed shortly after the Deolia one was opened.

In 1881 the a erage daily attendance of in-door and out-door patients was in round numbers 28 and 231 respectively. In 1891 there was a slight rise in the average of out-door patients, the figures being 27 and 281. In 1902 the daily average of both classes of patients had increased largely, that of the in-door patients being 49 and of the out-door 414. The figures show that medical work is

steadily extending.

The civil hospital and the dispensaries are maintained by contributions from Government, from municipal and local funds, and from private subscriptions. Both income and expenditure have risen of late years. On the side of income, that from Government payments has increased from Rs. 3,869 in 1881 to Rs. 4,990 in 1891, and to Rs. 6,353 in 1902; that from municipal and local funds has

dispensaries.

Medical sta tistics.

Finances.

134 MEDICAL.

risen from Rs. 900 in 1881 to Rs. 1,435 in 1891, and to Rs. 2,475 in 1902; from other sources the income in 1902 was Rs. 5,803, as against Rs. 2,796 in 1891 and Rs. 2,616 in 1881. Expenditure on establishments has risen from Rs. 4,197 in 1881 to Rs. 6,426 in 1902, and that upon medicines, diet, etc., from Rs. 3,549 to Rs. 6,320 within the same period.

The excellent medical work done by the United Free Church of Scotland Mission at its Ajmer and Nasīrābād dispensaries has al-

ready been noticed.

Diseases.

Although, with the exception of the miasmatic fevers after the rains, there are no diseases which can be called endemic, there is always a wide field for medical assistance. Diseases of the skin of every variety are common among the poorer classes, favus being a parasitic skin disease often met with, while ophthalmia and allied eye diseases are common. Many children are carried off every year by measles,

owing to the general ignorance as to suitable treatment.

The hospital and dispensaries are generally popular with the common people, but the well-to-do banias in towns still show some reluctance in availing themselves of the Western methods of treatment, and the number of baids and hakims as well as of quacks of every description is not inconsiderable. Shops are common in Ajmer, where country drugs in crude or prepared forms are obtainable. In diseases requiring surgical interference, however, the dispensaries are more frequently resorted to, though jarrahs (native barber surgeons) and sattias (a class of quack surgeons who undertake the cure of eye diseases) are not rare.

In surgical practice, operations for cataract and for the removal of stone from the bladder, a not infrequent complaint among children,

The villagers have great faith in the efficacy of quinine for driving away fevers, and frequently resort to the dispensaries for the yellow chinchona febrifuge, or the Government pink pills. The pice packet system has not been a success, owing probably to the fact that they are sold at Post Offices. In 1894 only two packets were sold and in 1901 only six. The people prefer to go to the dispensaries. The men of the 44th Merwara Infantry, when they return to their homes, help to enlighten the rural population as to the efficacy of dispensary treatment.

Lunatic asylum.

Vaccination.

There is no separate lunatic asylum for the province. Such lunatics as appear to require restraint are received temporarily in the Ajmer jail, and cases requiring prolonged treatment are sent to the lunatic asylum at Lahore. Their average daily attendance number is insignificant, being 50 in 1881 and 1.01 in 1902.

Vaccination was started in Ajmer-Merwāra by Dr. Lord, the Civil Surgeon, in 1853. At first only two vaccinators were employed, and the operations were performed at the dispensary. In 1866 house-tohouse vaccination was started, and in 1867 a native Superintendent was appointed, with four vaccinators paid by Government and two paid by the municipalities of Ajmer and Beāwar.

MEDICAL. 135

Vaccination increased steadily, and in 1886-87 the number of vaccinators was raised from six to eleven; it now stands at fourteen. The Vaccination Act was introduced within the limits of the Ajmer, Kekri and Beawar municipalities from the 1st October 1895, 1st October 1901, and 1st January 1902 respectively, and vaccination is

now compulsory in these places

It is carried out among all classes of the people in the districts, and vaccinators of good castes are employed. The total number of persons successfully vaccinated was 4,433 in 1881, 12,226 in 1891 and 12,179 in 1902, or per 1,000 of population 9.62, 22.54, and 25.54 respectively. The total cost of the department was Rs. 839 in 1881, Rs. 1,549 in 1891. and Rs. 2,267 in 1902. The cost of each successful case in these years came to 3 annas, 1 anna 11 pies, and 3 annas respectively.

The good results of vaccination are seen in a steady decrease of the blind in the last 20 years.

The general sanitation in the towns will compare not unfavourably with that of towns in other provinces. In certain villages simple rules have been brought into force and have worked smoothly.

Sanitation.

CHAPTER XXII.

SURVEYS.

Trigonometrical Survey of 1847-48. A trigonometrical survey of Ajmer-Merwāra was made in 1847-48, the area of the two districts being given as 2,059 and 602.5 square miles respectively. They were divided into 19 parganās and 591 villages. An index map was prepared on the scale of 4 miles to an inch; the pargana map scale was 1 mile to an inch; that of the village maps varied from 20 to 80 chains to an inch. Subsequent to the completion of these survey operations, Colonel Dixon carried out the first regular settlement of the two districts. Under it two separate standards of measurement were used in Ajmer and Merwāra, the bigha in the former measuring 1,936 square yards, and in the latter 1,764 square yards.

Topographical Survey of 1868-1875.

When the term of Colonel Dixon's settlement was approaching completion, a topographical survey of the district was commenced in 1868. It was finished in 1875, and showed the areas of Ajmer and Merwara as 2069'816 square miles and 640'864 square miles respectively. It was followed by the settlement of the districts by Mr. LaTouche in 1875. During the survey there was the first attempt to initiate the patwaris into survey work. Two special patwāri instructors were appointed and were fairly successful. Out of a total of 792,413 acres surveyed, the patwārīs measured 400,506 acres, or rather more than one-half. The survey was carried out by means of the plane table, and to each 4 or 5 measuring parties a munsarim was appointed to test the measurements and entries. These were again noted by superior officers. The outside boundary of the village was in all cases laid down and thoroughly tested by diagonal lines before the field survey was commenced. In the preparation of village maps a scale of 20 inches to the mile was adopted. The whole district, including Merwara, was on this occasion measured by the standard of the Ajmer bigha of 1,936 square yards.

Survey of 1884-85.

As the expiry of this decennial settlement was approaching, Mr. Whiteway was in January 1883 deputed for its revision. Instruction in survey work was given to the patwārīs, and a select few were sent to Rurki for special training to act as instructors to the rest after their return. The work of bringing the old maps up to date was then begun, but was soon found to be impracticable. The boundaries were often incorrect, and no attempt had been made by the patwāris to keep the maps up to date. A boundary and traverse survey was therefore determined on, and was carried out by the professional agency of the Survey Department. The same causes which had so soon rendered obsolete the maps of former measurements, prevented the introduction of a professional cadastral survey. The problem was to get the skeleton of the village drawn by trained surveyors in such a

SURVEYS. 137

way that the fiesh and bones of the field survey could be added by the pctwāri staff. To carry out this, the Survey Department mapped the boundaries of each village, and laid down a number of points so fixed by marks in the ground that the patients could always utilize them in measuring cultivation. One such map of each village was prepared, on a scale of 16 inches to the mile. The Survey Department worked with the theodolite only, and not with the plane table and chain. This method, though well suited to taking up fixed points, can only with great difficulty be applied to taking up a boundary. As a result, when the map was received by the settlement officials the boundaries of almost every village were found to be incorrect and had to be gone over again. When finally corrected, the work of filling in the fields in the maps was undertaken by the patwaris, each of whom was supplied with a plane table, chain, compasses, a scale and a cross staff. This work was subjected to continual and rigorous tests, and nothing but pencil entries were allowed until the final check had taken place. No survey of unculturable ground and topographical features, beyond roads, railways and streams, was attempted. Unlike previous surveys, which had been confined to khālsa and jāgīr areas, this one was extended to six minor istimurāri villages as well. The total area surveyed was 734,578 acres. It was completed in 1886. The patwari staff, which had been described as quite ignorant by Mr. Risdale in 1868, was warmly praised by the last settlement officer as an exceptionally able class of men showing a great aptitude for

It is well if this continues to be so, for the maintenance of the results of the survey lies in their hands. Under section 106 of the Ajmer Land Revenue Regulation II of 1877, rules have been framed by which patwārīs are bound to inspect all traverse survey and boundary marks within the limits of the village and report as to their condition. At the time of each girdāwari, the patwāri prepares slips of changes that have taken place during the preceding six months and the village maps are amended accordingly. They also maintain registers relating to the record of rights in prescribed forms, and must keep them up to date by periodical entries.

Out of 193 patwārīs and naib patwārīs in Ajmer-Merwāra, 150 have either passed the local patwārīs' examination held twice a year, or have been exempted. The examination requires an elementary knowledge of survey work. There is a patwārī class in Ajmer for the instruction of such as have not yet passed the test, and such patwārīs as can be spared from each tahsīl are sent to attend it.

A set of forest maps was prepared in 1884-85 by the Revenue Survey Department on a scale of 4 inches to a mile, but as they were merely skeletons, showing only the boundaries of the forests and of the village lands included in them, a fresh survey of the tracts, showing the topographical details was commenced in 1898, under a surveyor of the Forest Survey Department. The scale of the maps is the same as before. The work is not yet completed.

Survey training of Patwārīs.

> If orest Survey.

BIBLIOGRAPHY

Rājputāna Gazetteer, 1879, Volume II.
District Gazetteer of Ajmer-Merwāra, 1875.
Mr. (now Sir James) LaTouche's Settlement Report, 1875.
Tod's "Rājasthān," 1829 (frequently re-published).
Dixon's "Sketch of Merwāra," 1848.
King G. "Flora of Rājputāna."

Article on the Arts and Manufactures of Ajmer by Colonel Hendley, I.M.S., in Volume III of the Journal of Indian Art.

Census Reports of Ajmer-Merwāra for 1881, 1891 and 1901.

Talboys Wheeler's History of India gives a good account of the Mughal court at Ajmer at the time of Sir Thomas Roe's visit, and the $Ain-i-Akbar\bar{\imath}$ describes Akbar's pilgrimages there.

INDEX.

	A	١.		Page.					PAGE.
Abhay Singh				10	Databa Ct 1				20
Abi, cultivatio			59 10	12 °	Bakht Singh	• • •	•••	•••	20
Abkāri				3, 105, 106 109	Balād Balāi casto	•••	•••	•••	50, 116
Administration		•••	•••	78	Banās river	•••	•••	•••	33, 55
Aen	'		•••	84	Bānchh	•••	••	•••	2, 3
4	• • •	•••	•••	13	Båndanwāra	•••	•••	•••	101
1 1 .	•••		•••	26	Banjārās	•••	•••	•••	81, 82, 92
1	••·	•••	•••	-9	Bânta rent	•••	•	•••	27, 32, 34 54
	••·		•••	43.53	Bāpota .		•••	••	88
Agricultural in			•••	45	Bāpu Sindhia	•••		•••	13, 84
Agricultural st		•	•••		Bārādaris		• • •	•••	13, 34
Agriculturalist				47, 72, 81	Bārāni	••	•••	7 44	, 46, 97, 106
11	•••	•••	•••	40	Barār	•••		,, 11	14,31
A1. D-1-			•••	1, 9	Batār elan			•••	30, 31
Ajaipāl vide A				9	Barāt		•••		24
Ajit Singh	•••			20		•••	•••	•••	32,79
Ajmer city 17-	18, 36				Barley			•••	46
				2, 125, 133	Bur (pass)			•	2
Ajmer district				21, 60, 84	Basant Panch	mi	•	•••	24
- Ajmer municip				4, 116, 135	Bawan Rājā		•••	•••	27
				79, 81, 82,	Beāwar tahsii	29.			. 82. 87. 102
•			. , , , , ,	87, 102	,, town		16, 22,	25, 3.	, 47, 49, 55,
Akbar			10,	11, 17, 28	,.		56	. 58. 6:	2, 64, 67, 69,
Allahji				35					119, 125, 133
Alla-ud-din			•••	32	,, mune	apal	ity 23	. 114-1	15, 116, 135
Amir Khān	• • •			13, 118	Bernier M.	٠.,			11
Amrit				18, 19	' Bhāslān parga				29, 79
Ana	•••			9, 50	Bhairunji				35
Anāsāgar			• •	3, 50, 114	Bhāng		••	•••	109
A 1 1				9	Bhangi	***		•••	33
4 7 1				30, 31	Bhāt				91
Animals, wild.				6	Bhattu			•••	19
Anup				30, 31	' Bhet Bāi Sāh	iba			84
Arāvalli	•••			1, 2, 1, 43	Bhil				33
Arjanpura, (Kl	hālsa a	ınd		27, 28	Bhīm Tītrī	• • •	•••	•••	112
Army			••.	118.122	Bhinai		•••	20, 81	, 82, 91, 127
Arrhāi din kā	Jhonp	rā	•••	17	Bhrigu Rishi	• • •			19
Arya	•••		•••	132	Bhūm	:	26, 27, 2	8, 29, 8	84, 92-94, 96
Arya Samāj	• • •	•••	• • •	31, 35	, Bhūmiās	٠			28, 84, 92, 93
Ashāpura	•••	•••	••	36	Bigha		•••	•••	53, 136
As <essment <math="">+9</essment>			ater-	103	¦ Bijai Singh		• • •		12
Fixed and v	ariable	:—	•••	95 - 106	Bir tank		•••		116
Atitmand	•••	•••		62	Birjāl		•••		. 2
Atmateswara	•••	••	•••	20	Births and D				23
Aurangzeb	•••			11, 20	Bisaldeo Chai	ılıñı	ı	•••	50
		3.			Bisla Tank	••	•••	•••	3, 9, 50, 114
	•	٠,			Biswähdär	• • •	• • • •		88, 89
Bābar Empero	ľ	•••		30	Biswähdäri		•••	•••	88
Bachrāj R ājā	••	•••	***	27	Bithaldās	٠.		•••	28
Badri Narāya	1	•••	•••	20	Bohar Rao				32
Bādsha	•••	•••		40	Bohr is		•••	•••	98
T)	•••			3, 20, 79	Botany	• • •		•••	5, 6
Bagri		•••		14	Brāhma	•••		•••	18, 20, 34
Bahādur Khān	ni	•••	•••	31	Brāhman				25, 26, 27
Baids	•••			134	Brooke, Capt		•••		16, 101, 102
Bājra	•••		••	38, 46, 56	Budha Pushl				117
•					•				• •

ii. INDEX.

Page.	Page.
C	Dhanrāj Singhi 12
Compil Tientement 100	
Castes, Tribes and Races 26-34	Distance
Cattle 49	Dhimra 53 Dhobis 33
Cavendish Mr 85,91,96,97	Dholis 33, 56
Census 21	Dhoti 31, 38, 63, 64
Cesses 79, 84, 85, 104	Dilwāra tank 43, 50
Chāhi-well land 44, 45, 97, 106	Diseases 23, 134
Chamārs 33	Dispensaries 36, 133
Chambal river 2	Disposal of the dead 39
Chang pargana 13, 29, 79	District Board 112
Chärans 91	Divorce 25
Charas-bucket 53	Dixon, Colonel 4, 16, 35, 50, 51, 70
Charas-drug 109	89, 92, 94, 99, 100, 101, 102, 103, 116,
Charlie 3	120, 133, 136
Changastia Rashmana 9, 27	Dress 38-39
Chhanayātis Brāhmans 26 Chillies 47	Dufferin H. E. Earl of— 130
CI : Ci -1. CI	Dwellings 38
Chitas 27, 28, 30, 31	E.
Chitori coin 15	Earthquakes 8
Christians 27, 34	Edmonstone, Mr. 89, 97, 98, 99, 100
Chopad 39	Education 25, 126-132
Circles-revenue sub-divisions, 79	Emigration 22
Climate 6	Epidemic Disease Act 81
Coryat Thomas 11	Exciso 108-110
Cotton 46—Mills 64—Presses, 64	,, Act 81
Courts 81-82	Exports 65
Crime 81-82	Exproprietary tenants 54
Crops 46-47	F.
Currency 15, 85	T71!
Curzon H. E. Lord 131	Fairs 40
Curzon H. E. Lord 131 Customs 84-86	Fallows 46
Curzon H. E. Lord 131	Fallows 46 Famines 70-77
Curzon H. E. Lord 131 Customs 84-86	Fallows 46 Famines 70-77 Fatchgarh 92
Curzon H. E. Lord 131 Customs 84-86 D.	Fallows 46 Famines 70-77 Fatehgarh 92 Fātiha 41 Fauj khareh 28,84
Curzon H. E. Lord 131 Customs 84-86 D. Dāi Nadi 2, 3 Dānta 116, 118 Dāra 11	Fallows 46 Famines 70-77 Fatehgarh 92 Fātiha 41 Fauj kharch 28, 84 Festivals 24, 40-41
Curzon H. E. Lord 131 Customs 84-86 D. Dai Nadi 2, 3 Dânta 116, 118 Dâra 11 Dargāh Khwāja Sāhib 17, 25, 40, 64, 76, 77	Fallows 46 Famines 70-77 92
Curzon H. E. Lord 131 Customs 84-86 D. Dāi Nadi 2, 3 Dānta 116, 118 Dāra 11 Dargāh Khwāja Sāhib 17, 25, 40, 64, 76, 77 Darogās 33	Fallows 46 Famines 70-77 Fatchgarh 92 Fātiha
Curzon H. E. Lord 84-86 D. Dāi Nadi	Fallows 70-77 Fatchgarh
Curzon H. E. Lord	Fallows <
Curzon H. E. Lord	Fallows
Curzon H. E. Lord 131 Customs 84-86 D. Dai Nadi 2, 3 Dānta 116, 118 Dāra 11 Dargāh Khwāja Sāhib 17, 25, 40, 64, 76, 77 Darogās 33 Dārogās 77 Dār ul-Khair 11 Darzis 33 Dasahra 40	Fallows <
Curzon H. E. Lord 131 Customs 84-86 D. Dai Nadi 116,118 Dāra 11 Dargāh Khwāja Sāhib 17,25,40,64,76,77 Darogās 33 Dārogās 77 Dār-ul-Khair 11 Darsis 33 Dasahra 40 Daulat Bāgh 40	Fallows <
Curzon H. E. Lord	Fallows
Curzon H. E. Lord 84-86 D. Dāi Nadi <td>Fallows</td>	Fallows
Curzon H. E. Lord	Fallows
Curzon H. E. Lord </td <td>Fallows</td>	Fallows
Curzon H. E. Lord	Fallows

INDEX.

				PAGE.			
01.1-				50	Toins		
Girdāwar	•••	•••	•••	79	T . !		
Cirdāwar	***	••	•••	137	2 - 2 -		
Goella	•••	•••	•••	20	~		••
Gokul Parak Gola	•••	••	••	27	Y =1 . 31	• • •	
Goma Rão	•••	•••	•••	20	~ -1		
Gopāl Singh	•••	•••	• • •	28	→ .	24	
Goramji	•••		•••	2, 35, 44	Jawāja-village	and ta	n
Gora	•••		•••	31	Jethäna	•••	••
Gorāts	•••	•••	•••	30, 31	Jhāk pargana		••
Gor Rājputs	•••	•••	•••	27	Jharoka	•••	••
Got		•••	24,	29, 31, 32	÷		••
Government C	ollege	•••	116,	, 126, 127			••
Govind Rão	• •	•••	•••	12	o oan pa-		•• •
Grās	•••	•••	00.04	91			••
Gūjars	•••	•••		27, 29, 33 56	Judges	•••	••
Gur	•••	•••	***	30	T Y		
					o uma		•••
	1	H.				M	C .
				0.0	771		
Hadis	•••	•••	•••	36	Kābra .	•	••
Hakīms	•••	•••	•••	77, 134	Kāchbali pass		•••
Hall, Colonel		•••	••	15, 16, 94	Kachhwāha	•••	•••
Halsara	•••	••	•••	44,45	Kādhera Kahārs	•••	•••
Hammām	•••	•••	•••	10	Kāir	•••	
Hari Kāj Harrāj	•••	•••	•••	30, 31	Kaldār	•••	•••
Hatāi	•••	•••	•••	39	Kālinjar		
Hāthun	•••	•••	•••	14, 30	Kankar		•••
Hindus	•••		••	34	Kanphata Jog	is	•••
Hokrān	•••	•••	***	19	Kānākhera		•••
Holi	•••	•••		40,56	Kānūngoes	•••	•••
Hospitals			•••	133, 134	Karāntia	•••	•••
Humāyūn	•••	•••	• • •	18, 28	Karel	•••	•••
					Katha	•••	•••
		I.			Kāthāts Kāyasthās	•••	•••
Id-festivals		•••		40	Keronj		
Imports	•••	•••	•••	65	Kekri town an		
Income Tax		•••	•••	87, 111	69, 78, 80	, 81, 82	, 1(
Indebtedness			•••	48	Keshav Rai		•••
Indra	•••		•••	18	Keybānia	•••	•••
Indrakōt	•••	•••	• • •	9	Khādims		
Indrāni	•••	•••	• • •	18	Khālsa	1, 1	3,2
Inheritance	•••	•••	•••	25		84,8	59,
Interest	• - •	•••	•••	48	TZ1, =		
Irrigation	***	FO. 0		4,50-53	Khām Khāni Nodi	• •	•••
Istimrār	28	, 78. 8	14,88,91	, 93, 94, 96	Khāri Nadi Kharif	7,	8 4
Istimrārdārs	21 22	27, 26	o, ao, ae, ao ao ao	57, 72, 79, , 93, 94, 98	Khain	1,	0, 1
Istimrāri	1 6	93.5	26, 27, 31	, 50, 54, 66	Khārols		
12011111011	1, 0	, 20, 2	73.84.8	5, 124, 137	Kharwa	••	
			,	,,	Khem Chand		•••
		J.			Khewat	•••	
					Khwāja Sāhil	o	•••
Jāgīr	1,	26, 23	7, 28, 30,	31, 34, 50,	Kir	•••	
76,	88, 90	, 91,	92, 93, 9	6, 124, 137	Kishangarh	D = 1 4	•••
Jāgirdārs		•••	28, 88	, 92, 93, 94	Kishen Singh	Kähte	or
Jāgri	•••	•••	•••	65, 66	Kot	•••	•••
Jahāngīr		•••	•••	11, 20		iloro	•••
Jai Appa, Si	ndhia	•••	10 0	12 33. 124. 195		nage	•••
Jails			10. 7	10. 124. 175	Kinesi		

iv. INDEX.

		•••			
	Page.	i			Page.
Kōtri		3.4-			
Krighny Cotton Mills	91	Māpa tax	•••	***	85
Kāl-no	55, 64	Marāthās	•••	12, 58,	60, 84, 85, 90
Kumbhu Dānā of Mouran	30 10	Masāla		***	
Kumhārs	33	Masūda Māta	•••	•••	
Kūnta	54	Mata Material cond	ition o	filono	34,35
Kutb-ud-dīn Eibak	10	ple		_	
Kutka	$\tilde{40}$	Mauzāhwār	•••	8	57 8, 89, 98, 101
		Mayo College		1	16, 130—132
		Mayo Lord	•••	***	17, 121, 130
L.	ļ	Medical	•••		133—135
7-1	- 1	Mera	***		. 30
Lädpura	116	Mers 10, 24,	25, 27,	29, 33, 34	, 63, 119, 121
Laget	31	Merats	•••		
Lakes Lakshmi	50	Merta _	•••		12
	18	Meru	***		. 1
	0, 104	Merwāra Dist		1, 4, 13~	17, 21, 58, 61
Land Revenue 1, 87, 94	72,81	Merwāra Bati		16, 99, 1	19—122, 123
Langar Khāna	76	Merwāra elan		•••	29-34
Language	26	Meteorology Middleton, M		•••	6
Latāi	54	7.// 2		***	95, 96
LaTouch, Mr. (now Sir James) 51, 109	2, 104.	Military	•••	•••	29
	, 136.	Minās		•••	118—122 30, 33
Lawrence, Major-Gen. Sir G.	·	Mines and Mi	nerals		60—62
St. Patrick	121	Mirās	•••	***	88
Lawrence Sir Henry	100	Missions	•••		36-37
Legislation	81	Mohalla	•••		40
Literature	132	Moharram	•••		40
Lloyd, Major	102	Money-lenders	3.m.		48
Loch, Col., W., A.D.C Lohārs	131	Mortgage	•••	161	48
Land Dr	$\begin{vmatrix} 33 \\ 134 \end{vmatrix}$	Motamids			130
Loting	79	Moti Rāwats	•••	••• •••	32
Tollow williams		Mughal Muhammadans			0, 11, 27, 33
Lunatic Asylums	134	Muhammad G	S coo Doni asi	Jo Chal	33, 34, 36
*	3, 19	buddīn Mı	iliainme	d Chori	0
Lyall, Sir Alfred	130	Muhammad Sl	าลีโ		11 19
		Muin-ud-dīn-C	Chishti	·· ···	11, 12 17, 40
	1	Mukkīrār	•••		.39
IVI.		Mundkati, (ble	ood mor	ney)	12, 92
		Municipalities			113—115
Magat			•••		136
		Munsiffs	•••		81
Magazina Aiman Faut	32,35 18	Mutiny 1857	•••	•••	13
Mahadeo	34		81		
Mahājans 27, 33, 41, 6			M	•	
Mahfil	41				
Mahmūd, II	10	Nadi Nāla tan	l .		110
Maize 38, 4	6, 56	Maglennel	•••	•••	116 19
Majnun	109	Namahan			2, 9, 19, 43
Makrera	116	Nahar Rão of	Mando	r ,.,	20
Māldeo Rāhtor	10	Nais			33
Mālis 24,2	7, 33 3	Nāib Tahsīldār	•	•••	78, 81, 82
Mālwā 10,71,7 Māmla or Aen		Nallās			7, 44, 51, 52
Mandlän		Names and tit	les .		41
Mangal Singh Maharaia		λ1		•• •••	84
Man Singh Maharaja	30-1-	Mana I-		•• •••	31
Mant, Major, R. E.				96 10 5	34
Manuring	45	ritearrangu .	91 °C	, 30, 42, 5	8, 64, 67, 69
	1		01,0	, too, II	8—119, 125



	7,
Page.	Page.
Nasīrshāh 118	Puri Gosāins 20
===	
Mandada 20	Pushkar 4, 18-20, 43, 44, 67, 79
N=4- (-vide venei-ve)	R.
Marring can and Dannan	Lh.
No	Rabi 7, 8, 45, 46, 54, 70, 74, 97, 98
Nearān embankment 28, 90, 93	D - 1 - 2 - 11
Nearan 28	Rähtors 10, 11, 12, 27, 28, 32, 91
Negiria (Nagar) 2	
Newspapers 132	D. 1
Nikāli 31	D = 2 1 00 (8 E0 E0
Nim 58	Rajosi village 28, 43, 78, 79
Niyoga 24	
Noble, Mr 130	Rāj Singh $25-29$, 37
North Western Provinces,	Rāi Singh Mahārāna of Udainur 71
Government 78	Rāj Singh Mahārāna of Udaipur 71 Rāmdeoji 35, 39
Nūr Chashma 10,18	1) = T\ T\
_	Ram Deo Frantar 50 Ramgarh 14
Ο.	Rām Singh 12
Occupations 37	Rāmsar 2, 26, 13, 50, 51, 78,
Ochterlony, Sir David 118	
Octroi 113—115	Rão 40
Oil-seeds or Til 46	Rawānās 85
Opium 108	Rāwats 29, 31
Onut1a 00 40	Rebāris 27
Oswais 20, 40	Regars 27, 33
P.	Registration 83
- •	Religions 34—36
Pachbhadra 65	Rents 54 -55
Pākheria Ghāt 2	
Panchkāl 71	Revenue (suspension and re-
Panchāyat 15, 16, 24	mission of) 104, 106, 107
Paraband 44	Risdale, Mr 137
Pargānās 26, 28, 29, 30, 32, 43, 45, 79, 86	Rishi 18
Pārsis 34	Rivers 2,3
Pārvati 18, 40	Roads 68
Pätan—Battle of — 12	Roe, Sir Thomas 11
Patels 16, 79, 80, 84, 97, 101, 104	Rohitās 32
	Ryotwār 98
Patel-bāb 84 Pathāns 27,33,34,36	Ryotwāri 89, 101
Patwārīs 16, 23, 79, 97, 101, 102, 104	,,,,,,,,
Patwar fund 104	S.
Phera ceremony 24	
Pilgrims 20,41	Sägarmati river 2, 3, 43
Pindāri war 12	Sakrāni 20
Dīnl; [pass 2, 4]	Sales 48
$Pipli = \begin{cases} pass \dots & \dots & 2, 4 \\ village & \dots & \dots & 67, 69 \end{cases}$	Salīm vide Jahāngīr 11
Pīr 84	Salt 108
Pisāngan 3, 66, 79, 81, 82, 133	Sambhar Lake 3, 12, 65
Pokhri 40	On Sanas
Police 123, 124	Sanad 90
Poor Warren	0
	Sanitation 135
m .a	Sanitation 135
Danier 10	Sanitation 135 Sānsis caste 33 Sanyūsīs 20
Poppy 46	Sanitation 135 Sānsis caste 33 Sanyūsīs 20
Poppy 46 Post Office 68-69 Potlia 53	Sanitation 135 Sānsis caste 33 Sanyūsīs 20 Saraswati river 2, 3, 19
Poppy 46 Post Office 68-69 Potlia 53	Sanitation 135 Sānsis caste 33 Sanyūsīs 20 Sāraswati river 2, 3, 19 Sārgaon 4 Sārsth talvāl 70
Poppy 46 Post Office 68-69 Potlia 53 Powlett, Col 131	Sanitation 135 Sānsis caste 33 Sanyāsīs 20 Sāraswati river 2, 3, 19 Sārgaon 4 Sāroth tahsīl Sarūp ghāt Sarūpa Ghāta—pass 2
Poppy 46 Post Office 68-69 Potlia 53 Powlett, Col Pramar clan 32 Pränhera 66	Sanitation 4
Poppy 46 Post Office 68-69 Potlia 131 Pramer clan 66 Pränhera	Sanitation 135 Sānsis caste 33 Sanyāsīs 20 Saraswati river 2, 3, 19 Sārgaon 4 Sāroth tahsīl 79 Sarūp ghāt 19 Sarūpa Ghāta—pass 2
Poppy 46 Post Office 68-69 Potlia 33 Powlett, Col	Sanitation 135 Sānsis caste 33 Sanyāsīs 20 Saraswati river 2, 3, 19 Sārgaon 4 Sāroth tahsīl 79 Sarūp ghāt 19 Sarūpa Ghāta—pass 2 Sarwār 3 Sarbār 3
Poppy 46 Post Office 68-69 Potlia 53 Powlett, Col 131 Pramar clan 66 Pränhera 66 Presses Printing idem Prices 56-57 Prithvi Rāj 9, 27, 30	Sanitation 135 Sānsis caste Sanyāsīs 20 Saraswati river 2, 3, 19 Sārgaon 4 Sāroth tahsīl 79 Sarūp ghāt 19 Sarūpa Ghāta—pass 2 Sarwār 3 Sathāna 66
Poppy 46 Post Office 68-69 Potlia 53 Powlett, Col. 62 Pramar clan 66 Pranhera	Sanitation

vi.				INDI	EX.
				Page.	Page.
Saunders, Mr.				17	Telis 27,33
Sāvitii	•••	•••		18, 20	Temperature 6
Sawai Singh				13	Tenures SS—94
				79, 81, 82	Thomson, Mr S9
Sayyıd		•••		25, 27, 33	Til 45, 46
Sayyıd Huesai			•••	10	Tirthankers 35, 36
School		• • •	•••	127 -129	Tod, Colonel 9, 14, 18, 90, 92
Sendra	••	•		112	Todgarh tahsil and village 29, 30, 46,
Sesodia Rājpu	• · · ·	• • • •	• • •	27, 28	56, 79, 81, 82, 87, 102, 133.
		•	• •	26, 63	Tonga -Battle of— 12
Seths Settlements	•••		Si (01, 95-106	Toran 21
Shahāb ud-dīn		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			Trade 65-60
Ghori				9, 17	Treaties with Udaipur and
Shāh Alam	••	•••	•••	118	T. 11
		•••		3, 9, 17	
Shah Jahan Shaira		•	•	31	701. 1. w?
Shaiyas Shaleed	•••	••	•	31	f12.
Shāktas Shaktas	•	•••	••	31	
Shaktie		•••	••-		Tughlak 10
	••	•••	1.	3, 14, 30, 79	• •
Shāmlāt	• • • • • • • • • • • • • • • • • • •	. 1.		10 18	υ.
Shame ad din	711.1111	-H		10, 18	12.1
Sheep .		•••		49	Udaipur or Mewar 28, 118
Sheikh-		•••	• • •	33, 36	Undabāri — pies
Sheopura ghat				.2	Urs Dargāh Khawāja Sāhib 40, 67
Sherring, Mr.	ii.	•••	٠.	131	
Shrva	••	•••	I	9, 31, 35, 4)	V.
Shokla estate	•••	•••	•••	66	
Swaji	•••	•••	•••	28	Vaccination 131—133
Sil.lis	•••			34, 35, 119	Vaccination Act 8
Sındhıä-Băpu	••	• • •		13, 84	Varkunth 34
Sitla	•••			35	Vaishnavae 31
Somdia	•••			53	Vaishyña 20
Sowing			••	45	Vārāha 20
Spiers, Major				97	Variable Assessment ride
Simagai				28, 62, 79	Asses 'ment
Stamps			5	7, 110 - 111	Veterm'ry 4!
St. John Col.	Sir Oh	vet		1 1	Victoria Jubilee Clock Tower. 110
Subah			•••	11	Vigranatēja III or Visaldeo .
Subahdats				12, 13, 20	
Sudābāi		•		19	Vital statistics 22-2:
Sugai	•••		• •	65, 66	Volunteers 12:
ougareare	•		•••	46	1
Sunărs				33	w.
Sura Ghatā – 1	1.10-		•	2	٧٧.
		•••		136 137	Waddington Mr C W 191
Surveys	Joseph	•••	•••	130137	Waddington, Mr. C. W 131
Sutherland, C	doner	•••	•••	2.5	Water Revenue 51, 87
	-	-			Water rate 10.
		r.			Wages
n1 1 3 4					Wells 52-5
Tái-ul Masır	•••		***	10	Wheat 38, 47, 50
Tairsils			, 30, 31	, 32, 16, 78,	Whiteway, Mr 104, 130
79, 87, 102	, 105, 1		. 🗕 -		Wilder Mr 14, 85, 9;
Tahsildārs			1, 78, 7	9, 81, 82, 97	Winds
Tamur	•••	• • •	•••	10	Y.
Takayı	•••	•••		75	ļ
Tālabi		11,		97, 103, 106	Yajna of Brahma 18-26
Tanks				50 -51, 103	
Täntia Sindi i	а			84	Z.
				92	1
Tantoti	••				1
		1, 10	, 18, 60), 62, 94, 119	Zahti 90
), 62, 94, 119 109, 112	1 00 11 1-1
Tărăguh					100